



COMAL COUNTY

ENGINEER'S OFFICE

License to Operate On-Site Sewage Treatment and Disposal Facility

Issued This Date: 04/20/2021

Permit Number: 110583

Location Description: 160 BLUEJAY CT
CANYON LAKE, TX 78133

Subdivision: Point at Rancho del Lago
Unit: 2
Lot: 112
Block:
Acreage:

Type of System: Aerobic
Surface Irrigation

Issued to: Rodolfo Gonzalez, Jr. & Crystal Lynn Gonzales

This license is authorization for the owner to operate and maintain a private facility at the location described in accordance to the rules and regulations for on-site sewerage facilities of Comal County, Texas, and the Texas Commission on Environmental Quality.

The license grants permission to operate the facility. It does not guarantee successful operation. It is the responsibility of the owner to maintain and operate the facility in a satisfactory manner.

Alterations to this permit including, but not limited to:

- Increase in the square feet of living area
- Increase in the number of bedrooms
- A change of use (i.e. residential to commercial)
- Relocation of system components (including the relocation of spray heads)
- Installation of landscaping
- Adding new structures to the system

may require a new permit. **It is the responsibility of the owner to apply for a new permit, if applicable.**

Inspection and licensing of a facility indicates only that the facility meets certain minimum requirements. It does not impede any governmental entity in taking the proper steps to prevent or control pollution, to abate nuisance, or to protect the public health.

This license to operate is valid for an indefinite period. The holder may transfer it to a succeeding owner, provided the

Licensing Authority

Comal County Environmental Health


ENVIRONMENTAL HEALTH INSPECTOR

OS0032485


ENVIRONMENTAL HEALTH COORDINATOR

OS0035605

Comal County Environmental Health OSSF Inspection Sheet

Installer Name: SWOYER OSSF Installer #: OS0026238
 1st Inspection Date: 4/9/20 2nd Inspection Date: 4/20/21 3rd Inspection Date: _____
 Inspector Name: CONNOR Inspector Name: Connor Inspector Name: _____
 Permit#: 110538 Address: PT.RANCHO DEL LAGO 160 BLUEJAY CRT.

No.	Description	Answer	Citations	Notes	1st Insp.	2nd Insp.	3rd Insp.
1	SITE AND SOIL CONDITIONS & SETBACK DISTANCES Site and Soil Conditions Consistent with Submitted Planning Materials	X	285.31(a) 285.30(b)(1)(A)(iv) 285.30(b)(1)(A)(v) 285.30(b)(1)(A)(iii) 285.30(b)(1)(A)(ii) 285.30(b)(1)(A)(i)		X		
2	SITE AND SOIL CONDITIONS & SETBACK DISTANCES Setback Distances Meet Minimum Standards	X	285.91(10) 285.30(b)(4) 285.31(d)		X		
3	SEWER PIPE Proper Type Pipe from Structure to Disposal System (Cast Iron, Ductile Iron, Sch. 40, SDR 26)	X	285.32(a)(1)		X		
4	SEWER PIPE Slope from the Sewer to the Tank at least 1/8 Inch Per Foot	X	285.32(a)(3)		X		
5	SEWER PIPE Two Way Sanitary - Type Cleanout Properly Installed (Add. C/O Every 100' &/or 90 degree bends)	X	285.32(a)(5)		X		
6	PRETREATMENT Installed (if required) TCEQ Approved List PRETREATMENT Septic Tank(s) Meet Minimum Requirements		285.32(b)(1)(G)285.32(b)(1)(E)(iii) 285.32(b)(1)(E)(iv) 285.32(b)(1)(F) 285.32(b)(1)(B) 285.32(b)(1)(C)(i) 285.32(b)(1)(C)(ii) 285.32(b)(1)(D) 285.32(b)(1)(E) 285.32(b)(1)(A) 285.32(b)(1)(E)(ii)(II) 285.32(b)(1)(E)(i) 285.32(b)(1)(E)(ii)(I)				
7	PRETREATMENT Grease Interceptors if required for commercial		285.34(d)				

TANK SET. LEVEL. NO LEAKS. OPERATIONAL. COVER. 1ST SPRY AREA, REMOVE

PERSIMMONS.

4/20/21 JC covered.

2ND SPRY AREA, COVER LARGE ROCKS.

3RD SPRY AREA, REMOVE LARGE CEDAR.

**Comal County Environmental Health
OSSF Inspection Sheet**

No.	Description	Answer	Citations	Notes	1st Insp.	2nd Insp.	3rd Insp.
8	SEPTIC TANK Tank(s) Clearly Marked SEPTIC TANK If SingleTank, 2 Compartments Provided with Baffle SEPTIC TANK Inlet Flowline Greater than 3" and " T " Provided on Inlet and Outlet SEPTIC TANK Septic Tank(s) Meet Minimum Requirements		285.32(b)(1)(E) 285.91(2) 285.32(b)(1)(F) 285.32(b)(1)(E)(iii) 285.32(b)(1)(E)(ii)(II) 285.32(b)(1)(E)(ii)(I) 285.32(b)(1)(E)(i) 285.32(b)(1)(D) 285.32(b)(1)(C)(ii) 285.32(b)(1)(C)(i) 285.32(b)(1)(B) 285.32(b)(1)(A) 285.32(b)(1)(E)(iv)				
9	ALL TANKS Installed on 4" Sand Cushion/ Proper Backfill Used	X	285.32(b)(1)(F) 285.32(b)(1)(G) 285.34(b)		X		
10	SEPTIC TANK Inspection / Clean Out Port & Risers Provided on Tanks Buried Greater than 12" Sealed and Capped		285.38(d)				
11	SEPTIC TANK Secondary restraint system provided SEPTIC TANK Riser permanently fastened to lid or cast into tank SEPTIC TANK Riser cap protected against unauthorized intrusions		285.38(d) 285.38(e)				
12	SEPTIC TANK Tank Volume Installed						
13	PUMP TANK Volume Installed						
14	AEROBIC TREATMENT UNIT Size Installed	X			X		
15	AEROBIC TREATMENT UNIT Manufacturer AEROBIC TREATMENT UNIT Model Number	X X		MAXX AIR M600	X X		
16	DISPOSAL SYSTEM Absorptive		285.33(a)(4) 285.33(a)(1) 285.33(a)(2) 285.33(a)(3)				
17	DISPOSAL SYSTEM Leaching Chamber		285.33(a)(1) 285.33(a)(3) 285.33(a)(4) 285.33(a)(2)				
18	DISPOSAL SYSTEM Evapo-transpirative		285.33(a)(3) 285.33(a)(4) 285.33(a)(1) 285.33(a)(2)				

**Comal County Environmental Health
OSSF Inspection Sheet**

No.	Description	Answer	Citations	Notes	1st Insp.	2nd Insp.	3rd Insp.
19	DISPOSAL SYSTEM Drip Irrigation		285.33(c)(3)(A)-(F)				
20	DISPOSAL SYSTEM Soil Substitution		285.33(d)(4)				
21	DISPOSAL SYSTEM Pumped Effluent		285.33(a)(3) 285.33(a)(1) 285.33(a)(2)				
22	DISPOSAL SYSTEM Gravelless Pipe		285.33(a)(3) 285.33(a)(2) 285.33(a)(4) 285.33(a)(1)				
23	DISPOSAL SYSTEM Mound		285.33(a)(3) 285.33(a)(1) 285.33(a)(2) 285.33(a)(4)				
24	DISPOSAL SYSTEM Other (describe) (Approved Design)	X	285.33(d)(6) 285.33(c)(4)	AEROBIC SPRAY	X		
25	DRAINFIELD Absorptive Drainline 3" PVC or 4" PVC						
26	DRAINFIELD Area Installed						
27	DRAINFIELD Level to within 1 inch per 25 feet and within 3 inches over entire excavation		285.33(b)(1)(A)(v)				
28	DRAINFIELD Excavation Width DRAINFIELD Excavation Depth DRAINFIELD Excavation Separation DRAINFIELD Depth of Porous Media DRAINFIELD Type of Porous Media						
29	DRAINFIELD Pipe and Gravel - Geotextile Fabric in Place		285.33(b)(1)(E)				
30	DRAINFIELD Leaching Chambers DRAINFIELD Chambers - Open End Plates w/Splash Plate, Inspection Port & Closed End Plates in Place (per manufacturers spec.)		285.33(c)(2)				
31	LOW PRESSURE DISPOSAL SYSTEM Adequate Trench Length & Width, and Adequate Separation Distance between Trenches		285.33(d)(1)(C)(i)				

**Comal County Environmental Health
OSSF Inspection Sheet**

No.	Description	Answer	Citations	Notes	1st Insp.	2nd Insp.	3rd Insp.
32	EFFLUENT DISPOSAL SYSTEM Utilized Only by Single Family Dwelling EFFLUENT DISPOSAL SYSTEM Topographic Slopes < 2.0% EFFLUENT DISPOSAL SYSTEM Adequate Length of Drain Field (1000 Linear ft. for 2 bedrooms or Less & an additional 400 ft. for each additional bedroom) EFFLUENT DISPOSAL SYSTEM Lateral Depth of 18 inches to 3 ft. & Vertical Separation of 1ft on bottom and 2 ft. to restrictive horizon and ground water respectfully EFFLUENT DISPOSAL SYSTEM Lateral Drain Pipe (1.25 - 1.5" dia.) & Pipe Holes (3/16 - 1/4" dia. Hole Size) 5 ft. Apart		285.33(b)(3)(A) 285.33(b)(3)(A) 285.33(b)(3)(B) 285.91(13) 285.33(b)(3)(D) 285.33(b)(3)(F)				
33	AEROBIC TREATMENT UNIT Is Aerobic Unit Installed According to Approved Guidelines.	X	285.32(c)(1)		X		
34	AEROBIC TREATMENT UNIT Inspection/Clean Out Port & Risers Provided AEROBIC TREATMENT UNIT Secondary restraint system provided AEROBIC TREATMENT UNIT Riser permanently fastened to lid or cast into tank AEROBIC TREATMENT UNIT Riser cap protected against unauthorized intrusions	X X X X			X X X X		
35	AEROBIC TREATMENT UNIT Chlorinator Properly Installed with Chlorine Tablets in Place.	X			X		
36	PUMP TANK Is the Pump Tank an approved concrete tank or other acceptable materials & construction PUMP TANK Sampling Port Provided in the Treated Effluent Line PUMP TANK Check Valve and/or Anti- Siphon Device Present When Required PUMP TANK Audible and Visual High Water Alarm Installed on Separate Circuit From Pump						
37	PUMP TANK Inspection/Clean Out Port & Risers Provided PUMP TANK Secondary restraint system provided PUMP TANK Riser permanently fastened to lid or cast into tank PUMP TANK Riser cap protected against unauthorized intrusions						
38	PUMP TANK Secondary restraint system provided						
39	PUMP TANK Electrical Connections in Approved Junction Boxes / Wiring Buried	X			X		

**Comal County Environmental Health
OSSF Inspection Sheet**

No.	Description	Answer	Citations	Notes	1st Insp.	2nd Insp.	3rd Insp.
40	APPLICATION AREA Distribution Pipe, Fitting, Sprinkler Heads & Valve Covers Color Coded Purple?	X	285.33(d)(2)(G)(iii)(II)285.33(d)(2)(G)(iii)(III)285.33(d)(2)(G)(v) 285.33(d)(2)(G)(iii) 285.33(d)(2)(G)(iv) 285.33(d)(2)(G)(i) 285.33(d)(2)(G)(ii) 285.33(d)(2)(G)(iii)(I)		X		
41	APPLICATION AREA Low Angle Nozzles Used / Pressure is as required APPLICATION AREA Acceptable Area, nothing within 10 ft of sprinkler heads? APPLICATION AREA The Landscape Plan is as Designed	X X	285.33(d)(2)(G)(i) 285.33(d)(2)(A) 285.33(d)(2)(F)	SEE NOTES 1ST PG		X	
42	APPLICATION AREA Area Installed	X			X		
43	PUMP TANK Meets Minimum Reserve Capacity Requirements						
44	PUMP TANK Material Type & Manufacturer						
45	PUMP TANK Type/Size of Pump Installed						



COMAL COUNTY

ENGINEER'S OFFICE

Permit of Authorization to Construct an On-Site Sewage Facility Permit Valid For One Year From Date Issued

Permit Number: 110583
Issued This Date: 03/31/2020
This permit is hereby given to: Rodolfo Gonzalez, Jr. & Crystal Lynn Gonzales

To start construction of a private, on-site sewage facility located at:

160 BLUEJAY CT
CANYON LAKE, TX 78133

Subdivision: Point at Rancho del Lago
Unit: 2
Lot: 112
Block:
Acreage:

APPROVED MINIMUM SIZES AS PER ATTACHED DESIGN

Type of System: Aerobic
Surface Irrigation

This permit gives permission for the construction of the above referenced on-site facility to commence. Installation must be completed by an installer holding a valid registration card from the Texas Commission on Environmental Quality (TCEQ). Installation and inspection must comply with current TCEQ and Comal County requirements.

Call (830) 608-2090 to schedule inspections.



COMAL COUNTY
ENGINEER'S OFFICE

**OSSF DEVELOPMENT APPLICATION
CHECKLIST**

Staff will complete shaded items

<i>Date Received</i>	<i>Initials</i>	<i>Permit Number</i>

Instructions:

Place a check mark next to all items that apply. For items that do not apply, place "N/A". This OSSF Development Application Checklist **must** accompany the completed application.

OSSF Permit

RECEIVED

- ☒ Completed Application for Permit for Authorization to Construct an On-Site Sewage Facility and License to Operate
- ☒ Site/Soil Evaluation Completed by a Certified Site Evaluator or a Professional Engineer
- ☒ Planning Materials of the OSSF as Required by the TCEQ Rules for OSSF Chapter 285. Planning Materials shall consist of a scaled design and all system specifications.
- ☒ Required Permit Fee - See Attached Fee Schedule
- ☒ Copy of Recorded Deed
- ☒ Surface Application/Aerobic Treatment System
- ☒ Recorded Certification of OSSF Requiring Maintenance/Affidavit to the Public
- ☒ Signed Maintenance Contract with Effective Date as Issuance of License to Operate

MAR 30 2020

COUNTY ENGINEER

I affirm that I have provided all information required for my OSSF Development Application and that this application constitutes a completed OSSF Development Application.

Signature of Applicant

Date

___ COMPLETE APPLICATION

Check No. _____ Receipt No. _____

___ INCOMPLETE APPLICATION
(Missing Items Circled, Application Refeused)

*** COMAL COUNTY OFFICE OF ENVIRONMENTAL HEALTH ***
APPLICATION FOR PERMIT FOR AUTHORIZATION TO CONSTRUCT AN
ON-SITE SEWAGE FACILITY AND LICENSE TO OPERATE

Date 3/10/2020

Permit # 110583

Owner Name	<u>RODOLFO GONZALEZ, JR. & CRYSTAL LYNN GONZALEZ</u>	Agent Name	<u>GREG W. JOHNSON, P.E.</u>
Mailing Address	<u>C/O 23011 FM 306</u>	Agent Address	<u>170 HOLLOW OAK</u>
City, State, Zip	<u>CANYON LAKE, TEXAS 78133</u>	City, State, Zip	<u>NEW BRAUNFELS, TEXAS 78132</u>
Phone #	<u>830-935-4936</u>	Phone #	<u>830-905-2778</u>
Email	<u>katelyn@paulswoyerseptics.com</u>	Email	<u>gregjohnsonpe@yahoo.com</u>

All correspondence should be sent to: ☐ Owner ☐ Agent ☒ Both Method: ☐ Mail ☒ Email

Subdivision Name POINT AT RANCHO DEL LAGO (PHASE 2) Unit _____ Lot 112 Block _____

Acreage/Legal _____

Street Name/Address 160 BLUEJAY CT City CANYON LAKE Zip 78133

Type of Development:

☒ Single Family Residential

Type of Construction (House, Mobile, RV, Etc.) HOUSE

Number of Bedrooms 3

Indicate Sq Ft of Living Area 1819

☐ Non-Single Family Residential

(Planning materials must show adequate land area for doubling the required land needed for treatment units and disposal area)

Type of Facility _____

Offices, Factories, Churches, Schools, Parks, Etc. - Indicate Number Of Occupants _____

Restaurants, Lounges, Theaters - Indicate Number of Seats _____

Hotel, Motel, Hospital, Nursing Home - Indicate Number of Beds _____

Travel Trailer/RV Parks - Indicate Number of Spaces _____

Miscellaneous _____

Estimated Cost of Construction: \$ 160,000.00 (Structure Only)

Is any portion of the proposed OSSF located in the United States Army Corps of Engineers (USACE) flowage easement?

☐ Yes ☒ No (If yes, owner must provide approval from USACE for proposed OSSF improvements within the USACE flowage easement)

Source of Water ☒ Public ☐ Private Well

Are Water Saving Devices Being Utilized Within the Residence? ☒ Yes ☐ No

By signing this application, I certify that:

- The completed application and all additional information submitted does not contain any false information and does not conceal any material facts. I certify that I am the property owner or I possess the appropriate land rights necessary to make the permitted improvements on said property.
- Authorization is hereby given to the permitting authority and designated agents to enter upon the above described property for the purpose of site/soil evaluation and inspection of private sewage facilities.
- I understand that a permit of authorization to construct will not be issued until the Floodplain Administrator has performed the reviews required by the Comal County Flood Damage Prevention Order.
- I affirmatively consent to the online posting/public release of my e-mail address associated with this permit application, as applicable.

Rodolfo Gonzalez Jr
Signature of Owner

03-10-2020
Date

Page 1 of 2

* * * COMAL COUNTY OFFICE OF ENVIRONMENTAL HEALTH * * *

APPLICATION FOR PERMIT FOR AUTHORIZATION TO CONSTRUCT AN
ON-SITE SEWAGE FACILITY AND LICENSE TO OPERATEPlanning Materials & Site Evaluation as Required Completed By GREG W. JOHNSON, P.E.System Description PROPRIETARY; AEROBIC TREATMENT AND SURFACE IRRIGATION

Size of Septic System Required Based on Planning Materials & Soil Evaluation

Tank Size(s) (Gallons) MAXX AIR M600 Absorption/Application Area (Sq Ft) 4241Gallons Per Day (As Per TCEQ Table III) 240

(Sites generating more than 5000 gallons per day are required to obtain a permit through TCEQ)

RECEIVED

Is the property located over the Edwards Recharge Zone? ☐ Yes ☒ No

(If yes, the planning materials must be completed by a Registered Sanitarian (R.S.) or Professional Engineer (P.E.))

MAR 30 2020

Is there an existing TCEQ approved WPAP for the property? ☐ Yes ☒ No

(if yes, the R. S. or P. E. shall certify that the OSSF design complies with all provisions of the existing WPAP.)

COUNTY ENGINEER

If there is no existing WPAP, does the proposed development activity require a TCEQ approved WPAP? ☐ Yes ☐ No

(If yes, the R.S. or P. E. shall certify that the OSSF design will comply with all provisions of the proposed WPAP. A Permit to Construct will not be issued for the proposed OSSF until the proposed WPAP has been approved by the appropriate regional office.)

Is the property located over the Edwards Contributing Zone? ☒ Yes ☐ NoIs there an existing TCEQ approval CZP for the property? ☐ Yes ☒ No

(if yes, the P.E. or R.S. shall certify that the OSSF design complies with all provisions of the existing CZP)

If there is no existing CZP, does the proposed development activity require a TCEQ approved CZP? ☐ Yes ☒ No

(if yes, the P.E. or R.S. shall certify that the OSSF design will comply with all provisions of the proposed CZP. A Permit to construct will not be issued for the proposed OSSF until the CZP has been approved by the appropriate regional office.)

Is this property within an incorporated city? ☐ Yes ☒ No

If yes, indicate the city: _____



FIRM #2585

By signing this application, I certify that:

- The information provided above is true and correct to the best of my knowledge.
- I affirmatively consent to the online posting/public release of my e-mail address associated with this permit application, as applicable

Signature of Designer

March 25, 2020
Date

195 David Jonas Dr., New Braunfels, Texas 78132-3760 (830) 608-2090 Fax (830) 608-2078

Page 2 of 2
Revised July 2018

AFFIDAVITTHE COUNTY OF COMAL
STATE OF TEXAS**CERTIFICATION OF OSSF REQUIRING MAINTENANCE**

According to Texas Commission on Environmental Quality Rules for On-Site Sewage Facilities (OSSF's), this document is filed in the Deed Records of Comal County, Texas.

I

The Texas Health and Safety Code, Chapter 366 authorizes the Texas Commission on Environmental Quality (TCEQ) to regulate on-site sewage facilities (OSSFs). Additionally, the Texas Water Code (TWC), § 5.012 and § 5.013, gives the commission primary responsibility for implementing the laws of the State of Texas relating to water and adopting rules necessary to carry out its powers and duties under the TWC. The commission, under the authority of the TWC and the Texas Health and Safety code, requires owner's to provide notice to the public that certain types of OSSFs are located on specific pieces of property. To achieve this notice, the commission requires a recorded affidavit. Additionally, the owner must provide proof of the recording to the OSSF permitting authority. This recorded affidavit is not a representation or warranty by the commission of the suitability of this OSSF, nor does it constitute any guarantee by the commission that the appropriate OSSF was installed.

II

An OSSF requiring a maintenance contract, according to 30 Texas Administrative Code §285.91(12) will be installed on the property described as (insert legal description):

2 UNIT/PHASE/SECTION BLOCK 112 LOT THE POINT AT RANCHO DEL LAGO SUBDIVISION

IF NOT IN SUBDIVISION: ACREAGE SURVEY

The property is owned by (insert owner's full name): RODOLFO GONZALEZ, JR. & CRYSTAL LYNN GONZALEZ

This OSSF must be covered by a continuous maintenance contract for the first two years. After the initial two-year service policy, the owner of an aerobic treatment system for a single family residence shall either obtain a maintenance contract within 30 days or maintain the system personally.

Upon sale or transfer of the above-described property, the permit for the OSSF shall be transferred to the buyer or new owner. A copy of the planning materials for the OSSF can be obtained from the Comal County Engineer's Office.

WITNESS BY HAND(S) ON THIS 10th DAY OF MARCH, 2020

X Rodolfo Gonzalez Jr.

RODOLFO GONZALEZ, JR.

X Crystal Lynn Gonzalez

CRYSTAL LYNN GONZALEZ

Owner(s) signature(s)


Owner (s) Printed name (s)

Rodolfo + Crystal Lynn Gonzalez

SWORN TO AND SUBSCRIBED BEFORE ME ON THIS 10th DAY OF

MARCH, 2020

Katelyn Nicole Neumann
Notary Public Signature



(Notary Seal Here)

THIS AREA FOR COMAL COUNTY CLERK RECORDING PURPOSES ONLY

Filed and Recorded
Official Public Records
Bobbie Koepp, County Clerk
Comal County, Texas
03/30/2020 08:41:00 AM
TERRI 1 Pages(s)
202006011868



Bobbie Koepp

RECEIVED

MAR 30 2020

COUNTY ENGINEER



PAUL SWOYER SEPTIC SUPPLY &
SERVICE
23011 FM 306
CANYON LAKE, TX 78133

MP#0001708

CHRISTOPHER RYAN SEIDENSTICKER

PROPERTY LEGAL DESCRIPTION:

POINT AT RANCHO DEL LAGO PHASE 2, LOT 112

Customer: RODOLFO GONZALEZ, JR. & CRYSTAL LYNN GONZALEZ

Site Address: 160 BLUEJAY CT

City/State: CANYON LAKE, TEXAS **Zip:** 78133

County: COMAL **Permit#:**

Phone Number:

E-mail:

I. General: This On-Site Sewage Facility Service Agreement (hereinafter referred to as "Agreement") is entered into by and between RODOLFO GONZALEZ, JR. & CRYSTAL LYNN GONZALEZ (hereinafter referred to as "Client") and PS Supply & Service LLC, (hereinafter referred to as "Contractor"). By this agreement, Contractor agrees to render services, as described herein (the "Services"), and the client agrees to fulfill his/her/their responsibilities under this agreement herein.

RECEIVED

II. Effective Dates: This agreement commences on the date of License to Operate is issued for Three (3) years.

MAR 30 2020

Date of License to Operate: LTO Last Date of Service: 3 yrs from LTO

III. Services by Contractor: Contractor will provide the following Services:

COUNTY ENGINEER

1. Inspect and perform routine maintenance on the On-Site Sewage Facility ("OSSF") in compliance with the code, regulations, and/or rules of the Texas Commission on Environmental Quality ("TCEQ") and county in which the OSSF is located (the "County") and the manufacturer's requirements, at a frequency of approximately once every four (4) months.
2. Report to the appropriate regulatory authority and to Client, as required by the State of Texas' on-site rules and, if required, TCEQ or County rules. All findings must be reported to the appropriate regulatory authority within 14 days.
3. Notify Client and repair any components of the OSSF that are found to be in need of repair during the inspection. If warranty, you just do it. If not, Client will be responsible. Repairs will be made so brought up to compliance and bill forward.
4. Visit site in response to Client's request for unscheduled service within two business days from the date of Contractor's actual receipt of Client's request. Unscheduled service visits are not included in the fee agreement herein and will be billed to the client in addition to fees under this Agreement.
5. Provide notification of arrival to site to the Client or to site personnel. Additionally, Contractor will leave written notification of the visit at the site or with site personnel upon completion of inspection, and forward such notice to the appropriate regulatory authority within fourteen (14) days.

IV. Payment(s): Client shall pay to Contractor included w/ septic, for the Services describe herein (the "Inspection and Routine Maintenance Fee"), excepting those described in Section III (4), or Section IX, herein. The Fee does not include equipment, parts or labor supplied for anything beyond routine inspection and routine maintenance. Payments for such additional services are due at the time services are provided or rendered. Payments not received within thirty (30) days from the due date will be subject the greater of a \$20.00 late penalty or 1.5% carrying charge on the original balance for each month or portion thereof a balance in past due. If for any reason such charges are found to be usurious by a court of competent jurisdiction, such charges shall be reduced to the maximum allowable by law. By signing this contract, Client authorizes Contractor to remove any parts installed, but not paid in full at the end of the thirty (30) days. Client agrees to pay for any labor cost associated with the installation and the reasonable cost of removal of said parts.

Client: R.G. C.G.

Contractor: PS

MAR 30 2020

V. Client's Responsibilities: Client is responsible for each and all of the following:

COUNTY ENGINEER

1. To maintain chlorinator and provide proper chlorine supply, if OSSF is so equipped.
2. To provide all necessary yard or lawn maintenance and removal of obstacles as needed to allow the OSSF to function properly, and to allow Contractor ready access to all parts of the OSSF.
3. To maintain a current license to operate, and abide by the conditions and limitations of that license and all requirements for on-site sewage facilities from the State and local regulatory agency.
4. To maintain the OSSF in accordance with manufacturer's recommendations.
5. To immediately notify Contractor and Agency of any and all problems with, the OSSF, including failure thereof.
6. Upon receipt of any written notification of required services from Contractor, to contact Contractor and authorize the required service. If Client elects a different contractor to perform the required service, Client is responsible for ensuring the substitute contractor holds the proper license (Installer II) and is certified by the manufacturer. Additionally, Client shall be responsible for ensuring proper notification is given to the appropriate regulatory authority, as required by the State and/or local regulatory authority rules.
7. To provide Contractor with water usage records, upon request, for evaluation by Contractor of the OSSF performance.
8. To pay required sampling charges for samples collected for testing (e.g. Biological Oxygen Demand/Total Suspended Solids ("BOD/TSS")) that may be required on the OSSF.
9. To prevent backwash from water treatment or water conditioning equipment to enter the OSSF.
10. To provide, at Client's expense, for pumping of tanks as needed.
11. To maintain site drainage sufficient to prevent adverse effects on the OSSF.
12. To promptly and fully pay Contractor's bills, fees, or invoices as described herein.

VI. Access by Contractor: Client agrees to allow Contractor, or personnel authorized by the Contractor, to enter the property at reasonable times without prior notice for the purpose of performing the Services described herein. Such entry shall include access to the OSSF electrical and physical components, including tanks, by means of manways or risers for the purpose of evaluations required by the manufacturer, and/or regulatory authority rules. If such manways or risers are not in place, Client shall allow and be responsible for payment of required excavation, including labor and materials, necessary to allow access to the OSSF or any required components. Such excavation shall be billed at the rate of \$75.00 per hour for labor, plus materials billed at list price. Contractor shall make only those efforts reasonable under the circumstances to replace excavated soil.

VII. Application or Transfer of Payment: The fees paid for this agreement may transfer to any subsequent owner(s) of the property on which the OSSF is located. The subsequent owner(s) must sign a similar agreement authorizing Contractor to perform the above-described Services, and accepting Client's responsibilities. The replacement Agreement must be signed and received within 30 days of transfer of ownership. Contractor will apply all funds received from Client first to any past due obligations arising from this Agreement including late charges, return check charges, and charges for repairs or services not paid within 30 days of invoicing. The consumption of the payment in this manner may lead to termination of the agreement by Contractor.

VIII. Termination of Agreement: This agreement may be terminated by either party with 30 days written notice. If this agreement is so terminated by Client, Contractor shall be paid at the rate of \$75.00 per hour for any work performed or required, but not yet paid. If terminated by Contractor, all amounts outstanding shall be due within thirty days of termination. The party terminating will immediately notify the other party, the equipment manufacturer, and the regulatory agency of the termination.

IX. Limitation of Liability: In no event shall Contractor be liable for indirect, consequential, incidental or punitive damages, whether in contract, tort, or any other theory of liability. In no event shall the Contractor's liability for direct damages exceed payments by the Client under this Agreement.

X. Severability and Reformation: If any provision in this Agreement shall be held to be invalid or unenforceable for any reason, it shall be reformed to the minimum extent necessary to effect the intent of the Parties. If any provision is such that it cannot reasonably be reformed, it shall be struck from this Agreement and the remaining provisions shall continue to be valid and enforceable.

XI. Performance of Agreement: Commencement of performance by Contractor under this agreement is contingent on the following conditions: (1) Contractor receiving a fully executed original copy of this agreement, (2) Contractor receiving payment in full of the fee(s) described herein. If the above conditions are not met, then Contractor is from any obligation to perform any portion of this agreement.

XII. Modification. This Agreement may not be changed or modified except by an instrument in writing, signed by both Contractor and Client.

XIII. Waiver. Except as otherwise noted in this Agreement, the waiver by other party of a breach of any provision of this Agreement shall not operate or be construed as a continuing waiver or as a consent to or waiver of any subsequent breach hereof.

Client: R.B. C.G.Contractor: KS

MAR 30 2020

XIV. Headings. The Article and Section headings in this Agreement are for the convenience of reference only and do not constitute a part of this Agreement and shall not be deemed to limit or affect any of the provisions hereof.

COUNTY ENGINEER

XV. GOVERNING LAW AND CHOICE OF VENUE. EACH OF THE PARTIES HERETO HEREBY CONSENTS TO THE EXCLUSIVE JURISDICTION OF THE COURTS OF THE STATE OF TEXAS, COUNTY OF COMAL, AND TO THE UNITED STATES DISTRICT COURT FOR THE WESTERN DISTRICT OF TEXAS – SAN ANTONIO DIVISION, AS WELL AS TO THE JURISDICTION OF ALL COURTS TO WHICH AN APPEAL MAY BE TAKEN FROM SUCH COURTS, FOR THE PURPOSE OF ANY SUIT, ACTION, OR OTHER PROCEEDING ARISING OUT OF, OR IN CONNECTION WITH, THIS AGREEMENT OR ANY OF THE TRANSACTIONS CONTEMPLATED HEREBY, INCLUDING, WITHOUT LIMITATION, ANY PROCEEDING RELATING TO ANCILLARY MEASURES IN AID OF ARBITRATION, PROVISIONAL REMEDIES AND INTERIM RELIEF, OR ANY PROCEEDING TO ENFORCE ANY ARBITRAL DECISION OR AWARD. EACH PARTY HERETO EXPRESSLY WAIVES ANY AND ALL RIGHTS TO BRING ANY SUIT, ACTION, OR OTHER PROCEEDING IN OR BEFORE ANY COURT OR TRIBUNAL OTHER THAN COURTS OF THE STATE OF TEXAS, COUNTY OF COMAL, AND COVENANTS THAT IT SHALL NOT SEEK IN ANY MANNER TO PROSECUTE OR DEFEND ANY DISPUTE OTHER THAN AS SET FORTH IN THIS ARTICLE XVI OR TO CHALLENGE OR SET ASIDE ANY DECISION, AWARD, OR JUDGMENT OBTAINED IN ACCORDANCE WITH THE PROVISIONS HEREOF. EACH OF THE PARTIES HERETO HEREBY EXPRESSLY WAIVES ANY AND ALL OBJECTIONS IT MAY HAVE TO VENUE, INCLUDING, WITHOUT LIMITATION, THE INCONVENIENCE OF SUCH FORUM, IN ANY OF SUCH COURTS.

XVI. JURY TRIAL WAIVER. THE PARTIES HEREBY UNCONDITIONALLY WAIVE THEIR RIGHT TO A JURY TRIAL OF ANY AND ALL CLAIMS OR CAUSES OF ACTION ARISING FROM OR RELATING TO THEIR RELATIONSHIP. THE PARTIES ACKNOWLEDGE THAT A RIGHT TO A JURY IS A CONSTITUTIONAL RIGHT, THAT THEY HAVE HAD AN OPPORTUNITY TO CONSULT WITH INDEPENDENT COUNSEL, AND THAT THIS JURY WAIVER HAS BEEN ENTERED INTO KNOWINGLY AND VOLUNTARILY BY ALL PARTIES TO THIS AGREEMENT. IN THE EVENT OF LITIGATION, THIS AGREEMENT MAY BE FILED AS A WRITTEN CONSENT TO A TRIAL BY THE COURT.

Approved by Contractor:

MP#0001708

CHRISTOPHER RYAN SEIDENSTICKER

Approved by Client:

*Rodolfo Gonzales R
Crystal Gonzalez*

XVII. Reservation of Rights. Contractor reserves all rights not specifically granted herein.

XVIII. Counterparts. This Agreement may be executed in one or more counterparts, each of which shall be deemed to be an original but all of which together will constitute one and the same instrument.

XIX. Counsel. Contractor has previously recommended that Client engage counsel to assist him/her/it in reviewing this Agreement and all other matters relating to it. Contractor and Client shall each bear his/her/its own costs and expenses in connection with the negotiation and documentation of this Agreement.

XX. Entire Agreement: This agreement contains the entire agreement of the parties, and there are no promises or conditions in any other agreement, oral or written. The Parties expressly disclaim reliance on any prior statements, oral or written, by either party not expressly provided for herein.

Client:

RG C.G.

Contractor:

RS

ON-SITE SEWERAGE FACILITY SOIL EVALUATION REPORT INFORMATION

Date Soil Survey Performed: March 24, 2020

Site Location: The POINT at RANCHO DEL LAGO, UNIT 2, LOT 112

Proposed Excavation Depth: N/A

Requirements:

At least two soil excavations must be performed on the site, at opposite ends of the proposed disposal area.
Locations of soil boring or dug pits must be shown on the site drawing.
For subsurface disposal, soil evaluations must be performed to a depth of at least two feet below the proposed excavation depth. For surface disposal, the surface horizon must be evaluated.
Describe each soil horizon and identify any restrictive features on the form. Indicate depths where features appear.

SOIL BORING NUMBER		SURFACE EVALUATION				
Depth (Feet)	Texture Class	Soil Texture	Gravel Analysis	Drainage (Mottles/ Water Table)	Restrictive Horizon	Observations
0	III	CLAY LOAM	N/A	NONE OBSERVED	LIMESTONE @ 8"	BROWN
1						
2						
3						
4						
5						


RECEIVED

MAR 30 2020

COUNTY ENGINEER

SOIL BORING NUMBER		SURFACE EVALUATION				
Depth (Feet)	Texture Class	Soil Texture	Gravel Analysis	Drainage (Mottles/ Water Table)	Restrictive Horizon	Observations
0	SAME		AS		ABOVE	
1						
2						
3						
4						
5						

I certify that the findings of this report are based on my field observations and are accurate to the best of my ability.


Greg W. Johnson, P.E. 67587-F2585, S.E. 11561

03/24/2020
Date

Date: March 25, 2020

RODOLFO GONZALEZ Jr. & CRYSTAL LYNN

Name: GONZALEZ
Address: c/o 23011 F.M. 306
City: CANYON LAKE State: TEXAS
Zip Code: 78133 Phone: (830) 935-4936

Name: Greg W. Johnson, P.E., R.S., S.E. 11561

Address: 170 Hollow Oak
City: New Braunfels State: Texas
Zip Code: 78132 Phone & Fax (830)905-2778

Lot **112** Unit **2** Blk ____ Subd. **The POINT at RANCHO DEL LAGO**
Street Address: **160 BLUEJAY COURT**
City: **CANYON LAKE** Zip Code: **78133**
Additional Info.: _____

Name: _____
 Company: _____
 Address: _____
 City: _____ State: _____
 Zip Code: _____ Phone: _____

Topography: Slope within proposed disposal area: 6 to 12 %

Presence of 100 yr. Flood Zone:	YES <u> </u>	NO <u>X</u>
Existing or proposed water well in nearby area.	YES <u> </u>	NO <u>X</u>
Presence of adjacent ponds, streams, water impoundments	YES <u> </u>	NO <u>X</u>
Presence of upper water shed	YES <u> </u>	NO <u>X</u>
Organized sewage service available to lot	YES <u> </u>	NO <u>X</u>

RECEIVED

MAR 30 2020

Commercial

COUNTY ENGINEER

Q = _____ GPD _____

Residential Water conserving fixtures to be utilized? Yes X No

Number of Bedrooms the septic system is sized for: 3 Total sq. ft. living area 1819

$$Q \text{ gal/day} = (\text{Bedrooms} + 1) * 75 \text{ GPD} - (20\% \text{ reduction for water conserving fixtures})$$
$$Q = (3 + 1) * 75 - (20\%) = 240$$

Trash Tank Size 353 Gal.

TCEQ Approved Aerobic Plant Size 600 G.P.D.

Req'd Application Area = $Q/R_i = \frac{240}{0.064} = 3750$ sq. ft.

Application Area Utilized = 4241 sq. ft.

Pump Requirement 12 Gpm @ 41 Psi (Redjacket 0.5 HP 18 G.P.M. series or equivalent)

Dosing Cycle: ON DEMAND or X TIMED TO DOSE IN PREDAWN HOURS

Pump Tank Size = 768 Gal. 14.5 Gal/inch.

Reserve Requirement = 80 Gal. 1/3 day flow.

Alarms: Audible & Visual High Water Alarm & Visual Air Pump malfunction

With Chlorinator NSF/TCEO APPROVED

SCH-40 or SDR-26 3" or 4" sewer line to tank

Two way cleanout

Pop-up rotary sprinkler heads w/ purple non-potable lids

1" Sch-40 PVC discharge manifold

APPLICATION AREA SHOULD BE SEEDED AND MAINTAINED WITH VEGETATION.

I HAVE PERFORMED A THOROUGH INVESTIGATION BEING A REGISTERED PROFESSIONAL ENGINEER AND SITE EVALUATOR IN ACCORDANCE WITH CHAPTER 285, SUBCHAPTER D, §285.30, & §285.40 (REGARDING RECHARGE FEATURES), TEXAS COMMISSION OF ENVIRONMENTAL QUALITY (EFFECTIVE DECEMBER 29, 2016)

GREG W. JOHNSON, P.E. F#002585 - S.E. 11561

DATE _____

**FIRM #2585**

COUNTY ENGINEER

X= TEST HOLES

BLUEJAY
COURT

10' DRAINAGE EASEMENT



OWNER: RODOLFO GONZALEZ Jr. & CRYSTAL LYNN GONZALEZ		DRAWN BY: EJS III	
STREET ADDRESS: 160 BLUEJAY COURT			
LEGAL DESC: The POINT at RANCHO DEL LAGO		UNIT/SECTION/PHASE: 2	LOT: 112
PREPARED BY: GREG W. JOHNSON, P.E. F#002585		SCALE: 1"=40'	DATE: 3/25/2020
		REVISED:	

TANK NOTES:

Tanks must be set to allow a minimum of 1/8" per foot fall from the residence.

Tightlines to the tank shall be SCH-40 PVC.

A two way sanitary tee is required between residence and tank.



A minimum of 4" of sand, sandy loam, clay loam free of rock shall be placed under and around tanks

RECEIVED

MAR 30 2020

COUNTY ENGINEER


ALL WIRING MUST BE IN COMPLIANCE WITH
THE MOST RECENT NATIONAL ELECTRIC CODE



F-2585

03/15/2020

**TYPICAL PUMP TANK CONFIGURATION
MAXX AIR M600 768 GAL PUMP TANK**



SCALE IN MILES
0 1/8 1/4 3/8 1/2

SCALE IN FEET
0 1000 2000 3000



201906015966 06/10/2019 10:57:11 AM 1/2

1918
CV 1003
2/CS

General Warranty Deed

Date: May 7, 2019

Grantor: Mario and Cynthia A. Morrell,
Co-Trustees of the Mario and Cynthia A. Morrell Living Trust,
Dated December 23, 2008

Grantor's Mailing Address:

13571 W Watson LN, Surprise, AZ 85379

Grantee: Rodolfo Gonzalez, Jr. and Crystal Lynn Gonzalez

Grantee's Mailing Address:

1860 Island View, Compu Lake TX 78133

RECEIVED

MAR 30 2020

COUNTY ENGINEER

Consideration:

Cash and other good and valuable consideration, the receipt and sufficiency of which are hereby acknowledged.

Property (including any improvements):

Lot 112, The Point at Rancho Del Lago, Phase 2, a subdivision in Comal County, Texas, according to map and plat recorded in Volume 8, Page 64-66, of the Map and Plat Records of Comal County, Texas

Reservations from Conveyance: None

Exceptions to Conveyance and Warranty:

Validly existing easements, rights-of-way, and prescriptive rights, whether of record or not; all presently recorded and validly existing instruments, other than conveyances of the surface fee estate, that affect the Property; and taxes for 2019, which Grantee assumes and agrees to pay, but not subsequent assessments for that and prior years due to change in land usage, ownership, or both, the payment of which Grantor assumes.

Grantor, for the Consideration and subject to the Reservations from Conveyance and the Exceptions to Conveyance and Warranty, grants, sells, and conveys to Grantee the Property, together with all and singular the rights and appurtenances thereto in any way belonging, to have and to hold it to Grantee and Grantee's heirs, successors, and assigns forever. Grantor binds Grantor and Grantor's heirs and successors to warrant and forever defend all and singular the Property to Grantee and Grantee's heirs, successors, and assigns against every person whomsoever lawfully claiming or to claim the same or any part thereof, except as to the

Reservations from Conveyance and the Exceptions to Conveyance and Warranty.

When the context requires, singular nouns and pronouns include the plural.


Mario Morrell Co-Trustee
Mario Morrell, Co-Trustee
of the Mario and Cynthia A. Morrell Living Trust

Cynthia A. Morrell, Co-Trustee
Cynthia A. Morrell, Co-Trustee
of the Mario and Cynthia A. Morrell Living Trust

STATE OF ARIZONA)

COUNTY OF Maricopa)

This instrument was acknowledged before me on May 7th, 2019, by Mario Morrell and Cynthia A. Morrell, Co-Trustees of the Mario and Cynthia A. Morrell Living Trust



Destiny Coleman
Notary Public, State of Arizona
My Commission expires: 03/28/2021

PREPARED IN THE OFFICE OF:

DWAIN W BLASCHKE
P.O. Box 1744
Canyon Lake, TX 78133
Tel: (830) 964-4442
Fax: (830) 964-4426

RECEIVED

MAR 30 2020

COUNTY ENGINEER

Filed and Recorded
Official Public Records
Bobbie Koepf, County Clerk
Comal County, Texas
05/10/2019 10:57:11 AM
TERRI 2 Page(s)
201906015966



Bobbie Koepf

PS Septic Supply & Service
23011 FM 306
Canyon Lake, TX 78133

Phone: (830) 850-0080
Fax: (830) 935-4932

To: Crystal Gonzales
160 Bluejay Court
Canyon Lake, TX 78133

Printed: 8/9/2021
Site: 160 Bluejay Court
Canyon Lake, TX 78133
(210) 844-9156

Permit #: **110583**
Agency: Comal County
County:
Mfg / Brand: -

Customer ID: 1992
Contract Dates: 4/20/2021 - 4/20/2024
Scheduled Date 8/20/2021 Inspection 1 of 9

GPS Coordinates - Latitude: 29.9317 Longitude: -98.2212

Service Type: Scheduled Inspection

☒ This counts as a type of "Scheduled Inspection"

Visit Date: 8/6/2021

Entered By: _

Method: Grab

Technician: Ryan Seidensticker

Maint. Provider: Ryan Seidensticker

Aerators: Operational

Sludge Levels

Filters: Operational

For Tank 1: 4

Irrigation Pumps: Operational

Disinfection Device: Operational

Chlorine Supply: Operational

Chlorine Residual: .3

Tank Lid / Riser: Secured

Sprinkler Drip Backwash: Good

Electric Circuits: Operational

Distribution System: Operational

Sprayfield Veg: Operational

Color: Good

Odor: Good

Alarm: Operational

Comments

Scum on pretreatment 0" M.A. - Technician Secured the Tank Lid and/or Riser prior to leaving location.

☒ **Service Completed**

Owner signature: _____

Insp ID #: 11257

Provider: Christopher Ryan Seidensticker
PS Septic Supply & Service

Technician: Christopher Ryan Seidensticker
PS Septic Supply & Service

License Info: MP0001708 Expires:

License Info: MP0001708 Expires: 9/1/2023

PS Septic Supply & Service
23011 FM 306
Canyon Lake, TX 78133

Phone: (830) 850-0080
Fax: (830) 935-4932

To: Crystal Gonzales
160 Bluejay Court
Canyon Lake, TX 78133

Printed: 12/27/2021
Site: 160 Bluejay Court
Canyon Lake, TX 78133
(210) 844-9156

Permit #: **110583**
Agency: Comal County
County:
Mfg / Brand: -

Customer ID: 1992
Contract Dates: 4/20/2021 - 4/20/2024
Scheduled Date: 12/20/2021 Inspection 2 of 9

GPS Coordinates - Latitude: 29.9317 Longitude: -98.2212

Service Type: Scheduled Inspection

Visit Date: 12/21/2021

Method: Grab

Technician: Nick Zigalo

Maint. Provider: Ryan Seidensticker

☒ This counts as a type of "Scheduled Inspection"

Entered By: Michelle Irvin

Aerators: Operational

Filters: Operational

Irrigation Pumps: Operational

Disinfection Device: Operational

Chlorine Supply: Operational

Chlorine Residual: .10

Sludge Levels

For Tank 1: 14

For Tank 2: 4

For Tank 3: 4

Tank Lid / Riser: Secured

Sprinkler Drip Backwash: Good

Electric Circuits: Operational

Distribution System: Operational

Sprayfield Veg: Operational

Color: Good

Odor: Good

Alarm: Operational

Comments

Scum = 2" - Technician Secured the Tank Lid and/or Riser prior to leaving location.

☒ **Service Completed**

Insp ID #:13990

Provider: *Christopher Ryan Seidensticker*
PS Septic Supply & Service

License Info: MP0001708 Expires:

License Info: MT0002016 Expires: 12/31/2023

PS Septic Supply & Service
23011 FM 306
Canyon Lake, TX 78133

Phone: (830) 850-0080
Fax: (830) 935-4932

To: Crystal Gonzales
160 Bluejay Court
Canyon Lake, TX 78133

Printed: 4/20/2022
Site: 160 Bluejay Court
Canyon Lake, TX 78133
(210) 844-9156

Permit #: **110583**
Agency: Comal County
County:
Mfg / Brand: -

Customer ID: 1992
Contract Dates: 4/20/2021 - 4/20/2024
Scheduled Date: 4/20/2022 Inspection 3 of 9

GPS Coordinates - Latitude: 29.9317 Longitude: -98.2212

Service Type: Scheduled Inspection

☒ This counts as a type of "Scheduled Inspection"

Visit Date: 4/19/2022

Entered By: Michelle Irvin

Method: Grab

Technician: Not Assigned

Maint. Provider: Ryan Seidensticker

Aerators: Operational

Sludge Levels

Filters: Operational

For Tank 1: 12

Irrigation Pumps: Operational

Disinfection Device: Operational

For Tank 3: 3

Chlorine Supply: Operational

Chlorine Residual: .29

Tank Lid / Riser: Secured

Sprinkler Drip Backwash: Good

Electric Circuits: Operational

Distribution System: Operational

Sprayfield Veg: Operational

Color: Good

Odor: Good

Alarm: Operational

Comments

☒ **Service Completed**

Scum = 2" - Technician Secured the Tank Lid and/or Riser prior to leaving location.

Insp ID #: 17129

Provider: *Christopher Ryan Seidensticker*
PS Septic Supply & Service

License Info: MP0001708 Expires:

PS Septic Supply & Service
23011 FM 306
Canyon Lake, TX 78133

Phone: (830) 850-0080
Fax: (830) 935-4932

To: Crystal Gonzales
160 Bluejay Court
Canyon Lake, TX 78133

Printed: 9/8/2022
Site: 160 Bluejay Court
Canyon Lake, TX 78133
(210) 844-9156

Permit #: **110583**

Agency: Comal County

County:

Mfg / Brand: -

Customer ID: 1992

Contract Dates: 4/20/2021 - 4/20/2024

Scheduled Date: 8/20/2022

Inspection 4 of 9

GPS Coordinates - Latitude: 29.9317 Longitude: -98.2212

Service Type: Scheduled Inspection

☒ This counts as a type of "Scheduled Inspection"

Visit Date: 9/8/2022

Entered By: _

Method: Grab

Technician: Not Assigned

Maint. Provider: Ryan Seidensticker

Aerators: Operational

Sludge Levels

Filters: Operational

Irrigation Pumps: Operational

For Tank 2: 15

Disinfection Device: Operational

For Tank 3: 4

Chlorine Supply: Operational

Chlorine Residual: .31

Electric Circuits: Operational

Tank Lid / Riser: Secured

Distribution System: Operational

Insp. Port / Plug: Secured

Sprayfield Veg: Operational

Alarm: Operational

Comments

☒ **Service Completed**

- Scum on pretreatment 1 - Technician Secured the Tank Lid and/or Riser prior to leaving location. - Inspection Port Plug was noted as Secured prior to leaving.

Insp ID #:20657

Provider: *Christopher Ryan Seidensticker*
PS Septic Supply & Service

License Info: MP0001708 Expires:

PS Septic Supply & Service
23011 FM 306
Canyon Lake, TX 78133

Phone: (830) 850-0080
Fax: (830) 935-4932

Printed: 12/16/2022 Insp ID #: 23923

Permit #: **110583**

To: Crystal Gonzales
160 Bluejay Court
Canyon Lake, TX 78133

Main Phone: (210) 844-9156

Work:

Cell Phone:

Alt Cell:

Customer ID: 1992

Contract Dates: 4/20/2021 - 4/20/2024

Scheduled Date: 12/20/2022

Inspection 5 of 9

Agency: Comal County

County:

Mfg / Brand: -

GPS Coordinates: Latitude: 29.9317 Longitude: -98.2212

Service Type: Scheduled Inspection

☒ This counts as a type of "Scheduled Inspection"

Entered By: Chris Zigalo

Visit Date: 12/15/2022

Method: Grab

Technician: Chris Zigalo

Maint. Provider: Ryan Seidensticker

Aerators: Operational

Filters: Operational

Irrigation Pumps: Operational

Disinfection Device: Operational

Chlorine Supply: Operational

Chlorine Residual: .13

Sludge Levels

For Tank 1: 14

For Tank 3: 6

For Tank 4: 2

Electric Circuits: Operational

Distribution System: Operational

Sprayfield Veg: Operational

Tank Lid / Riser: Secured

Insp. Port / Plug: Secured

Alarm: Operational

Comments

☒ **Service Completed**

scum 0 - Red switch secure - Technician Secured the Tank Lid and/or Riser prior to leaving location. - Inspection Port Plug was noted as Secured prior to leaving.

Please call office to update email

Site: 160 Bluejay Court, Canyon Lake, TX 78133

Provider: *Christopher Ryan Seidensticker*
PS Septic Supply & Service

License Info: MP0001708 Expires:

License Info: MT001878 Expires: 7/31/2023

Luna Environmental

4222 FM 482

New Braunfels, TX 78132

(830) 312-8776

sherrie@lunaenvironmental.com

Printed:10/6/2023

Permit: 110583

Site: 160 Bluejay Court, Canyon Lake, TX 78133

Main Phone: 2108449156

Rodolfo & Crystal Gonzales

160 Bluejay Court

Canyon Lake, TX 78133

Agency: Comal County

County: Comal County

Subdivision: The Point @ RDL

System Info: MFG: <u>Brand: MAXX AIR</u>	Customer ID: <u>3391</u>
Treatment Type: <u>Aerobic</u>	Disposal Type: <u>Surface Application</u>
Installed: <u>4/20/2021</u>	Warranty Expiration: <u>4/20/2024</u>
Insp ID: <u>33995</u>	
Visit Details	
Visit Date: <u>10/5/2023</u>	Entered By: Nicole Loria
Scheduled Date: <u>8/20/2023</u>	Contract Starts: <u>4/20/2021</u>
Entered On: <u>10/6/2023</u>	Contract Ends: <u>4/20/2024</u>
Visit Results	
GPS Lat: 29.9317 GPS Long: -98.2212	

Service Type: Scheduled Inspection

Count: Inspection 7 of 9

Method: Grab

Technician: Luke Campbell

License #

MT0002614

Expires

9/30/2026

Provider: Luna Environmental, LLC

☒ Service Completed

Aerators: <u>Operational</u>	Sludge Level Tank 1: <u>18</u>
Filters: <u>Operational</u>	Sludge Level Tank 2: <u>N/A</u>
Irrigation Pumps: <u>Operational</u>	Sludge Level Tank 3: <u>4</u>
Disinfection Device: <u>Operational</u>	Sludge Level Tank 4: <u>6</u>
Chlorine Supply: <u>Operational</u>	
Chlorine Residual: <u>.01</u>	

Electric Circuits: <u>Operational</u>	Tank Lid / Riser: <u>Secured</u>
Distribution System: <u>Operational</u>	Insp. Port / Plug: <u>Secured</u>
Drip/Sprayfield Veg: <u>Operational</u>	

Alarm: Operational

PSI Pressure: 2.3

Comments

- Scum on pretreatment 0 - Technician Secured the Tank Lid and/or Riser prior to leaving location. - Inspection Port Plug was noted as Secured prior to leaving. - Please contact office to update email/account info

PS Septic Supply & Service
23011 FM 306
Canyon Lake, TX 78133

Phone: (830) 850-0080
Fax: (830) 935-4932

Printed: 5/1/2023

Insp ID #: 27955

Permit #: **110583**

To: Rodolfo & Crystal Gonzales
160 Bluejay Court
Canyon Lake, TX 78133

Main Phone: (210) 844-9156

Work:

Cell Phone:

Alt Cell:

Customer ID: 1992

Contract Dates: 4/20/2021 - 4/20/2024

Scheduled Date: 4/20/2023

Inspection 6 of 9

Installed: 4/20/2021

Warranty End: 4/20/2024

Agency: Comal County

County: Comal County

Mfg / Brand: - MAXX AIR

Sub: The Point @ RDL

Treatment Type: Aerobic

Disposal: Surface Application

GPS Coordinates: Latitude: 29.9317 Longitude: -98.2212

Service Type: Scheduled Inspection

☒ This counts as a type of "Scheduled Inspection"

Entered By: Julie Feibelman

Visit Date: 4/28/2023

Method: Grab

Technician: Logan

Maint. Provider: Ryan Seidensticker

Aerators: Operational

Filters: Operational

Irrigation Pumps: Operational

Disinfection Device: Operational

Chlorine Supply: Operational

Chlorine Residual: 0.01

Sludge Levels

For Tank 1: 20

For Tank 2: NA

For Tank 3: 14

For Tank 4: 4

Electric Circuits: Operational

Distribution System: Operational

Sprayfield Veg: Operational

Tank Lid / Riser: Secured

Insp. Port / Plug: Secured

Alarm: Operational

Comments

☒ **Service Completed**

- Scum on pretreatment - 0 - Needs to add bleach to chlorine reservoir. - Technician Secured the Tank Lid and/or Riser prior to leaving location. - Inspection Port Plug was noted as Secured prior to leaving.

Site: 160 Bluejay Court, Canyon Lake, TX 78133

Provider: *Christopher Ryan Seidensticker*
PS Septic Supply & Service

License Info: MP0001708 Expires: