

# Comal County Environmental Health OSSF Inspection Sheet

Installer Name: \_\_\_\_\_

OSSF Installer #: \_\_\_\_\_

1st Inspection Date: \_\_\_\_\_

2nd Inspection Date: \_\_\_\_\_

3rd Inspection Date: \_\_\_\_\_

Inspector Name: \_\_\_\_\_

Inspector Name: \_\_\_\_\_

Inspector Name: \_\_\_\_\_

Permit#: \_\_\_\_\_

Address: \_\_\_\_\_

No.	Description	Answer	Citations	Notes	1st Insp.	2nd Insp.	3rd Insp.
1	SITE AND SOIL CONDITIONS & SETBACK DISTANCES Site and Soil Conditions Consistent with Submitted Planning Materials		285.31(a) 285.30(b)(1)(A)(iv) 285.30(b)(1)(A)(v) 285.30(b)(1)(A)(iii) 285.30(b)(1)(A)(ii) 285.30(b)(1)(A)(i)				
2	SITE AND SOIL CONDITIONS & SETBACK DISTANCES Setback Distances Meet Minimum Standards		285.91(10) 285.30(b)(4) 285.31(d)				
3	SEWER PIPE Proper Type Pipe from Structure to Disposal System (Cast Iron, Ductile Iron, Sch. 40, SDR 26)		285.32(a)(1)				
4	SEWER PIPE Slope from the Sewer to the Tank at least 1/8 Inch Per Foot		285.32(a)(3)				
5	SEWER PIPE Two Way Sanitary - Type Cleanout Properly Installed (Add. C/O Every 100' &/or 90 degree bends)		285.32(a)(5)				
6	PRETREATMENT Installed (if required) TCEQ Approved List PRETREATMENT Septic Tank(s) Meet Minimum Requirements		285.32(b)(1)(G) 285.32(b)(1)(E)(iii) 285.32(b)(1)(E)(iv) 285.32(b)(1)(F) 285.32(b)(1)(B) 285.32(b)(1)(C)(i) 285.32(b)(1)(C)(ii) 285.32(b)(1)(D) 285.32(b)(1)(E) 285.32(b)(1)(A) 285.32(b)(1)(E)(ii)(II) 285.32(b)(1)(E)(i) 285.32(b)(1)(E)(ii)(I)				
7	PRETREATMENT Grease Interceptors if required for commercial		285.34(d)				

Inspector Notes:

**Comal County Environmental Health  
OSSF Inspection Sheet**

No.	Description	Answer	Citations	Notes	1st Insp.	2nd Insp.	3rd Insp.
8	SEPTIC TANK Tank(s) Clearly Marked SEPTIC TANK If Single Tank, 2 Compartments Provided with Baffle SEPTIC TANK Inlet Flowline Greater than 3" and " T " Provided on Inlet and Outlet SEPTIC TANK Septic Tank(s) Meet Minimum Requirements		285.32(b)(1) (E)285.91(2)285.32(b)(1) (F)285.32(b)(1)(E) (iii)285.32(b)(1)(E)(ii) (II)285.32(b)(1)(E)(ii) (I)285.32(b)(1)(E) (i)285.32(b)(1) (D)285.32(b)(1)(C) (ii)285.32(b)(1)(C) (i)285.32(b)(1) (B)285.32(b)(1) (A)285.32(b)(1)(E)(iv)				
9	ALL TANKS Installed on 4" Sand Cushion/ Proper Backfill Used		285.32(b)(1)(F) 285.32(b)(1)(G) 285.34(b)				
10	SEPTIC TANK Inspection / Clean Out Port & Risers Provided on Tanks Buried Greater than 12" Sealed and Capped		285.38(d)				
11	SEPTIC TANK Secondary restraint system provided SEPTIC TANK Riser permanently fastened to lid or cast into tank SEPTIC TANK Riser cap protected against unauthorized intrusions		285.38(d) 285.38(e)				
12	SEPTIC TANK Tank Volume Installed						
13	PUMP TANK Volume Installed						
14	AEROBIC TREATMENT UNIT Size Installed						
15	AEROBIC TREATMENT UNIT Manufacturer AEROBIC TREATMENT UNIT Model Number						
16	DISPOSAL SYSTEM Absorptive		285.33(a)(4) 285.33(a)(1) 285.33(a)(2) 285.33(a)(3)				
17	DISPOSAL SYSTEM Leaching Chamber		285.33(a)(1) 285.33(a)(3) 285.33(a)(4) 285.33(a)(2)				
18	DISPOSAL SYSTEM Evapo-transpirative		285.33(a)(3) 285.33(a)(4) 285.33(a)(1) 285.33(a)(2)				

**Comal County Environmental Health  
OSSF Inspection Sheet**

No.	Description	Answer	Citations	Notes	1st Insp.	2nd Insp.	3rd Insp.
19	DISPOSAL SYSTEM Drip Irrigation		285.33(c)(3)(A)-(F)				
20	DISPOSAL SYSTEM Soil Substitution		285.33(d)(4)				
21	DISPOSAL SYSTEM Pumped Effluent		285.33(a)(4) 285.33(a)(3) 285.33(a)(1) 285.33(a)(2)				
22	DISPOSAL SYSTEM Gravelless Pipe		285.33(a)(3) 285.33(a)(2) 285.33(a)(4) 285.33(a)(1)				
23	DISPOSAL SYSTEM Mound		285.33(a)(3) 285.33(a)(1) 285.33(a)(2) 285.33(a)(4)				
24	DISPOSAL SYSTEM Other (describe) (Approved Design)		285.33(d)(6) 285.33(c)(4)				
25	DRAINFIELD Absorptive Drainline 3" PVC or 4" PVC						
26	DRAINFIELD Area Installed						
27	DRAINFIELD Level to within 1 inch per 25 feet and within 3 inches over entire excavation		285.33(b)(1)(A)(v)				
28	DRAINFIELD Excavation Width DRAINFIELD Excavation Depth DRAINFIELD Excavation Separation DRAINFIELD Depth of Porous Media DRAINFIELD Type of Porous Media						
29	DRAINFIELD Pipe and Gravel - Geotextile Fabric in Place		285.33(b)(1)(E)				
30	DRAINFIELD Leaching Chambers DRAINFIELD Chambers - Open End Plates w/Splash Plate, Inspection Port & Closed End Plates in Place (per manufacturers spec.)		285.33(c)(2)				
31	LOW PRESSURE DISPOSAL SYSTEM Adequate Trench Length & Width, and Adequate Separation Distance between Trenches		285.33(d)(1)(C)(i)				

**Comal County Environmental Health  
OSSF Inspection Sheet**

No.	Description	Answer	Citations	Notes	1st Insp.	2nd Insp.	3rd Insp.
32	EFFLUENT DISPOSAL SYSTEM Utilized Only by Single Family Dwelling EFFLUENT DISPOSAL SYSTEM Topographic Slopes < 2.0% EFFLUENT DISPOSAL SYSTEM Adequate Length of Drain Field ( 1000 Linear ft. for 2 bedrooms or Less & an additional 400 ft. for each additional bedroom ) EFFLUENT DISPOSAL SYSTEM Lateral Depth of 18 inches to 3 ft. & Vertical Separation of 1ft on bottom and 2 ft. to restrictive horizon and ground water respectfully EFFLUENT DISPOSAL SYSTEM Lateral Drain Pipe ( 1.25 - 1.5" dia. ) & Pipe Holes ( 3/16 - 1/4" dia. Hole Size ) 5 ft. Apart		285.33(b)(3)(A) 285.33(b)(3)(A) 285.33(b)(3)(B) 285.91(13) 285.33(b)(3)(D) 285.33(b)(3)(F)				
33	AEROBIC TREATMENT UNIT Is Aerobic Unit Installed According to Approved Guidelines.		285.32(c)(1)				
34	AEROBIC TREATMENT UNIT Inspection/Clean Out Port & Risers Provided AEROBIC TREATMENT UNIT Secondary restraint system provided AEROBIC TREATMENT UNIT Riser permanently fastened to lid or cast into tank AEROBIC TREATMENT UNIT Riser cap protected against unauthorized intrusions						
35	AEROBIC TREATMENT UNIT Chlorinator Properly Installed with Chlorine Tablets in Place.						
36	PUMP TANK Is the Pump Tank an approved concrete tank or other acceptable materials & construction PUMP TANK Sampling Port Provided in the Treated Effluent Line PUMP TANK Check Valve and/or Anti- Siphon Device Present When Required PUMP TANK Audible and Visual High Water Alarm Installed on Separate Circuit From Pump						
37	PUMP TANK Inspection/Clean Out Port & Risers Provided PUMP TANK Secondary restraint system provided PUMP TANK Riser permanently fastened to lid or cast into tank PUMP TANK Riser cap protected against unauthorized intrusions						
38	PUMP TANK Secondary restraint system provided						
39	PUMP TANK Electrical Connections in Approved Junction Boxes / Wiring Buried						

**Comal County Environmental Health  
OSSF Inspection Sheet**

No.	Description	Answer	Citations	Notes	1st Insp.	2nd Insp.	3rd Insp.
40	APPLICATION AREA Distribution Pipe, Fitting, Sprinkler Heads & Valve Covers Color Coded Purple?		285.33(d)(2)(G)(iii)(II) 285.33(d)(2)(G)(iii)(III) 285.33(d)(2)(G)(v) 285.33(d)(2)(G)(iii) 285.33(d)(2)(G)(iv) 285.33(d)(2)(G)(i) 285.33(d)(2)(G)(ii) 285.33(d)(2)(G)(iii)(I)				
41	APPLICATION AREA Low Angle Nozzles Used / Pressure is as required APPLICATION AREA Acceptable Area, nothing within 10 ft of sprinkler heads? APPLICATION AREA The Landscape Plan is as Designed		285.33(d)(2)(G) (i)285.33(d)(2) (A)285.33(d)(2)(F)				
42	APPLICATION AREA Area Installed						
43	PUMP TANK Meets Minimum Reserve Capacity Requirements						
44	PUMP TANK Material Type & Manufacturer						
45	PUMP TANK Type/Size of Pump Installed						



# COMAL COUNTY

ENGINEER'S OFFICE

## Permit of Authorization to Construct an On-Site Sewage Facility Permit Valid For One Year From Date Issued

Permit Number: 118320  
Issued This Date: 02/21/2025  
This permit is hereby given to: ROBERT J. & RAQUEL MUSULIN

To start construction of a private, on-site sewage facility located at:

95 SUN VALLEY DR  
SPRING BRANCH, TX 78070

Subdivision: SUN VALLEY VILLAGE  
Unit: 2  
Lot: 97, 99  
Block: 0  
Acreage: 8.1200

APPROVED MINIMUM SIZES AS PER ATTACHED DESIGN

Type of System: Septic Tank  
Leaching Chambers

This permit gives permission for the construction of the above referenced on-site facility to commence. Installation must be completed by an installer holding a valid registration card from the Texas Commission on Environmental Quality (TCEQ). Installation and inspection must comply with current TCEQ and Comal County requirements.

Call (830) 608-2090 to schedule inspections.



# COMAL COUNTY

ENGINEER'S OFFICE

## OSSF DEVELOPMENT APPLICATION CHECKLIST

Staff will complete shaded items

		118320
--	--	--------

Date Received

Initials

Permit Number

### Instructions:

Place a check mark next to all items that apply. For items that do not apply, place "N/A". This OSSF Development Application Checklist **must** accompany the completed application.

### OSSF Permit

- Completed Application for Permit for Authorization to Construct an On-Site Sewage Facility and License to Operate
- Site/Soil Evaluation Completed by a Certified Site Evaluator or a Professional Engineer
- Planning Materials of the OSSF as Required by the TCEQ Rules for OSSF Chapter 285. Planning Materials shall consist of a scaled design and all system specifications.
- Required Permit Fee - See Attached Fee Schedule
- Copy of Recorded Deed
- Surface Application/Aerobic Treatment System
  - Recorded Certification of OSSF Requiring Maintenance/Affidavit to the Public
  - Signed Maintenance Contract with Effective Date as Issuance of License to Operate

I affirm that I have provided all information required for my OSSF Development Application and that this application constitutes a completed OSSF Development Application.

Signature of Applicant

01/23/2025

Date

<input type="checkbox"/> COMPLETE APPLICATION Check No. _____ Receipt No. _____
--

<input type="checkbox"/> INCOMPLETE APPLICATION (Missing Items Circled, Application Refused)
---



COMAL COUNTY  
ENGINEER'S OFFICE

# ON-SITE SEWAGE FACILITY APPLICATION

195 DAVID JONAS DR  
NEW BRAUNFELS, TX 78132  
(830) 608-2090  
[WWW.CCEO.ORG](http://WWW.CCEO.ORG)

Date December 4, 2024

Permit Number 118320

## 1. APPLICANT / AGENT INFORMATION

Owner Name ROBERT J. & RAQUEL MUSULIN  
Mailing Address 95 SUN VALLEY DRIVE  
City, State, Zip SPRING BRANCH TEXAS 78070  
Phone # 830-708-8603  
Email star-tech@gvtc.com

Agent Name GREG JOHNSON, P.E.  
Agent Address 170 HOLLOW OAK  
City, State, Zip NEW BRAUNFELS TEXAS 78132  
Phone # 830-905-2778  
Email gregjohnsonpe@yahoo.com

## 2. LOCATION

Subdivision Name SUN VALLEY VILLAGE Unit 2 Lot 97 & 99 Block \_\_\_\_\_  
Survey Name / Abstract Number \_\_\_\_\_ Acreage \_\_\_\_\_  
Address 95 SUN VALLEY DRIVE City SPRING BRANCH State TX Zip 78070

## 3. TYPE OF DEVELOPMENT

Single Family Residential

Type of Construction (House, Mobile, RV, Etc.) HOUSE AND DETACHED SHOP W TOILET

Number of Bedrooms 4

Indicate Sq Ft of Living Area 3486 + 800 SHOP

Non-Single Family Residential

(Planning materials must show adequate land area for doubling the required land needed for treatment units and disposal area)

Type of Facility \_\_\_\_\_

Offices, Factories, Churches, Schools, Parks, Etc. - Indicate Number Of Occupants \_\_\_\_\_

Restaurants, Lounges, Theaters - Indicate Number of Seats \_\_\_\_\_

Hotel, Motel, Hospital, Nursing Home - Indicate Number of Beds \_\_\_\_\_

Travel Trailer/RV Parks - Indicate Number of Spaces \_\_\_\_\_

Miscellaneous \_\_\_\_\_

Estimated Cost of Construction: \$ 500,000 (Structure Only)

Is any portion of the proposed OSSF located in the United States Army Corps of Engineers (USACE) flowage easement?

Yes  No (If yes, owner must provide approval from USACE for proposed OSSF improvements within the USACE flowage easement)

Source of Water  Public  Private Well  Rainwater Collection

## 4. SIGNATURE OF OWNER

By signing this application, I certify that:

- The completed application and all additional information submitted does not contain any false information and does not conceal any material facts. I certify that I am the property owner or I possess the appropriate land rights necessary to make the permitted improvements on said property.
- Authorization is hereby given to the permitting authority and designated agents to enter upon the above described property for the purpose of site/soil evaluation and inspection of private sewage facilities..
- I understand that a permit of authorization to construct will not be issued until the Floodplain Administrator has performed the reviews required by the Comal County Flood Damage Prevention Order.
- I affirmatively consent to the online posting/public release of my e-mail address associated with this permit application, as applicable.

[Signature]  
Signature of Owner

\_\_\_\_\_  
Date



ON-SITE SEWAGE FACILITY APPLICATION

Planning Materials & Site Evaluation as Required Completed By GREG W. JOHNSON, P.E.

System Description PROPRIETARY; SEPTIC TANK AND LEACHING CHAMBERS

Size of Septic System Required Based on Planning Materials & Soil Evaluation

Tank Size(s) (Gallons) 1000 GAL. & 750 GAL DUAL COMP. SEPTIC TANKS Absorption/Application Area (Sq Ft) 1350

Gallons Per Day (As Per TCEQ Table 111) 360

(Sites generating more than 5000 gallons per day are required to obtain a permit through TCEQ.)

Is the property located over the Edwards Recharge Zone?  Yes  No

(if yes, the planning materials must be completed by a Registered Sanitarian (R.S.) or Professional Engineer (P.E.))

Is there an existing TCEQ approved WPAP for the property?  Yes  No

(if yes, the R.S. or P.E. shall certify that the OSSF design complies with all provisions of the existing WPAP.)

Is there at least one acre per single family dwelling as per 285.40(c)(1)?  Yes  No

If there is no existing WPAP, does the proposed development activity require a TCEQ approved WPAP?  Yes  No

(if yes, the R.S or P.E. shall certify that the OSSF design will comply with all-provisions of the proposed WPAP. A Permit to Construct will not be issued for the proposed OSSF until the proposed WPAP has been approved by the appropriate regional office.)

Is the property located over the Edwards Contributing Zone?  Yes  No

Is there an existing TCEQ approval CZP for the property?  Yes  No


(if yes, the P.E. or R.S. shall certify that the OSSF design complies with all provisions of the existing CZP.)

If there is no existing CZP, does the proposed development activity require a TCEQ approved CZP?  Yes  No

(if yes, the R.S. or P.E. shall certify that the OSSF design will comply with all provisions of the proposed CZP. A Permit to Construct will not be issued for the proposed OSSF until the UP has been approved by the appropriate reg

Is this property within an incorporated city?  Yes  No

If yes, indicate the city: \_\_\_\_\_



FIRM #2585

By signing this application, I certify that:

- The information provided above is true and correct to the best of my knowledge.
- I affirmatively consent to the online posting/public release of my e-mail address associated with this permit application, as applicable.

[Signature]  
Signature of Designer

January 21, 2025  
Date

### AFFIDAVIT TO THE PUBLIC

THE COUNTY OF COMAL §  
STATE OF TEXAS §

**ROBERT J. MUSULIN & RAQUEL MUSULIN**

Before me, the undersigned authority, on this day personally appeared \_\_\_\_\_ who after being by me duly sworn, upon oath state that they are the owner of record of that certain tract or parcel of land lying and being situated in Comal County, Texas, and being more particularly described as follows:

2 UNIT/PHASE/SECTION \_\_\_\_\_ BLOCK 97 & 99 LOT \_\_\_\_\_ SUN VALLEY VILLAGE SUBDIVISION

IF NOT IN SUBDIVISION: \_\_\_\_\_ ACREAGE \_\_\_\_\_ SURVEY

The property is owned by (insert owner's full name): ROBERT J. MUSULIN & RAQUEL MUSULIN

The undersigned further state that the on-site sewage facility for the referenced properties crosses the boundary between the properties. These properties cannot be sold separately and must be sold as one. Any buyer or transferee is hereby notified of this requirement.


WITNESS MY/OUR HAND(S) on this 17 day of January, 2025

X [Signature]  
ROBERT J. MUSULIN

X [Signature]  
RAQUEL MUSULIN

SWORN TO AND SUBSCRIBED BEFORE ME on this 17 day of January, 2025.

[Signature]  
Notary Public Signature



**THE COUNTY OF COMAL  
STATE OF TEXAS**

**CERTIFICATION OF SINGLE FAMILY DWELLING**

According to Texas Commission of Environmental Quality Rules for On-Site Sewage Facilities, this document is filed in the Deed Records of COMAL COUNTY, TEXAS.

I

**ROBERT J. & RAQUEL**

Before me this day appeared MUSULIN, being the owners of the referenced property at 95 SUN VALLEY DRIVE. They further state that the Residence and any additional living space on this property will be occupied only by a single family.

An OSSF requiring a Certification of Single Family Dwelling, will be installed on the property described as:

2 UNIT BLOCK 97 & 99 LOT SUN VALLEY VILLAGE SUBDIVISION

IF NOT IN SUBDIVISION: \_\_\_\_\_ ACREAGE \_\_\_\_\_ SURVEY \_\_\_\_\_

The property is owned by ROBERT J. MUSULIN & RAQUEL MUSULIN

WITNESS MY HAND ON THIS 17 OF DAY OF January, 2025.

X [Signature]  
OWNER (SIGNATURE)


X [Signature]  
OWNER (SIGNATURE)

SWORN TO AND SUBSCRIBED BEFORE ME ON THIS 17 DAY OF January, 2025 BY

ROBERT J. MUSULIN  
OWNER NAME (PRINTED)

RAQUEL MUSULIN  
OWNER NAME (PRINTED)

[Signature]  
Notary Public Signature



Filed and Recorded  
Official Public Records  
Bobbie Koepf, County Clerk  
Comal County, Texas  
01/22/2025 08:11:03 AM  
TRACY 2 Pages(s)  
202506001870

 Bobbie Koepf

# ON-SITE SEWERAGE FACILITY SOIL EVALUATION REPORT INFORMATION

Date Soil Survey Performed: December 30, 2024

Site Location: 95 SUN VALLEY DRIVE - SUN VALLEY VILLAGE, UNIT 2, LOT 97 & 99

Proposed Excavation Depth: 18"-36"


**Requirements:**

At least two soil excavations must be performed on the site, at opposite ends of the proposed disposal area. Locations of soil boring or dug pits must be shown on the site drawing. For subsurface disposal, soil evaluations must be performed to a depth of at least two feet below the proposed excavation depth. For surface disposal, the surface horizon must be evaluated. Describe each soil horizon and identify any restrictive features on the form. Indicate depths where features appear.


SOIL BORING NUMBER <u>1</u>						
Depth (Feet)	Texture Class	Soil Texture	Gravel Analysis	Drainage (Mottles/ Water Table)	Restrictive Horizon	Observations
0	III	CLAY LOAM				BROWN
1						
2						
3	III	SILTY LOAM	N/A	NONE OBSERVED	NONE OBSERVED	TAN CALICHE
4						
5						

SOIL BORING NUMBER <u>2</u>						
Depth (Feet)	Texture Class	Soil Texture	Gravel Analysis	Drainage (Mottles/ Water Table)	Restrictive Horizon	Observations
0	SAME	AS	ABOVE			
1						
2						
3						
4						
5						

I certify that the findings of this report are based on my field observations and are accurate to the best of my ability.

  
 \_\_\_\_\_  
 Greg W. Johnson, P.E. 67587-F2585, S.E. 11561

12/30/24  
 \_\_\_\_\_  
 Date



**FIRM #2585**

**OSSF SOIL EVALUATION REPORT INFORMATION**

Date: December 31, 2024

**Applicant Information:**

Name: ROBERT J. MUSULIN & RAQUEL MUSULIN  
Address: 95 SUN VALLEY DRIVE  
City: SPRING BRANCH State: TX  
Zip Code: 78070 Phone: 830-708-8603

**Site Evaluator Information:**

Name: Greg W. Johnson, P.E., R.S., S.E. 11561  
Address: 170 Hollow Oak  
City: New Braunfels State: Texas  
Zip Code: 78132 Phone & Fax: (830)905-2778

**Property Location:**

Lot \* Unit 2 Blk  Subd. SUN VALLEY VILLAGE  
Street Address: 95 SUN VALLEY DRIVE  
City: SPRING BRANCH Zip Code: 78070  
Additional Info.: \* LOTS 97 & 99

**Installer Information:**

Name: \_\_\_\_\_  
Company: \_\_\_\_\_  
Address: \_\_\_\_\_  
City: \_\_\_\_\_ State: \_\_\_\_\_  
Zip Code: \_\_\_\_\_ Phone: \_\_\_\_\_

**Topography:** Slope within proposed disposal area: 8-12 %  
Presence of 100 yr. Flood Zone: YES \_\_\_ NO X  
Existing or proposed water well in nearby area: YES X NO \_\_\_ >100'  
Presence of adjacent ponds, streams, water impoundments: YES \_\_\_ NO X  
Presence of upper water shed: YES \_\_\_ NO X  
Organized sewage service available to lot: YES \_\_\_ NO X

**Design Calculations for Leaching Chambers:**

**Commercial**

Q= \_\_\_\_\_ GPD

Residential Water conserving fixtures to be utilized? Yes X No \_\_\_\_\_

Number of Bedrooms the septic system is sized for: 4 Total sq. ft. living area 3486

Q gal/day = (Bedrooms +1) \* 75 GPD

Q = (4 + 1) \* 75 - (20 %) = 300 + 60 SHOP

**PERSONAL SHOP HAS 800 SF LIVING**

A = Q/Ra = 360 / 0.20 = 1800 sq. ft.

Tank Size = (~3 \* Q) = 1000+750 Gal. Dual Comp.


**Excavation Length & Width**

L = 0.75A/(W+2) (<3' Wide) = 1350 / 5 = 270' of 36" WIDE **USING 54 - 5' HANCOR CHAMBERS**


I HAVE PERFORMED A THOROUGH INVESTIGATION BEING A REGISTERED PROFESSIONAL ENGINEER AND SITE EVALUATOR IN ACCORDANCE WITH CHAPTER 285, SUBCHAPTER D, §285.30, & §285.40 (REGARDING RECHARGE FEATURES), TEXAS COMMISSION OF ENVIRONMENTAL QUALITY (EFFECTIVE DECEMBER 27, 2016).

  
\_\_\_\_\_  
GREG W. JOHNSON, P.E. 67587 - F#2585

12/31/24  
\_\_\_\_\_  
DATE



**FIRM #2585**



INSTALL 1350sf OF FIELD USING 54 HANCOR LEACHING CHAMBER PANELS WITH BULKHEADS

\*USE TWO WAY CLEAN OUT  
 \*\*USE SCH-40 OR SDR-26 TO TANK

X= TEST HOLE

SUN VALLEY DRIVE

MOORE DRIVE



OWNER: ROBERT J. & RAQUEL MUSULIN		DRAWN BY: EJS III/GWJ	
STREET ADDRESS: 95 SUN VALLEY DRIVE			
LEGAL DESC: SUN VALLEY VILLAGE	UNIT/SECTION/PHASE: 2	BLOCK:	LOT: 97 & 99
PREPARED BY: GREG W. JOHNSON, P.E. F#002585	SCALE: 1"=100'	DATE: 12/31/2024	REVISED:

INSTALL 1350sf OF FIELD USING 54  
 HANCOR LEACHING CHAMBER  
 PANELS WITH BULKHEADS



\*USE TWO WAY CLEAN OUT  
 \*\*USE SCH-40 OR SDR-26 TO TANK

X= TEST HOLE




LOT 99



LOT 97




OWNER: ROBERT J. & RAQUEL MUSULIN		DRAWN BY: EJS III/GWJ	
STREET ADDRESS: 95 SUN VALLEY DRIVE			
LEGAL DESC: SUN VALLEY VILLAGE	UNIT/SECTION/PHASE: 2	BLOCK:	LOT: 97 & 99
PREPARED BY: GREG W. JOHNSON, P.E. F#002585	SCALE: 1"=50'	DATE: 12/31/2024	REVISED:



**TYPICAL TWO COMPARTMENT SEPTIC TANK**



**HANCOR ARC 36 LEACHING CHAMBER DETAIL**



**HANCOR ARC 36 LEACHING CHAMBER DETAIL**

4013000602

Warranty Deed



201106043873 12/21/2011 08:38:58 AM 1/1

Notice of confidentiality rights: If you are a natural person, you may remove or strike any or all of the following information from any instrument that transfers an interest in real property before it is filed for record in the public records: your Social Security number or your driver's license number.

Date: December 16, 2011

Grantor: VERONICA CONSUELO ULRICH and VIOLANTE ULRICH

Grantor's Mailing Address:

Grantee: ROBERT J. MUSULIN and RAQUEL MUSULIN

Grantee's Mailing Address: 3239 Comal Springs, Canyon Lake, Texas 78133

Consideration: TEN DOLLARS (\$10.00) and other good and valuable consideration, the receipt and sufficiency of which are hereby acknowledged.

Property (including any improvements): Lots 95 and 97, Sun Valley Village, Unit Two, Comal County, Texas, according to plat thereof recorded Volume 4, Pages 38-39, Map and Plat Records of Comal County, Texas.

Reservations from and Exceptions to Conveyance and Warranty: All effective and enforceable restrictions, reservations, conditions, covenants and easements of record in the Deed and Real Property Records of Comal County, Texas.

Grantor, for the Consideration and subject to the Reservations from Conveyance and the Exceptions to Conveyance and Warranty, grants, sells, and conveys to Grantee the Property, together with all and singular the rights and appurtenances thereto in any way belonging, to have and to hold it to Grantee and Grantee's heirs, successors, and assigns forever. Grantor binds Grantor and Grantor's heirs and successors to warrant and forever defend all and singular the Property to Grantee and Grantee's heirs, successors, and assigns against every person whomsoever lawfully claiming or to claim the same or any part thereof, except as to the Reservations from Conveyance and the Exceptions to Conveyance and Warranty.

When the context requires, singular nouns and pronouns include the plural


VERONICA CONSUELO ULRICH

VIOLANTE ULRICH

STATE OF TEXAS  
COUNTY OF BEXAR

This instrument was acknowledged before me on this 16 day of December, 2011, by VERONICA CONSUELO ULRICH and VIOLANTE ULRICH.

Notary Public, State of Texas



AFTER RECORDING RETURN TO:  
ROBERT J. MUSULIN and RAQUEL MUSULIN  
3239 Comal Springs  
Canyon Lake, Texas 78133

Filed and Recorded  
Official Public Records  
Joy Streater, County Clerk  
Comal County, Texas  
12/21/2011 08:38:58 AM  
CASHFOUR  
201106043873

ATC-BULVERDE BRANCH

↘ **First American Title**

**GF #** 1709948



201206024395 07/16/2012 03:24:55 PM 1/3

**3**  
**TM**  
\$ ~~NOTICE OF CONFIDENTIALITY RIGHTS: IF YOU ARE A NATURAL PERSON, YOU MAY REMOVE OR STRIKE ANY OR ALL OF THE FOLLOWING INFORMATION FROM ANY INSTRUMENT THAT TRANSFERS AN INTEREST IN REAL PROPERTY BEFORE IT IS FILED FOR RECORD IN THE PUBLIC RECORDS: YOUR SOCIAL SECURITY NUMBER OR YOUR DRIVER'S LICENSE NUMBER.~~

**WARRANTY DEED WITH VENDOR'S LIEN**

**Date:** July 10, 2012

**Grantor:** Larry Grona

**Grantor's Mailing Address:**

**Grantee:** Robert J. Musulin and Raquel Musulin

**Grantee's Mailing Address:**

**Consideration:** TEN AND NO/100 DOLLARS and other good and valuable consideration to the undersigned in hand paid by the Grantee herein named, the receipt of which is hereby acknowledged, and the further consideration of a note of even date that is in the principal amount of \$48,750.00 and is executed by Grantee, payable to the order of Broadway National Bank. The note is secured by a vendor's lien retained in favor of Broadway National Bank in this deed and by a deed of trust of even date, from Grantee to D'Layne Rhynsburger, Trustee.

Broadway National Bank, at Grantee's request, having paid in cash to Grantor that portion of the purchase price of the property that is evidenced by the note described, the vendor's lien and superior title to the property are retained for the benefit of Broadway National Bank and are transferred to Broadway National Bank without recourse on Grantor.

**Property (including any improvements):**

**Lot 99, SUN VALLEY VILLAGE, UNIT TWO, Comal County, Texas, according to map or plat thereof, recorded in Volume 4, Pages 38-39, of the map and plat records of Comal County, Texas.**

**Reservations From and Exceptions to Conveyance and Warranty:** This conveyance, however, is made and accepted subject to the following matters, to the extent same are in effect at this time: any and all restrictions, covenants, assessments, reservations, outstanding mineral interests held by third parties, conditions, and easements, if any, relating to the hereinabove described property, but

only to the extent they are still in effect and shown of record in the hereinabove mentioned County and State or to the extent that they are apparent upon reasonable inspection of the property; and to all zoning laws, regulations and ordinances of municipal and/or other governmental authorities, if any, but only to the extent they are still in effect and relating to the hereinabove described property. Ad valorem taxes on said property for the current year, having been prorated, the payment thereof is assumed by Grantee.

The Contract between Grantor as the Seller and Grantee as the Buyer, if any, may contain limitations as to warranty or other agreed matters; to the extent that the Contract provides for any such limitations or other agreed matters to survive the closing and this conveyance, then such limitations or other agreed matters are hereby deemed incorporated by reference. The warranty of title contained in this Deed is hereby expressly excluded from the limitations or other agreed matters referenced in this paragraph.

Grantor, for the consideration, receipt of which is acknowledged, and subject to the reservations from and exceptions to conveyance and warranty, grants, sells and conveys to Grantee the property, together with all and singular the rights and appurtenances thereto in any wise belonging, to have and hold it to Grantee, Grantee's heirs, executors, administrators, successors or assigns forever. Grantor binds Grantor and Grantor's heirs, executors, administrators and successors to warrant and forever defend all and singular the property to Grantee and Grantee's heirs, executors, administrators, successors and assigns against every person whomsoever lawfully claiming or to claim the same or any part thereof, except as to the reservations from and exceptions to conveyance and warranty.

The vendor's lien against and superior title to the property are retained until each note described is fully paid according to its terms, at which time this deed shall become absolute.

When the context requires, singular nouns and pronouns include the plural.

  
Larry Groha

ACKNOWLEDGMENT

STATE OF TEXAS

§

COUNTY OF BEXAR

§

§

This instrument was acknowledged before me on this the 10<sup>th</sup> day of July 2012, by Larry Grona.


**STEPHANIE C TREVINO**  
 Notary Public  
 STATE OF TEXAS  
 My Comm. Exp. 03-18-16  
*Stephanie C Trevino*  
 Notary Public State of Texas

PREPARED IN THE OFFICE OF:  
Law Office of Kenneth R. Cooper  
14607 San Pedro, Suite 130  
San Antonio, TX 78232-4356


AFTER RECORDING RETURN TO:  
Robert J. Musulin and Raquel Musulin  
3239 Comal Springs  
Canyon Lake, TX 78133

*Linda Abbott*  
*First American Title*  
*10999 IH10 W Ste. 850*  
*San Antonio, TX*  
*78230*

Filed and Recorded  
Official Public Records  
Joy Streater, County Clerk  
Comal County, Texas  
07/16/2012 03:24:55 PM  
TAMMY 3 Page(s)  
201208024396



*Joy Streater*



SEE PAGE 40

