

Comal County Environmental Health

OSSF Inspection Sheet

Installer Name: _____

OSSF Installer #: _____

1st Inspection Date: _____

2nd Inspection Date: _____

3rd Inspection Date: _____

Inspector Name: _____

Inspector Name: _____

Inspector Name: _____

Permit#:

Address:

No.	Description	Answer	Citations	Notes	1st Insp.	2nd Insp.	3rd Insp.
1	SITE AND SOIL CONDITIONS & SETBACK DISTANCES Site and Soil Conditions Consistent with Submitted Planning Materials		285.31(a) 285.30(b)(1)(A)(iv) 285.30(b)(1)(A)(v) 285.30(b)(1)(A)(iii) 285.30(b)(1)(A)(ii) 285.30(b)(1)(A)(i)				
2	SITE AND SOIL CONDITIONS & SETBACK DISTANCES Setback Distances Meet Minimum Standards		285.91(10) 285.30(b)(4) 285.31(d)				
3	SEWER PIPE Proper Type Pipe from Structure to Disposal System (Cast Iron, Ductile Iron, Sch. 40, SDR 26)		285.32(a)(1)				
4	SEWER PIPE Slope from the Sewer to the Tank at least 1/8 Inch Per Foot		285.32(a)(3)				
5	SEWER PIPE Two Way Sanitary - Type Cleanout Properly Installed (Add. C/O Every 100' &/or 90 degree bends)		285.32(a)(5)				
6	PRETREATMENT Installed (if required) TCEQ Approved List PRETREATMENT Septic Tank(s) Meet Minimum Requirements		285.32(b)(1)(G) 285.32(b)(1)(E)(iii) 285.32(b)(1)(E)(iv) 285.32(b)(1)(F) 285.32(b)(1)(B) 285.32(b)(1)(C)(i) 285.32(b)(1)(C)(ii) 285.32(b)(1)(D) 285.32(b)(1)(E) 285.32(b)(1)(A) 285.32(b)(1)(E)(ii)(II) 285.32(b)(1)(E)(i) 285.32(b)(1)(E)(ii)(I)				
7	PRETREATMENT Grease Interceptors if required for commercial		285.34(d)				

Inspector Notes:

**Comal County Environmental Health
OSSF Inspection Sheet**

No.	Description	Answer	Citations	Notes	1st Insp.	2nd Insp.	3rd Insp.
8	SEPTIC TANK Tank(s) Clearly Marked SEPTIC TANK If Single Tank, 2 Compartments Provided with Baffle SEPTIC TANK Inlet Flowline Greater than 3" and " T " Provided on Inlet and Outlet SEPTIC TANK Septic Tank(s) Meet Minimum Requirements		285.32(b)(1) (E) 285.91(2) 285.32(b)(1) (F) 285.32(b)(1)(E) (iii) 285.32(b)(1)(E)(ii) (II) 285.32(b)(1)(E)(ii) (I) 285.32(b)(1)(E) (i) 285.32(b)(1) (D) 285.32(b)(1)(C) (ii) 285.32(b)(1)(C) (i) 285.32(b)(1) (B) 285.32(b)(1) (A) 285.32(b)(1)(E)(iv)				
9	ALL TANKS Installed on 4" Sand Cushion/ Proper Backfill Used		285.32(b)(1)(F) 285.32(b)(1)(G) 285.34(b)				
10	SEPTIC TANK Inspection / Clean Out Port & Risers Provided on Tanks Buried Greater than 12" Sealed and Capped		285.38(d)				
11	SEPTIC TANK Secondary restraint system provided SEPTIC TANK Riser permanently fastened to lid or cast into tank SEPTIC TANK Riser cap protected against unauthorized intrusions		285.38(d) 285.38(e)				
12	SEPTIC TANK Tank Volume Installed						
13	PUMP TANK Volume Installed						
14	AEROBIC TREATMENT UNIT Size Installed						
15	AEROBIC TREATMENT UNIT Manufacturer AEROBIC TREATMENT UNIT Model Number						
16	DISPOSAL SYSTEM Absorptive		285.33(a)(4) 285.33(a)(1) 285.33(a)(2) 285.33(a)(3)				
17	DISPOSAL SYSTEM Leaching Chamber		285.33(a)(1) 285.33(a)(3) 285.33(a)(4) 285.33(a)(2)				
18	DISPOSAL SYSTEM Evapo-transpirative		285.33(a)(3) 285.33(a)(4) 285.33(a)(1) 285.33(a)(2)				

**Comal County Environmental Health
OSSF Inspection Sheet**

No.	Description	Answer	Citations	Notes	1st Insp.	2nd Insp.	3rd Insp.
19	DISPOSAL SYSTEM Drip Irrigation		285.33(c)(3)(A)-(F)				
20	DISPOSAL SYSTEM Soil Substitution		285.33(d)(4)				
21	DISPOSAL SYSTEM Pumped Effluent		285.33(a)(4) 285.33(a)(3) 285.33(a)(1) 285.33(a)(2)				
22	DISPOSAL SYSTEM Gravelless Pipe		285.33(a)(3) 285.33(a)(2) 285.33(a)(4) 285.33(a)(1)				
23	DISPOSAL SYSTEM Mound		285.33(a)(3) 285.33(a)(1) 285.33(a)(2) 285.33(a)(4)				
24	DISPOSAL SYSTEM Other (describe) (Approved Design)		285.33(d)(6) 285.33(c)(4)				
25	DRAINFIELD Absorptive Drainline 3" PVC or 4" PVC						
26	DRAINFIELD Area Installed						
27	DRAINFIELD Level to within 1 inch per 25 feet and within 3 inches over entire excavation		285.33(b)(1)(A)(v)				
28	DRAINFIELD Excavation Width DRAINFIELD Excavation Depth DRAINFIELD Excavation Separation DRAINFIELD Depth of Porous Media DRAINFIELD Type of Porous Media						
29	DRAINFIELD Pipe and Gravel - Geotextile Fabric in Place		285.33(b)(1)(E)				
30	DRAINFIELD Leaching Chambers DRAINFIELD Chambers - Open End Plates w/Splash Plate, Inspection Port & Closed End Plates in Place (per manufacturers spec.)		285.33(c)(2)				
31	LOW PRESSURE DISPOSAL SYSTEM Adequate Trench Length & Width, and Adequate Separation Distance between Trenches		285.33(d)(1)(C)(i)				

**Comal County Environmental Health
OSSF Inspection Sheet**

No.	Description	Answer	Citations	Notes	1st Insp.	2nd Insp.	3rd Insp.
32	EFFLUENT DISPOSAL SYSTEM Utilized Only by Single Family Dwelling EFFLUENT DISPOSAL SYSTEM Topographic Slopes < 2.0% EFFLUENT DISPOSAL SYSTEM Adequate Length of Drain Field (1000 Linear ft. for 2 bedrooms or Less & an additional 400 ft. for each additional bedroom) EFFLUENT DISPOSAL SYSTEM Lateral Depth of 18 inches to 3 ft. & Vertical Separation of 1ft on bottom and 2 ft. to restrictive horizon and ground water respectfully EFFLUENT DISPOSAL SYSTEM Lateral Drain Pipe (1.25 - 1.5" dia.) & Pipe Holes (3/16 - 1/4" dia. Hole Size) 5 ft. Apart		285.33(b)(3)(A) 285.33(b)(3)(A) 285.33(b)(3)(B)285.91(13) 285.33(b)(3)(D) 285.33(b)(3)(F)				
33	AEROBIC TREATMENT UNIT Is Aerobic Unit Installed According to Approved Guidelines.		285.32(c)(1)				
34	AEROBIC TREATMENT UNIT Inspection/Clean Out Port & Risers Provided AEROBIC TREATMENT UNIT Secondary restraint system provided AEROBIC TREATMENT UNIT Riser permanently fastened to lid or cast into tank AEROBIC TREATMENT UNIT Riser cap protected against unauthorized intrusions						
35	AEROBIC TREATMENT UNIT Chlorinator Properly Installed with Chlorine Tablets in Place.						
36	PUMP TANK Is the Pump Tank an approved concrete tank or other acceptable materials & construction PUMP TANK Sampling Port Provided in the Treated Effluent Line PUMP TANK Check Valve and/or Anti- Siphon Device Present When Required PUMP TANK Audible and Visual High Water Alarm Installed on Separate Circuit From Pump						
37	PUMP TANK Inspection/Clean Out Port & Risers Provided PUMP TANK Secondary restraint system provided PUMP TANK Riser permanently fastened to lid or cast into tank PUMP TANK Riser cap protected against unauthorized intrusions						
38	PUMP TANK Secondary restraint system provided						
39	PUMP TANK Electrical Connections in Approved Junction Boxes / Wiring Buried						

**Comal County Environmental Health
OSSF Inspection Sheet**

No.	Description	Answer	Citations	Notes	1st Insp.	2nd Insp.	3rd Insp.
40	APPLICATION AREA Distribution Pipe, Fitting, Sprinkler Heads & Valve Covers Color Coded Purple?		285.33(d)(2)(G)(iii)(II) 285.33(d)(2)(G)(iii)(III) 285.33(d)(2)(G)(v) 285.33(d)(2)(G)(iii) 285.33(d)(2)(G)(iv) 285.33(d)(2)(G)(i) 285.33(d)(2)(G)(ii) 285.33(d)(2)(G)(iii)(I)				
41	APPLICATION AREA Low Angle Nozzles Used / Pressure is as required APPLICATION AREA Acceptable Area, nothing within 10 ft of sprinkler heads? APPLICATION AREA The Landscape Plan is as Designed		285.33(d)(2)(G) (i)285.33(d)(2) (A)285.33(d)(2)(F)				
42	APPLICATION AREA Area Installed						
43	PUMP TANK Meets Minimum Reserve Capacity Requirements						
44	PUMP TANK Material Type & Manufacturer						
45	PUMP TANK Type/Size of Pump Installed						



COMAL COUNTY

ENGINEER'S OFFICE

Permit of Authorization to Construct an On-Site Sewage Facility Permit Valid For One Year From Date Issued

Permit Number: 118798
Issued This Date: 08/04/2025
This permit is hereby given to: Richard and Veronica Griffin

To start construction of a private, on-site sewage facility located at:

434 GLENN DR
CANYON LAKE, TX 78133

Subdivision: Canyon Lake Hills
Unit: 3
Lot: 1562R
Block: -
Acreage: 0.6400

APPROVED MINIMUM SIZES AS PER ATTACHED DESIGN

Type of System: Aerobic
Surface Irrigation

This permit gives permission for the construction of the above referenced on-site facility to commence. Installation must be completed by an installer holding a valid registration card from the Texas Commission on Environmental Quality (TCEQ). Installation and inspection must comply with current TCEQ and Comal County requirements.

Call (830) 608-2090 to schedule inspections.



COMAL COUNTY
ENGINEER'S OFFICE

**OSSF DEVELOPMENT APPLICATION
CHECKLIST**

Staff will complete shaded items

		118798
Date Received	Initials	Permit Number

Instructions:

Place a check mark next to all items that apply. For items that do not apply, place "N/A". This OSSF Development Application Checklist **must** accompany the completed application.

OSSF Permit

- ☒ Completed Application for Permit for Authorization to Construct an On-Site Sewage Facility and License to Operate
- ☒ Site/Soil Evaluation Completed by a Certified Site Evaluator or a Professional Engineer
- ☒ Planning Materials of the OSSF as Required by the TCEQ Rules for OSSF Chapter 285. Planning Materials shall consist of a scaled design and all system specifications.
- ☒ Required Permit Fee - See Attached Fee Schedule
- ☒ Copy of Recorded Deed
- ☒ Surface Application/Aerobic Treatment System
 - ☒ Recorded Certification of OSSF Requiring Maintenance/Affidavit to the Public
 - ☒ Signed Maintenance Contract with Effective Date as Issuance of License to Operate

I affirm that I have provided all information required for my OSSF Development Application and that this application constitutes a completed OSSF Development Application.

Richard Griffin + Veronica Griffin
Signature of Applicant

6-30-2025
Date

___ COMPLETE APPLICATION	
Check No. _____	Receipt No. _____

INCOMPLETE APPLICATION
___ (Missing Items Circled, Application Refused)



COMAL COUNTY
ENGINEER'S OFFICE

ON-SITE SEWAGE FACILITY APPLICATION

195 DAVID JONAS DR
NEW BRAUNFELS, TX 78132
(830) 608-2090
WWW.CCEO.ORG

Date _____

Permit Number 118798

1. APPLICANT / AGENT INFORMATION

Owner Name Richard and Veronica Griffin
Mailing Address 434 Glenn Dr
City, State, Zip Canyon Lake, TX 78133
Phone # _____
Email _____

Agent Name Doug Dowlearn R.S.
Agent Address PO BOX 212
City, State, Zip Bulverde, TX 78163
Phone # 210-878-8100
Email TXSEPTIC@GMAIL.COM

2. LOCATION

Subdivision Name Canyon Lake Hills Unit 3 Lot 1562R Block -
Survey Name / Abstract Number _____ Acreage .64
Address 434 Glenn Dr City Canyon Lake State TX Zip 78133

3. TYPE OF DEVELOPMENT

☒ Single Family Residential

Type of Construction (House, Mobile, RV, Etc.) HOUSE

Number of Bedrooms 3

Indicate Sq Ft of Living Area <2500

☐ Non-Single Family Residential

(Planning materials must show adequate land area for doubling the required land needed for treatment units and disposal area)

Type of Facility _____

Offices, Factories, Churches, Schools, Parks, Etc. - Indicate Number Of Occupants _____

Restaurants, Lounges, Theaters - Indicate Number of Seats _____

Hotel, Motel, Hospital, Nursing Home - Indicate Number of Beds _____

Travel Trailer/RV Parks - Indicate Number of Spaces _____

Miscellaneous _____

Estimated Cost of Construction: \$ 0 (Structure Only)

Is any portion of the proposed OSSF located in the United States Army Corps of Engineers (USACE) flowage easement?

☐ Yes ☒ No (If yes, owner must provide approval from USACE for proposed OSSF improvements within the USACE flowage easement)

Source of Water ☒ Public ☐ Private Well ☐ Rainwater

4. SIGNATURE OF OWNER

By signing this application, I certify that:

- The completed application and all additional information submitted does not contain any false information and does not conceal any material facts. I certify that I am the property owner or I possess the appropriate land rights necessary to make the permitted improvements on said property.
- Authorization is hereby given to the permitting authority and designated agents to enter upon the above described property for the purpose of site/soil evaluation and inspection of private sewage facilities..
- I understand that a permit of authorization to construct will not be issued until the Floodplain Administrator has performed the reviews required by the Comal County Flood Damage Prevention Order.
- I affirmatively consent to the online posting/public release of my e-mail address associated with this permit application, as applicable.

Richard Griffin + Veronica Griffin
Signature of Owner

6-30-2025
Date



Planning Materials & Site Evaluation as Required Completed By _____

System Description _____

Size of Septic System Required Based on Planning Materials & Soil Evaluation

Tank Size(s) (Gallons) _____ Absorption/Application Area (Sq Ft) _____

Gallons Per Day (As Per TCEQ Table III) _____

(Sites generating more than 5000 gallons per day are required to obtain a permit through TCEQ.)

Is the property located over the Edwards Recharge Zone? ☐ Yes ☐ No

(If yes, the planning materials must be completed by a Registered Sanitarian (R.S.) or Professional Engineer (P.E.))

Is there an existing TCEQ approved WPAP for the property? ☐ Yes ☐ No

(If yes, the R.S. or P.E. shall certify that the OSSF design complies with all provisions of the existing WPAP.)

Is there at least one acre per single family dwelling as per 285.40(c)(1)? ☐ Yes ☐ No

If there is no existing WPAP, does the proposed development activity require a TCEQ approved WPAP? ☐ Yes ☐ No

(If yes, the R.S. or P.E. shall certify that the OSSF design will comply with all provisions of the proposed WPAP. A Permit to Construct will not be issued for the proposed OSSF until the proposed WPAP has been approved by the appropriate regional office.)

Is the property located over the Edwards Contributing Zone? ☐ Yes ☐ No

Is there an existing TCEQ approval CZP for the property? ☐ Yes ☐ No

(If yes, the P.E. or R.S. shall certify that the OSSF design complies with all provisions of the existing CZP.)

If there is no existing CZP, does the proposed development activity require a TCEQ approved CZP? ☐ Yes ☐ No

(If yes, the R.S. or P.E. shall certify that the OSSF design will comply with all provisions of the proposed CZP. A Permit to Construct will not be issued for the proposed OSSF until the CZP has been approved by the appropriate regional office.)

Is this property within an incorporated city? ☐ Yes ☐ No

If yes, indicate the city: _____

By signing this application, I certify that:

- The information provided above is true and correct to the best of my knowledge.
- I affirmatively consent to the online posting/public release of my e-mail address associated with this permit application, as applicable.

Signature of Designer

Date



202506019966 06/30/2025 04:07:30 PM 1/1

**COUNTY OF COMAL
STATE OF TEXAS**

AFFIDAVIT TO THE PUBLIC

CERTIFICATION OF OSSF REQUIRING MAINTENANCE

According to Texas Commission on Environmental Quality (TCEQ) Rules for On-Site Sewage Facilities (OSSFs), this document is filed in the Deed Records of Comal County, Texas.

I
The Texas Health and Safety Code, Chapter 366 authorizes the Texas Commission on Environmental Quality (TCEQ) to regulate on-site sewage facilities (OSSFs). Additionally, the Texas Water Code (TWC), § 5.012 and § 5.013, give the commission primary responsibility for implementing the laws of the State of Texas relating to water and adopting rules necessary to carry out its powers and duties under the TWC. The commission, under the authority of the TWC and the Texas Health and Safety Code, requires owners to provide notice to the public that certain types of OSSFs are located on specific pieces of property. To achieve this notice, the commission requires a recorded affidavit. Additionally, the owner must provide proof of the recording to the OSSF permitting authority. This recorded affidavit is not a representation or warranty by the commission of the suitability of this OSSF, nor does it constitute any guarantee by the commission that the appropriate OSSF was installed.

II
An OSSF requiring a maintenance contract, according to 30 Texas Administrative Code § 285.91 (12) will be installed on the property described as (insert legal description):

Canyon Lake Hills, Unit 3, Lot 1562R

The property is owned by (Insert owner's full name):

Richard A. Griffin and Veronica Griffin

This OSSF must be covered by a continuous maintenance contract for the first two years. After the initial two-year service policy, the owner of an aerobic treatment system for a single family residence shall either obtain a maintenance contract within 30 days or maintain the system personally.

Upon sale or transfer of the above described property, the permit for the OSSF shall be transferred to the buyer or new owner. A copy of the planning materials for OSSF may be obtained from **Comal County Engineer's Office**.


WITNESS BY HAND(S) ON THIS 30 DAY OF June 2025

Richard A. Griffin
Veronica Barta Griffin
Owner(s) signature(s)

Rick Griffin
Veronica Barta Griffin
(PRINTED NAME) /TITLE

SWORN TO AND SUBSCRIBED BEFORE ME ON THIS 30 DAY OF June, 2025

[Signature]
Notary Public, State of Texas
Notary's Printed Name: Darlene Martinez
My Commission Expires: 09/26/2026



Filed and Recorded
Official Public Records
Bobbie Koepp, County Clerk
Comal County, Texas
06/30/2025 04:07:30 PM
TERRI 1 Page(s)
202506019966



Bobbie Koepp

RECEIVED

By Brandon Olvera at 2:55 pm, Aug 04, 2025

DAVID WINTERS SEPTICS, LLC
1550 Oak Meadows
Canyon Lake, TX 78133
830-935-2477 OFFICE
830-935-2477 FAX
wintersseptics@gvvc.com

Routine Maintenance and Inspection Agreement

This **Work-for-Hire Agreement** (hereafter referred to as this "Agreement") is entered into, by, and between Richard and Veronica Griffin (referred to as "Client") and **David Winters Septic's, LLC, Inc.** (hereafter referred to as "Contractor") located at 434 Glenn Dr Date beginning on Issue Date of and contract ending 2 years from Issue Date of License to Operate License to Operate
By this agreement the Contractor agrees to render professional service, as described herein, and the Client agrees to fulfill the terms of this Agreement as described herein.

This agreement will provide for all required inspections, testing, and service for your Aerobic Treatment System.
The policy will include the following:

1. Three (3) inspections per year/service calls (at least one every four months), for a total of six (6) over the two-year period, including inspection, adjustment, and servicing of the mechanical, electrical and other applicable component parts to ensure proper function. This includes inspecting control panel, air pumps, air filters, diffuser operation, and replacing or repairing any component not found to be functioning correctly. Any alarm situations affecting the proper function of the Aerobic process will be addressed within a 48-hour time frame. This contract does not include labor on warranty and non-warranty parts.
2. An effluent quality inspection consisting of a visual check of color, turbidity, scum overflow and examination for odors. A test for chlorine residual and pH will be taken and reported as necessary.
3. If any improper operation is observed, which cannot be corrected at the time of the service visit, you will be notified on your inspection report.
4. The Client is responsible for the chlorine tablets and/or liquid chlorine; they must be filled before or during the service visit.
5. Any additional visits, inspections or sample collection required by specific Municipalities, Water/River Authorities, and County Agencies the TCEQ or any other authorized regulatory agency in your jurisdiction will not be covered by this policy.

At the conclusion of the initial service policy, our company will make available, for purchase on an annual basis, a continuing service policy cover **NORMAL** inspection, maintenance and repair.

The Homeowners Manual must be strictly followed or warranties are subject invalidation. Pumping of sludge build up is not covered by this policy and will result in additional charges.

This agreement does not cover any labor or parts for items which must be replaced due to acts of God, i.e., lightning strikes, high winds, flooding, freezing.

This agreement **DOES NOT COVER** materials or parts which must be replaced due to misuse or abuse of the system. These include but are not limited to: Sewage flows exceeding the recommended daily hydraulic design capabilities, Disposal of Non-Biodegradable materials, such as chemicals, grease or oil, sanitary napkins, tampons, baby wipes, disposable diapers, Clogs in the line between the house and the tank.

This agreement **DOES NOT COVER LABOR OR PARTS** for out- of- warranty items.

RECEIVED

By Brandon Olvera at 2:55 pm, Aug 04, 2025

ACCESS BY CONTRACTOR

The contractor or anyone authorized by the contractor may enter the property at reasonable times without prior notice for the purpose of service described above.

First 2 years
included with new

PAYMENT AGREEMENT

The client will pay compensation to the contractor for the services in the amount of install. This compensation shall be payable in one lump sum payment upon acceptance of this agreement. Payments not received within 30 days of the above described due date will be subject to a \$25.00 late penalty.

TERMINATION OF THIS AGREEMENT

Either party may terminate this agreement within 10 days of written notice in the event of substantial failure to perform in accordance with its terms by other party without fault of the terminating party. If this agreement is terminated, the contractor will immediately notify the appropriate health authority.

LIMIT OF LIABILITY

The Contractor will not be liable for indirect, consequential, incidental or punitive damages, whether in contract or any other theory. In no event shall the Contractor's liability for direct damages exceed the price for the services described in this agreement.

Permit # _____

The effective date of this initial maintenance agreement shall be the date the license to operate is issued.

Client

Richard and Veronica Griffin

Name

434 Glenn Dr

Address

Canyon Lake, TX 78133

City/State/Zip Code

Phone Number

Contractor

David Winters Septic's, LLC, Inc.

P.O. Box 195

Spring Branch, Texas 780170

Office 830-935-2477 Fax 830-935-2477

Richard Griffin Veronica Griffin

Signature of Client

David Winters

Signature of Contractor

Maintenance Provider LIC #MP0001686

Douglas R. Dowlearn
D.A.D. Services, Inc.
703 Oak Drive
Blanco, TX 78606
(210)240-2101
txseptic@gmail.com

July 1, 2025

RE: 434 Glenn Dr

To Whom It May Concern:


I am requesting a variance for the placement of a spray disposal area 10 feet from the property line, but less than 20 feet from the property line as Comal County regulations require. This variance is requested due to limited space. This setback complies with TCEQ CHAPTER 285 rules Table X. requirements. Equivalent protection will be maintained by including a battery backup to the timer clock to assure sprayers only spray during the predawn hours. In my professional opinion this variance will not pose a threat to the environment or public health.

If there are any questions or concerns, please contact me at 210.240.2101 or by email at txseptic@gmail.com.

Sincerely,



Douglas R. Dowlearn, R.S.



OSSF SOIL EVALUATION REPORT INFORMATION

Date: 7/1/2025

Applicant Information:

Name: Richard and Veronica Griffin

Address: 434 Glenn Dr

City, State & Zip Code: Canyon Lake, TX 78133

Phone:

Email:

Site Evaluator Information:

Name: Douglas R. Dowlearn

Company: D.A.D. Services, Inc.

Address: 703 Oak Drive

City, State & Zip: Blanco, TX 78606

Phone: (210)240-2101 **Fax:** (866)260-7687

Email: txseptic@gmail.com

Property Location:

Subdivision: Canyon Lake Hills Unit: 2 Lot: 1562R

Street/Road Address: 434 Glenn Dr

City: Canyon Lake **Zip:** 78133

Additional Info: Comal County

Depth	Texture Class	Soil Texture	Structure (For Class III – blocky, platy or massive)	Drainage (Mottles/Water Table)	Restrictive Horizon	Observation
Soil Boring #1 60"	III	0-6" Clay Loam 6"+ Limestone	Blocky	<30% Gravel	6"+ Limestone	Groundwater at 6"
Soil Boring #2 60"		Same as above				

DESIGN SPECIFICATIONS

Application Rate (RA): 0.064

OSSF is designed for: 3 Bedroom <2500 Sq. Ft House

240 Gallons per day required

An aerobic treatment/spray disposal system is to be utilized based on the site evaluation.

3750 sq. ft. disposal area required

600 gallon/day aerobic tank required

Calculations: Absorption Area: $Q/RA = 240/0.064 = 3750$ Sq. Ft.

FEATURES OF SITE AREA

Presence of 100-year flood zone: NO

Existing or proposed water well in nearby area: NO

Presence of adjacent ponds, streams, water impoundments: NO

Presence of upper water shed: NO

Organized sewage service available to lot: NO

I certify that the findings of this report are based on my field observations and are accurate to the best of my ability. The site evaluation and OSSF design are subject to approval by the TCEQ or the local authorized agent. The planning materials and the OSSF design should not be considered final until a permit to construct has been issued.

Site Evaluator:

NAME: Douglas R. Dowlearn, R.S.

Signature:



License No. OS9902

TDH: #2432

Designed for:
Griffin Richard A & Veronica

The installation site is at lot 1562R of the Canyon Lake Hills 3 subdivision in Comal County, TX. The proposed OSSF will treat the wastewater from a 3 Bedroom (< 2500 sq. ft.) residence. The proposed method of wastewater treatment is aerobic treatment with spray irrigation. This method was chosen because of unsuitable soil conditions.

PROPOSED SYSTEM:

A 3" or 4" PVC pipe will discharge from the residence to a pre-treatment tank, which flows into a 600 gpd aerobic treatment plant. The aerobic tank effluent flows to a 800 gallon storage/pump tank containing a liquid chlorinator and a single 20 gpm submersible pump. Distribution is set to spray in the pre-dawn hours of midnight to 5:00 am through 4 K-Rain Gear Driven pop-up sprinklers, with low angle (13 degrees) spray nozzles spraying at 40 psi. One sprinkler will spray a radius of 27 feet and 360 degrees of arc; One sprinkler will spray a radius of 24 feet and 360 degrees of arc; One sprinkler will spray a radius of 18 feet and 180 degrees of arc; One sprinkler will spray a radius of 20 feet and 180 degrees of arc; An audio and visual alarm monitoring both high water and aerator failure will be placed in a noticeable location.

DESIGN SPECIFICATIONS:

Daily Waste Flow: 240 gpd

Application rate: 0.064

Application area required: $240 / .064 = 3750$ sq. ft.

Application area utilized: 5235 sq. ft. - 504 sq. ft. (spray overlap) - 9 sq. ft. (impermeable tank lids) = 4722 sq. ft.

Pump tank reserve capacity: 80 gal minimum

SYSTEM COMPONENTS:

SCH 40 PVC sewer line

AquaKlear AKA600CA

500-gallon Pretreatment tank

600 GPD Aerobic Treatment Unit

800-gallon Pump tank with timed controls set to spray in the pre-dawn hours of midnight to 5:00 am

C-1 20X, Model no. 20XC1-05P4-2W115 (or equivalent) submersible pump

Liquid chlorinator

1" purple PVC supply line

4 K-Rain Gear Driven pop-up sprinklers




Brandon Olvera

LANDSCAPING:



The entire surface application area must consist of an area with vegetation capable of growth, before system start up. In the event the surface application area does not have vegetation capable of growth, the bare area shall be seeded or sodded. If the non-vegetative area consists of rock or caliche, 3" of class II or III soil, capable of growing and sustaining vegetative growth, will be added before it is seeded or sodded.

RECEIVED

By Brandon Olvera at 2:58 pm, Aug 04, 2025



KEY



SCALE 1" = 20'
PRINT SIZE 11" X 17"

NOTES:

- 1" SCH 40 PURPLE PIPE TO ALL SPRAY HEADS.
- 1" SCH 40 PURPLE PIPE WILL BE SLEEVED IN SCH 40 PVC PIPE WHERE IT CROSSES UNDER SURFACE IMPROVEMENTS, DRIVE, WALKWAY AND 5' BEYOND. THIS WILL PROVIDE EQUIVALENT PROTECTION FOR THE OSSF SETBACKS REQUIREMENTS OF TAC 285.
- 3" OR 4" SCH 40 PVC PIPE FROM STRUCTURE TO TANK.
- SEWER PIPE CONNECTING THE STRUCTURE TO THE TANK MUST HAVE AT MINIMUM 1/8" FALL PER 1'.
- TANK TO BE > 5' FROM STRUCTURES AND SURFACE IMPROVEMENTS. THIS WILL PROVIDE EQUIVALENT PROTECTION FOR THE SETBACK REQUIREMENTS OF TAC 285.
- CLEANOUT WITHIN 3' OF STRUCTURE.
- TOTAL SPRAY AREA = 5235 SF - 504 SF(SPRAY OVERLAP) - 9 SF(IMPERMEABLE TANK LIDS) = 4722 SF.
- TANK WILL BE WATER TIGHT AND MANUFACTURED ACCORDING TO ASTM DESIGNATION: C 1227.
- DRAINFIELD SHALL BE GREATER THAN 100' FROM PRIVATE WELLS, AND GREATER THAN 150' FROM PUBLIC WELLS. VERIFY WELL LOCATION(S) ON SITE.
- SPRAY HEADS SHALL BE LOCATED AT LEAST 10' AWAY FROM TREES WITHIN THE DISTRIBUTION AREA.
- ADD FLOTATION PREVENTION MEASURE BY BURYING TANK SO THAT THERE IS 24" OF SOIL OVER TANK.

ASSEMBLY DETAILS



Douglas R. Dowlearn

Dimensions:

Outside Height: 65.5"

Outside Width: 77"


Outside Length: 158.65"

General Notes:

1. Structure material to be precast concrete and steel.
2. Maximum burial depth is 30" from slab top to grade.
3. Treatment Capacity is 600 GPD. Trash Tank is 500 gallons. Pump Tank is 800 gallons.
4. BOD Loading = 1.2-1.8 lbs./day
5. Standard tablet chlorinator or optional liquid chlorinator. NSF approved chlorinators available.
6. 20" access riser with lid. Extension risers available.
7. 20 GPM, ½ HP effluent pump.
8. Thomas/HiBlow Air Compressor connected with ½" Sch 40 PVC pipe (Max. 50 Lft from plant).
9. AKA600CA with timed spray application (AKT Panel).

SEE NOTE 6

SEE NOTE 5



RECEIVED

By Brandon Olvera at 2:59 pm, Aug 04, 2025

13.44 GAL/IN

51" - 59.5" - RESERVE - 114.24 GALLONS

51" - ALARM ON

27" - 51" - WORKING LEVEL - 322.56 GALLONS

25" - 27" - ON/OFF TETHER - 26.88 GALLONS

0 - 25" SUMP - 336 GALLONS

NOTE: SET ON A TIMER TO DOSE IN PREDAWN HOURS BETWEEN MIDNIGHT TO 5AM.

AKA600CA

NOT TO SCALE

DESIGNED TO TREAT 600 GALLONS PER DAY

TRASH TANK: 500 GALLONS

AERATION ZONE: 633 GALLONS

CLARIFIER ZONE: 220 GALLONS

PUMP TANK: 800 GALLONS



AquaKlear, Inc.

876 N. Bierdeman Rd.

Pearl, MS 39208

877-936-7711

C1 SERIES

CISTERN PUMPS

Designed for use in gray water / filtered effluent service applications, the C1 Series cistern pump provides high performance and long life in less than ideal water conditions. The C1 Series pump is able to pass solids up to 1/8" without having a negative effect on the internal hydraulic components.


The pump's unique bottom suction design allows for maximum fluid drawdown without compromising durability or overall life, and it does not require the use of a flow induction sleeve. Intended specifically for use in a cistern or tank, C1 Series pumps are suitable for use in agricultural, residential, and commercial installations.



Franklin Electric

franklinwater.com

C1 Series Family Curve



FEATURES

- Supplied with a removable 5" base for secure and reliable mounting
- Bottom suction design
- Robust thermoplastic discharge head design resists breakage during installation and operation
- Single shell housing design provides a compact unit while ensuring cool and quiet operation
- Hydraulic components molded from high quality engineered thermoplastics
- Optimized hydraulic design allows for increased performance and decreased power usage
- All metal components are made of high grade stainless steel for corrosion resistance
- Available with a high quality 115 V or 230 V, ½ hp motor
- Fluid flows of 10, 20, and 30 gpm, with a max shut-off pressure of over 100 psi
- Heavy duty 600 V 10 foot SJ00W jacketed lead

APPLICATIONS

- Gray water pumping
- Filtered effluent service water pumping
- Water reclamation projects such as pumping from rain catchment basins
- Aeration and other foundation or pond applications
- Agriculture and livestock water pumping

ORDERING INFORMATION

C1 Series Pumps							
GPM	HP	Volts	Stage	Model No.	Order No.	Length (in)	Weight (lbs)
10	1/2	115	7	10C1-05P4-2W115	90301005	26	17
		230	7	10C1-05P4-2W230	90301010	26	17
20		115	5	20C1-05P4-2W115	90302005	25	16
		230	5	20C1-05P4-2W230	90302010	25	16
20X		115	6	20XC1-05P4-2W115	90302015	26	17
		230	6	20XC1-05P4-2W230	90302020	26	17
30		115	4	30C1-05P4-2W115	90303005	25	16
		230	4	30C1-05P4-2W230	90303010	25	16

Note: All units have 10 foot long SJ00W leads.



Franklin Electric

franklinwater.com

M1698 07-14

DAVID WINTERS SEPTICS, LLC
PO BOX 195
SPRING BRANCH, TX 78070
830-935-2477 OFFICE
830-935-2477 FAX
wintersseptics@gvvc.com

Routine Maintenance and Inspection Agreement

This Work-for-Hire Agreement (hereafter referred to as this "Agreement") is entered into, by, and between
Richard and Veronica Griffin (referred to as "Client") and David Winters Septic's, LLC, Inc.

and contract ending 2 years from Issue Date of License to Operate

By this agreement the Contractor agrees to render professional service, as described herein, and the Client agrees to fulfill the terms of this Agreement as described herein.

This agreement will provide for all required inspections, testing, and service for your Aerobic Treatment System.
The policy will include the following:

1. Three (3) inspections per year, once called for every four months for a total of two-year period, including inspection, adjustment, and service of the mechanical, electrical, and other applicable components to ensure proper function. This includes inspecting the control panel, air pump, air filter, blower, and repairing or replacing any components found to be inoperative. Any abnormal operation affecting the proper function of the aerobic process will be addressed within a 48-hour time frame. This agreement does not include a warranty and no-warranty parts.
2. An effluent quality inspection consisting of a visual check of color, clarity, scum, flow and expansion for odors. A test for chlorine and pH will be performed and reported as necessary.
3. If any improper operation is observed, it will be corrected and the name of the person who will be notified on your inspection report.
4. The Client is responsible for the chlorine tablets and/or liquid chlorine; they must be filled before or during the service visit.
5. Any additional visits, inspections or sample collection required by specific Municipalities, Water/River Authorities, and

At the conclusion of the initial service policy, our company will make available, for purchase on an annual basis, a continuing service policy cover NORMAL inspection, maintenance and repair.

The Homeowners Manual must be strictly followed or warranties are subject invalidation. Pumping of sludge build up is not covered by this policy and will result in additional charges.

This agreement does not cover any labor or parts for items which must be replaced due to acts of God, i.e., lightning strikes, high winds, flooding, freezing.

This agreement DOES NOT COVER materials or parts which must be replaced due to misuse or abuse of the system. These include but are not limited to: Sewage flows exceeding the recommended daily hydraulic design capabilities, Disposal of Non-Biodegradable materials, such as chemicals, grease or oil, sanitary napkins, tampons, baby wipes, disposable diapers, Clogs in the line between the house and the tank.

This agreement DOES NOT COVER LABOR OR PARTS for out-of-warranty items.

ACCESS BY CONTRACTOR

The contractor or anyone authorized by the contractor may enter the property at reasonable times without prior notice for the purpose of service described above.

First 2 years
included with new

PAYMENT AGREEMENT

The client will pay compensation to the contractor for the services in the amount of install. This compensation shall be payable in one lump sum payment upon acceptance of this agreement. Payments not received within 30 days of the above described due date will be subject to a \$25.00 late penalty.

TERMINATION OF THIS AGREEMENT

Either party may terminate this agreement within 10 days of written notice in the event of substantial failure to perform in accordance with its terms by other party without fault of the terminating party. If this agreement is terminated, the contractor will immediately notify the appropriate health authority.

LIMIT OF LIABILITY

The Contractor shall not be liable for direct, consequential, incidental or punitive damages arising from this contract or any other theory. In no event shall the Contractor's liability exceed the amount of the fee for the service provided in this agreement.

Permit # _____

The effective date of this agreement shall be the date the license to operate is issued.

Client

Richard and Veronica
Name

David Winters
Septic

434 Glenn Dr

P.O. Box 195

Address

Canyon Lake, TX 78133

Spring Branch, Texas 780170

City/State/Zip

Office 830-935-2477

Fax 830-935-2477

Phone Number

Richard Biggin

Veronica Biggin

David Winters

Signature of Client

Signature of Contractor

Maintenance Provider LIC #MP0001686

D.A.D SERVICES, INC.
DOUG DOWLEARN
PO BOX 212, BULVERDE, TX 78163
Designed for:
Griffin Richard A & Veronica

The installation site is at lot 1562 and lot 1563(replatted together) of the Canyon Lake Hills 3 subdivision in Comal County, TX. The proposed OSSF will treat the wastewater from a 3 Bedroom (< 2500 sq. ft.) residence. The proposed method of wastewater treatment is aerobic treatment with spray irrigation. This method was chosen because of unsuitable soil conditions.

PROPOSED SYSTEM:

A 3" or 4" PVC pipe will discharge from the residence to a pre-treatment tank which flows into a 600 gpd aerobic treatment plant. The aerobic tank effluent flows to a 800 gallon storage/pump tank containing a liquid chlorinator and a single 20 gpm submersible pump. Distribution is set to spray in the pre-dawn hours of midnight to 5:00 am through 4 K-Rain Gear Driven pop-up sprinklers, with low angle (13 degrees) spray nozzles spraying at 40 psi. One sprinkler will spray a radius of 27 feet and 360 degrees of arc; One sprinkler will spray a radius of 24 feet and 360 degrees of arc; One sprinkler will spray a radius of 18 feet and 180 degrees of arc; One sprinkler will spray a radius of 18 feet and 180 degrees of arc. The system will include a monitoring bell with water level indicator and a visual alarm.

DESIGN SPECIFICATIONS:

Daily Waste Flow: 240 gal
Application rate: 0.064 gal/sq. ft.
Application area: 240/.064 = 3750 sq. ft.
Application area: 5235 sq. ft. (overlap) = 4722 sq. ft.
Pump tank reservoir capacity: 80 gal min

SYSTEM COMPONENTS:

4" SCH 40 PVC sewer line

Aquaclear AA1000-CA

500-gallon Pretreatment tank

600 GPD Aerobic Treatment Unit


800-gallon Pump tank with timed controls set to spray in the pre-dawn hours of midnight to 5:00 am

C-1 20X, Model no. 20XC1-05P4-2W115 (or equivalent) submersible pump

Liquid chlorinator

1" purple PVC supply line


4 K-Rain Gear Driven pop-up sprinklers



Douglas R. Dowlearn

LANDSCAPING:

The entire surface application area must consist of an area with vegetation capable of growth, before system start up. In the event the surface application area does not have vegetation capable of growth, the bare area shall be seeded or sodded. If the non-vegetative area consists of rock or caliche, 3" of class II or III soil, capable of growing and sustaining vegetative growth, will be added before it is seeded or sodded.




NEW 600
GPD ATU

NOTE: ADD
FLOTATION
PREVENTION
MEASURE BY
BURYING TANK
SO THAT THERE
IS 24" OF SOIL
OVER TANK.

KEY


	- 2 WAY CLEANOUT
	- 10' OSSF SPRAY SETBACK FROM PROPERTY LINE
	- 1" SCH 40 PVC PURPLE PIPE
	- WATER LINE(VERIFY LOCATION ON SITE)
	- TEST HOLE
	- 600 GPD AEROBIC TREATMENT UNIT
	- DRIVE/WALKWAY
	- SPRAY OVERLAP = 504 SF

GRIFFIN RICHARD A & VERONICA
434 GLENN DR
CANYON LAKE, TX 78133
CANYON LAKE HILLS 3
LOT 1562 AND 1563(REPLATTED TOGETHER)
COMAL COUNTY



SCALE 1" = 20'
PRINT SIZE 11" X 17"

- NOTES:
- 1" SCH 40 PURPLE PIPE TO ALL SPRAY HEADS.
 - 1" SCH 40 PURPLE PIPE WILL BE SLEEVED IN SCH 40 PVC PIPE WHERE IT CROSSES UNDER SURFACE IMPROVEMENTS, DRIVE, WALKWAY AND 5' BEYOND. THIS WILL PROVIDE EQUIVALENT PROTECTION FOR THE OSSF SETBACKS REQUIREMENTS OF TAC 285.
 - 3" OR 4" SCH 40 PVC PIPE FROM STRUCTURE TO TANK.
 - SEWER PIPE CONNECTING THE STRUCTURE TO THE TANK MUST HAVE AT MINIMUM 1/8" FALL PER 1'.
 - TANK TO BE > 5' FROM STRUCTURES AND SURFACE IMPROVEMENTS. THIS WILL PROVIDE EQUIVALENT PROTECTION FOR THE SETBACK REQUIREMENTS OF TAC 285.
 - CLEANOUT WITHIN 3' OF STRUCTURE.
 - TOTAL SPRAY AREA = 5235 SF - 504 SF(SPRAY OVERLAP) - 9 SF(IMPERMEABLE TANK LIDS) = 4722 SF.
 - TANK WILL BE WATER TIGHT AND MANUFACTURED ACCORDING TO ASTM DESIGNATION: C 1227.
 - DRAINFIELD SHALL BE GREATER THAN 100' FROM PRIVATE WELLS, AND GREATER THAN 150' FROM PUBLIC WELLS. VERIFY WELL LOCATION(S) ON SITE.
 - SPRAY HEADS SHALL BE LOCATED AT LEAST 10' AWAY FROM TREES WITHIN THE DISTRIBUTION AREA.
 - ADD FLOTATION PREVENTION MEASURE BY BURYING TANK SO THAT THERE IS 24" OF SOIL OVER TANK.



ASSEMBLY DETAILS


Dimension

Outside Height: 65.5"
Outside Width: 77"
Outside Length: 158.65

General Notes:

1. Structure material to be precast concrete and steel.
2. Maximum burial depth is 30" from slab top to grade.
3. Treatment Capacity is 600 GPD. Trash Tank is 500 gallons. Pump Tank is 800 gallons.
4. BOD Loading = 1.2-1.8 lbs./day
5. Standard tablet chlorinator or optional liquid chlorinator. NSF approved chlorinators available.
6. 20" access riser with lid. Extension risers available.
7. 20 GPM, ½ HP effluent pump.
8. Thomas/HiBlow Air Compressor connected with 1" Sch 40 PVC pipe (Max. 50 Lft from plant).
9. AKA600CA with timed spray application (AKT Panel).

SEE NOTE 6



AKA600CA

NOT TO SCALE

DESIGNED TO TREAT 600 GALLONS PER DAY

TRASH TANK: 500 GALLONS

AERATION ZONE: 633 GALLONS

CLARIFIER ZONE: 220 GALLONS

PUMP TANK: 800 GALLONS



AquaKlear, Inc.

876 N. Bierdeman Rd.
Pearl, MS 39208
877-936-7711



COMAL COUNTY

ENGINEER'S OFFICE

RE: ***434 Glenn Dr.
Canyon Lake Hills 3
Lot 1562R***

Dear Property Owner & Agent,

Thank you for your submission. We have reviewed the planning materials for the referenced permit application, and unfortunately, they are insufficient. To proceed with processing this permit, we require the following:

- ✓. All documents need to reflect the amended lot number.
- ✓. Maintenance Contract:
 - ✓. 285.7(d)(1)(F): indicate the **business physical address** and telephone number for the maintenance provider.
- ✓. Pump tank details needs to be signed and sealed.
- 4. Revise accordingly and resubmit.

If you have any questions, you can email me or call the office.

Thank You,

| Brandon Olvera | Designated Representative OS0034792 |

| t: 830-608-2090 | e: olverb@co.comal.tx.us |

4/TC



201306049969 12/06/2013 09:25:31 AM 1/4

ATC-CF401300 2107 VJS

ATC-BULVERDE

NOTICE OF CONFIDENTIALITY RIGHTS: IF YOU ARE A NATURAL PERSON, YOU MAY REMOVE OR STRIKE ANY OR ALL OF THE FOLLOWING INFORMATION FROM ANY INSTRUMENT THAT TRANSFERS AN INTEREST IN REAL PROPERTY BEFORE IT IS FILED FOR RECORD IN THE PUBLIC RECORDS: YOUR SOCIAL SECURITY NUMBER OR YOUR DRIVER'S LICENSE NUMBER.

GENERAL WARRANTY DEED
(With Third Party Vendor's Lien)

THE STATE OF TEXAS

§

COUNTY OF COMAL

§

THAT **RICHARD C. EVANS**, hereinafter referred to as "Grantor" (whether one or more), for and in consideration of the sum of TEN AND NO/100 DOLLARS (\$10.00) and other good and valuable consideration to Grantor in hand paid by **RICHARD A. GRIFFIN AND VERONICA GRIFFIN, HUSBAND AND WIFE**, hereinafter referred to as "Grantee" (whether one or more), the receipt and sufficiency of which are hereby acknowledged and confessed, and for the further consideration of the execution and delivery by Grantee of one certain Promissory Note of even date herewith, in the original principal sum of **One Hundred Sixty-Six Thousand One Hundred Forty And No/100 Dollars (\$166,140.00)**, payable to the order of **CALIBER HOME LOANS, INC.**, hereinafter called "Mortgagee"; said Promissory Note being secured by a Vendor's Lien and the Superior Title herein retained and reserved in favor of Grantor and assigned and conveyed, without recourse, to Mortgagee, and also being secured by a Deed of Trust of even date herewith from Grantee to **THOMAS E. BLACK, JR.**, Trustee, reference to said Promissory Note and Deed of Trust being hereby made for all purposes; Grantor has GRANTED, SOLD AND CONVEYED, and by these presents does GRANT, SELL AND CONVEY, unto Grantee, the following described real property, to-wit:

SEE EXHIBIT A ATTACHED HERETO AND INCORPORATED HEREIN FOR ALL PURPOSES.

together with all improvements thereon, if any, and all rights, privileges, tenements, hereditaments, rights of way, easements, appendages and appurtenances, in anyway appertaining thereto, and all right, title, and interest of Grantor in and to any streets, ways, alleys, strips or gores of land adjoining the above described property or any part thereof (hereinafter referred to as the "Property").

TO HAVE AND TO HOLD the Property, together with all and singular the rights and appurtenances thereto in any wise belonging, unto Grantee and Grantee's heirs or assigns FOREVER. Grantor does hereby bind Grantor and Grantor's heirs, executors, and administrators TO WARRANT AND FOREVER DEFEND all and singular the said Property unto Grantee and Grantee's heirs and assigns against every person whomsoever lawfully claiming or to claim the same, or any part thereof.

But it is expressly agreed that Grantor reserves and retains for Grantor, and Grantor's heirs and assigns, a Vendor's Lien, as well as the Superior Title, against the Property until the above described Promissory Note and all interest therein have been fully paid according to the terms thereof, when this Deed shall become absolute.

WHEREAS, Mortgagee, at the special instance and request of Grantee, having paid to Grantor a portion of the purchase price of the Property, as evidenced by the above described Promissory Note, Grantor hereby assigns, transfers, conveys and delivers, without recourse, to Mortgagee said Vendor's Lien and Superior Title against said Property to secure the payment of said Promissory Note, and subrogates Mortgagee to all rights and remedies of Grantor in the Property by virtue thereof.

To the extent applicable to and enforceable against the Property, this Deed is executed, delivered and accepted subject to the following: any liens described herein; ad valorem taxes for the current and all subsequent years, and subsequent assessments for prior years due to changes in land usage or ownership; zoning ordinances, utility district assessments, and standby fees, if any; all valid utility easements created by the dedication deed or plat of the platted subdivision in which the Property is located, covenants and restrictions common to the platted subdivision in which the Property is located, mineral reservations, and maintenance or assessment liens (if any), all as shown by the real property records of the County Clerk of the County in which said Property is located; and any title or rights asserted by anyone (including, but not limited to, persons, corporations, governments or other entities) to tidelands, or lands comprising the shores or beds of navigable or perennial rivers and streams, lakes, bays, gulfs or oceans, or to any land extending from the line of the harbor or bulkhead lines as established or changed by any government or to filled-in lands, or artificial islands, or to riparian rights or other statutory water rights, or the rights or interests of the State of Texas or the public generally in the area extending from the line of mean low tide to the line of vegetation or the right of access thereto, or right of easement along and across the same, if any.

The contract between Grantor, as the seller, and Grantee, as the buyer, may contain limitations as to warranties. To the extent said contract provides for such limitations to survive this conveyance, they shall be deemed incorporated herein by reference. However, the warranty of title contained in this Deed is hereby expressly excluded from any limitations as to warranties contained in the contract referenced in this paragraph.

When this Deed is executed by more than one person, or when Grantee is more than one person, the instrument shall read as though pertinent verbs, nouns and pronouns were changed correspondingly, and when executed by or to a legal entity other than a natural person, the words "heirs, executors and administrators" or "heirs and assigns" shall be construed to mean "successors and assigns". Reference to any gender shall include either gender and in the case of a legal entity other than a natural person, shall include the neuter gender, all as the case may be. The term "Mortgagee" shall include the Mortgagee's heirs, successors and assigns, as applicable.

DATED the ^{2nd} day of December, 2013.



RICHARD C. EVANS

After Recording Return To Grantee
At GRANTEE'S MAILING ADDRESS:


RICHARD A. GRIFFIN
3403 RIVER BEND
ROSENBERG, TX 77471

ACKNOWLEDGMENTS

The State of TEXAS §

County of COMAL §

This instrument was acknowledged before me on the 2nd day of December,
2013, by RICHARD C. EVANS.



My commission expires:

Velda J. Brown
Notary Public

Notary's Name (printed)

Exhibit A

Tract 1:

Lots 1562 and 1563, Canyon Lake Hills Unit No. 3, Comal County Texas, according to map or plat recorded in Volume 2, page 19, Map and Plat Records of Comal County Texas.

Tract 2:

Lot 131, Astro Hills Unit No. 2, Comal County Texas, according to map or plat recorded in Volume 2, page 33, Map and Plat Records of Comal County Texas.

Filed and Recorded
Official Public Records
Joy Streater, County Clerk
Comal County, Texas
12/06/2013 09:25:31 AM
LAURA 4 Page(s)
201306049969



Joy Streater