staller Name:	OSSF Installer #:	OSSF Installer #:			
1st Inspection Date:	2nd Inspection Date:	3rd Inspection Date:			
Inspector Name:	Inspector Name:	Inspector Name:			

Perm	Permit#: Address:						
No.	Description	Answer	Citations	Notes	1st Insp.	2nd Insp.	3rd Insp.
1	SITE AND SOIL CONDITIONS & SETBACK DISTANCES Site and Soil Conditions Consistent with Submitted Planning Materials		285.31(a) 285.30(b)(1)(A)(iv) 285.30(b)(1)(A)(v) 285.30(b)(1)(A)(iii) 285.30(b)(1)(A)(ii) 285.30(b)(1)(A)(i)				
2	SITE AND SOIL CONDITIONS & SETBACK DISTANCES Setback Distances Meet Minimum Standards		285.91(10) 285.30(b)(4) 285.31(d)				
3	SEWER PIPE Proper Type Pipe from Structure to Disposal System (Cast Iron, Ductile Iron, Sch. 40, SDR 26)		285.32(a)(1)				
4	SEWER PIPE Slope from the Sewer to the Tank at least 1/8 Inch Per Foot		285.32(a)(3)				
	SEWER PIPE Two Way Sanitary - Type Cleanout Properly Installed (Add. C/O Every 100' &/or 90 degree bends)		285.32(a)(5)				
5	PRETREATMENT Installed (if required) TCEQ Approved List PRETREATMENT Septic Tank(s) Meet Minimum Requirements		285.32(b)(1)(G) 285.32(b)(1)(E)(iii) 285.32(b)(1)(E)(iv) 285.32(b)(1)(F) 285.32(b)(1)(C)(i) 285.32(b)(1)(C)(ii) 285.32(b)(1)(D) 285.32(b)(1)(E) 285.32(b)(1)(E) 285.32(b)(1)(E) 285.32(b)(1)(E)(ii)(II) 285.32(b)(1)(E)(ii)(II) 285.32(b)(1)(E)(ii)(II) 285.32(b)(1)(E)(ii)(II)				
7	PRETREATMENT Grease Interceptors if required for commercial		285.34(d)				

Inspector Notes:

N-	December 41	A mar	Citotiana	Net	1 at 1	2 m d 1	7 mal 1
No.	Description SEPTIC TANK Tank(s) Clearly	Answer	Citations	Notes	1st Insp.	2nd Insp.	3rd Insp.
8	Marked SEPTIC TANK IsingleTank, 2Compartments Provided withBaffle SEPTIC TANK Inlet Flowline Greater than3" and "T" Provided on Inlet and OutletSEPTIC TANK Septic Tank(s) MeetMinimum Requirements		285.32(b)(1) (E)285.91(2)285.32(b)(1) (F)285.32(b)(1)(E) (iii)285.32(b)(1)(E)(ii) (I)285.32(b)(1)(E) (i)285.32(b)(1)(E) (i)285.32(b)(1)(C) (ii)285.32(b)(1)(C) (ii)285.32(b)(1)(C) (ii)285.32(b)(1) (B)285.32(b)(1) (A)285.32(b)(1)(E)(iv)				
1	ALL TANKS Installed on 4" Sand Cushion/ Proper Backfill Used		285.32(b)(1)(F) 285.32(b)(1)(G) 285.34(b)				
	SEPTIC TANK Inspection / Clean Out Port & Risers Provided on Tanks Buried Greater than 12" Sealed and Capped		285.38(d)				
	SEPTIC TANK Secondary restraint system providedSEPTIC TANK Riser permanently fastened to lid or cast into tank SEPTIC TANK Riser cap protected against unauthorized intrusions		285.38(d) 285.38(e)				
	SEPTIC TANK Tank Volume Installed						
12							
	PUMP TANK Volume Installed						
1	AEROBIC TREATMENT UNIT Size Installed						
14							
	AEROBIC TREATMENT UNIT Manufacturer AEROBIC TREATMENT UNIT Model Number						
15	DISPOSAL SYSTEM Absorptive		285.33(a)(4) 285.33(a)(1) 285.33(a)(2) 285.33(a)(3)				
17	DISPOSAL SYSTEM Leaching Chamber		285.33(a)(1) 285.33(a)(3) 285.33(a)(4) 285.33(a)(2)				
18	DISPOSAL SYSTEM Evapo- transpirative		285.33(a)(3) 285.33(a)(4) 285.33(a)(1) 285.33(a)(2)				
18			203.33(a)(2)				

	_ , .			- -			
No.	Description	Answer	Citations	Notes	1st Insp.	2nd Insp.	3rd Insp.
19	DISPOSAL SYSTEM Drip Irrigation		285.33(c)(3)(A)-(F)				
20	DISPOSAL SYSTEM Soil Substitution		285.33(d)(4)				
21	DISPOSAL SYSTEM Pumped Effluent		285.33(a)(4) 285.33(a)(3) 285.33(a)(1) 285.33(a)(2)				
22	DISPOSAL SYSTEM Gravelless Pipe		285.33(a)(3) 285.33(a)(2) 285.33(a)(4) 285.33(a)(1)				
23	DISPOSAL SYSTEM Mound		285.33(a)(3) 285.33(a)(1) 285.33(a)(2) 285.33(a)(4)				
24	DISPOSAL SYSTEM Other (describe) (Approved Design)		285.33(d)(6) 285.33(c)(4)				
	DRAINFIELD Absorptive Drainline 3" PVC or 4" PVC						
26	DRAINFIELD Area Installed						
	DRAINFIELD Level to within 1 inch per 25 feet and within 3 inches over entire excavation		285.33(b)(1)(A)(v)				
	DRAINFIELD Excavation Width DRAINFIELD Excavation Depth DRAINFIELD Excavation Separation DRAINFIELD Depth of Porous Media DRAINFIELD Type of Porous Media						
	DRAINFIELD Pipe and Gravel - Geotextile Fabric in Place		285.33(b)(1)(E)				
	DRAINFIELD Leaching Chambers DRAINFIELD Chambers - Open End Plates w/Splash Plate, Inspection Port & Closed End Plates in Place (per manufacturers spec.)		285.33(c)(2)				
	LOW PRESSURE DISPOSAL SYSTEM Adequate Trench Length & Width, and Adequate Separation Distance between Trenches		285.33(d)(1)(C)(i)				

	O331 Inspection sheet								
No.	Description	Answer	Citations	Notes	1st Insp.	2nd Insp.	3rd Insp.		
32	EFFLUENT DISPOSAL SYSTEM Utilized Only by Single Family Dwelling EFFLUENT DISPOSAL SYSTEM Topographic Slopes < 2.0% EFFLUENT DISPOSAL SYSTEM Adequate Length of Drain Field (1000 Linear ft. for 2 bedrooms or Less & an additional 400 ft. for each additional bedroom) EFFLUENT DISPOSAL SYSTEM Lateral Depth of 18 inches to 3 ft. & Vertical Separation of 1ft on bottom and 2 ft. to restrictive horizon and ground water respectfully EFFLUENT DISPOSAL SYSTEM Lateral Drain Pipe (1.25 - 1.5" dia.) & Pipe Holes (3/16 - 1/4" dia. Hole Size) 5 ft. Apart		285.33(b)(3)(A) 285.33(b)(3)(A) 285.33(b)(3) (B)285.91(13) 285.33(b)(3)(D) 285.33(b)(3)(F)						
	AEROBIC TREATMENT UNIT IS Aerobic Unit Installed According to Approved Guidelines.		285.32(c)(1)						
	AEROBIC TREATMENT UNIT Inspection/Clean Out Port & Risers Provided AEROBIC TREATMENT UNIT Secondary restraint system provided AEROBIC TREATMENT UNIT Riser permanently fastened to lid or cast into tank AEROBIC TREATMENT UNIT Riser cap protected against unauthorized intrusions								
	AEROBIC TREATMENT UNIT Chlorinator Properly Installed with Chlorine Tablets in Place.								
	PUMP TANK Is the Pump Tank an approved concrete tank or other acceptable materials & construction PUMP TANK Sampling Port Provided in the Treated Effluent Line PUMP TANK Check Valve and/or Anti- Siphon Device Present When Required PUMP TANK Audible and Visual High Water Alarm Installed on Separate Circuit From Pump PUMP TANK Inspection/Clean Out								
37	Port & Risers Provided PUMP TANK Secondary restraint system provided PUMP TANK Riser permanently fastened to lid or cast into tank PUMP TANK Riser cap protected against unauthorized intrusions								
38	PUMP TANK Secondary restraint system provided PUMP TANK Electrical								
	Connections in Approved Junction Boxes / Wiring Buried								

	<u>-</u>								
No.	Description	Answer	Citations	Notes	1st Insp.	2nd Insp.	3rd Insp.		
	APPLICATION AREA Distribution Pipe, Fitting, Sprinkler Heads & Valve Covers Color Coded Purple?		285.33(d)(2)(G)(iii)(II) 285.33(d)(2)(G)(iii)(III) 285.33(d)(2)(G)(v) 285.33(d)(2)(G)(iii) 285.33(d)(2)(G)(iv) 285.33(d)(2)(G)(i) 285.33(d)(2)(G)(iii) 285.33(d)(2)(G)(iii)(I)						
	APPLICATION AREA Low Angle Nozzles Used / Pressure is as required APPLICATION AREA Acceptable Area, nothing within 10 ft of sprinkler heads? APPLICATION AREA The Landscape Plan is as Designed		285.33(d)(2)(G) (i)285.33(d)(2) (A)285.33(d)(2)(F)						
	APPLICATION AREA Area Installed								
	PUMP TANK Meets Minimum Reserve Capacity Requirements								
	PUMP TANK Material Type & Manufacturer								
	PUMP TANK Type/Size of Pump Installed								



Permit of Authorization to Construct an On-Site Sewage Facility Permit Valid For One Year From Date Issued

Permit Number: 118898

Issued This Date: 09/09/2025

This permit is hereby given to: Steve & Natalie Wiggins

To start construction of a private, on-site sewage facility located at:

1016 ADYSON RIDGE DR CITY OF BULVERDE, TX 78163

Subdivision: Centennial Ridge

Unit: 3
Lot: 60
Block: 1

Acreage: 5.0100

APPROVED MINIMUM SIZES AS PER ATTACHED DESIGN

Type of System: Aerobic

Surface Irrigation

This permit gives permission for the construction of the above referenced on-site facility to commence. Installation must be completed by an installer holding a valid registration card from the Texas Commission on Environmental Quality (TCEQ). Installation and inspection must comply with current TCEQ and County requirements.

Call (830) 608-2090 to schedule inspections.



OSSF DEVELOPMENT APPLICATION CHECKLIST

Staff will complete shaded items

		F.:	
	Date Received	Initials	Permit Number
Instructions:			
Place a check mark next to all items that apply. For it Checklist <u>must</u> accompany the completed application		ce "N/A". This C	SSF Development Application
OSSF Permit			
Completed Application for Permit for Authorization	on to Construct an On-Site	Sewage Facili	ty and License to Operate
Site/Soil Evaluation Completed by a Certified Si	te Evaluator or a Profession	nal Engineer	
Planning Materials of the OSSF as Required by of a scaled design and all system specifications.		Chapter 285.	Planning Materials shall consist
Required Permit Fee - See Attached Fee Sched	ule		
Copy of Recorded Deed			
Surface Application/Aerobic Treatment System			
Recorded Certification of OSSF Requiring	Maintenance/Affidavit to t	he Public	
Signed Maintenance Contract with Effective	ve Date as Issuance of Lic	ense to Operate	е

I affirm that I have provided all information required for my OSSF Development Application and that this application constitutes a completed OSSF Development Application.

Signature of Applicant	Autor 7/14/25
COMPLETE APPLICATION	INCOMPLETE APPLICATION
Check No Receipt No	—— (Missing Items Circled, Application Refeused)

Revised: September 2019





ON-SITE SEWAGE FACILITY APPLICATION

195 DAVID JONAS DR NEW BRAUNFELS, TX 78132 (830) 608-2090 WWW.CCEO.ORG

Data	Permit Number	118898
Date	remit Number	710075
1. APPLICANT / AGENT INFORMATION		
Owner Name Steve + Notalie Wiggins	Agent Name Planet Frience	dly Designs
Mailing Address 254 Appellation	Agent Address 1353 Lakes	ide Loop
City, State, Zip New Braunfels TX 78132	City, State, Zip Rand Rock	TX 78665
Phone #	Phone # 512 - 757 - 9	5827
Email	Email planetfriendly des	igns@gmail.com
2. LOCATION	,	0
Subdivision Name Centernial Ridge	Unit <u>3</u> Lot (OO Block
Survey Name / Abstract Number 211845TK	Ac	reage 5.01
Address 1016 Adyson Ridge	City Bulverde State	TX Zip 78163
3. TYPE OF DEVELOPMENT		
Single Family Residential		
Type of Construction (House, Mobile, RV, Etc.)	<u></u>	
Number of Bedrooms		
Indicate Sq Ft of Living Area 300)		
Non-Single Family Residential		
(Planning materials must show adequate land area for doubling the	e required land needed for treatment units a	and disposal area)
Type of Facility		
Offices, Factories, Churches, Schools, Parks, Etc Indicate	Number Of Occupants	
Restaurants, Lounges, Theaters - Indicate Number of Seats		
Hotel, Motel, Hospital, Nursing Home - Indicate Number of E		
Travel Trailer/RV Parks - Indicate Number of Spaces		
Miscellaneous		
Estimated Cost of Construction: \$ 1,242,700 (S	tructure Only)	
Is any portion of the proposed OSSF located in the United State		
Yes No (If yes, owner must provide approval from USACE for p	proposed OSSF improvements within the USACE	E flowage easement)
Source of Water Public Rivate Well		
4. SIGNATURE OF OWNER		
By signing this application, I certify that: - The completed application and all additional information submitted does facts. I certify that I am the property owner or I possess the appropriate property.		
- Authorization is hereby given to the permitting authority and designated site/soil evaluation and inspection of private sewage facilities		-
- I understand that a permit of authorization to construct will not be issued by the Compal County Flood Damage Prevention Order.		·
- I affirm a vely consent to the online posting/public release of my e-mail a	ddress associated with this permit applicati	on, as applicable.
Her no Ylaton	7/14/65	-
Signature of Owner	Date	Page 1 of 2 Revised January 2021



ON-SITE SEWAGE FACILITY APPLICATION

195 DAVID JONAS DR NEW BRAUNFELS, TX 78132 (830) 608-2090 WWW.CCEO.ORG

Planning Materials & Site Evaluation as Required Completed By Eric Schneider RS4431/Corrie Smith OS0029488
System Description Aerobic Surface Application
Size of Septic System Required Based on Planning Materials & Soil Evaluation
Tank Size(s) (Gallons) 600 ATU Absorption/Application Area (Sq Ft) 5,652 Sq Ft
Gallons Per Day (As Per TCEQ Table III) 360 GPD (Sites generating more than 5000 gallons per day are required to obtain a permit through TCEQ.)
Is the property located over the Edwards Recharge Zone? Yes No (If yes, the planning materials must be completed by a Registered Sanitarian (R.S.) or Professional Engineer (P.E.))
Is there an existing TCEQ approved WPAP for the property? Yes No (If yes, the R.S. or P.E. shall certify that the OSSF design complies with all provisions of the existing WPAP.)
If there is no existing WPAP, does the proposed development activity require a TCEQ approved WPAP? Yes No (If yes, the R.S. or P.E. shall certify that the OSSF design will comply with all provisions of the proposed WPAP. A Permit to Construct will not be issued for the proposed OSSF until the proposed WPAP has been approved by the appropriate regional office.)
Is the property located over the Edwards Contributing Zone? X Yes No
Is there an existing TCEQ approval CZP for the property? X Yes No
(If yes, the P.E. or R.S. shall certify that the OSSF design complies with all provisions of the existing CZP.)
If there is no existing CZP, does the proposed development activity require a TCEQ approved CZP? Yes No (If yes, the R.S. or P.E. shall certify that the OSSF design will comply with all provisions of the proposed CZP. A Permit to Construct will not be issued for the proposed OSSF until the CZP has been approved by the appropriate regional office.)
Is this property within an incorporated city? Yes No
If yes, indicate the city: Bulverde
By signing this application, I certify that:
- The information provided above is true and correct to the best of my knowledge. - I affirmatively consent to the online posting/public release of my e-mail address associated with this permit application, as applicable.
Signature of Designer Date

Countryside Construction, Inc.

300 Chapman Parkway, Canyon Lake, TX. 78133

Phone: 830-899-2615 or 1-888-379-3721 Fax: 830-899-6662

Septic System Service Agreement

In consideration of payment for this service cont	tract, we will abide by an	nd agree to its terms and conditions:
Name: Steve + Notale Wiggins Subdy: Centennal Respunty: Comal Permit #: TYPE: Phone:	Address: 101 City: Bulve(de Serial #:	6 Adyson Ridge ST: TX Zip 78163
/ Model #:	OO2.444.2 11	and the second of the second o
) Initial Two Year Service Agreement & Two Year Limited Warranty	() One Ye	ar Service Agreement
	NICEED	ANALYSIS
RENEWAL NAME TRA	MOLEN	AIVALISIS
The effective date of the initial maintenance contract shall be the defect. For, this contract will be in effect FROMTO		
A. An inspection/service call every (4) four months wh servicing of the mechanical & electrical component system.		
B. An effluent quality inspection consisting of a visual	check for color,	turbidity, scum, overflow and odor.
C. The property owner is responsible for "purcha		
applicable). If the chlorine test reveals "No Chlorin additional cost.	e" in the system,	, the property owner may incur an
D. If any improper operation is observed (which cann	ot be corrected a	at that time) the property owner
will be notified immediately of the conditions and t	he estimated cos	t.
E. The response time to a complaint by the property of	wner regarding	operation of the system shall be
within 48 hours from the time of the notification.		
F. ANY PARTS, WARRANTY OR NON-WARRANTY, OR FREI NOT PAID FOR REMAIN THE PROPERTY OF COUNTRYS REPOSSION OF PARTS BY COUNTRYSIDE CONSTRUCTION	SIDE CONSTRUCTI	
G. THE SIGNING OF THIS SERVICE AGREEMENT AUTHOR		DE CONSTRUCTION TO ENTER THE
PROPERTY TO EXECUTE ALL TERMS OF THIS CONTRACT		Che. VIVII A ANNO NEW YORK AND
Countryside Construction, Inc., will warrant installation of the septic of designs approved by the county. HOMEOWNER WILL BE RESPONSIB ANY "Parts Under Warranty" EXCHANGED DURING WARRANTY. Important: As Countryside Construction, Inc. cannot control what or warranty how the system will function. Refer to manufacturer's or installed electrical power to the system, sprinklers that are broken, leaking, stockydraulic/organic design capabilities and the input of non-biodegradable to the requirements as advised by authorized service representative. Lat or parts that are out of warranty are available at a reasonable cost. This contract does not include the pumping of a tank or of any compatible system regardless of reason: Violations of the warranty also include: disconnecting the alarm, restricted.	All other components how much effluent states instructions for states that are required or opped-up or otherwise materials (solvents, grant boratory test work is a artment of a tank, or	ALLS, LABOR AND SHIPPING COSTS ON will be according to manufacturer's warranties. goes into this septic system, we cannot suggestions on septic operation. This Service parts out of warranty, the failure to maintain mal-functioning or sewage flows exceeding the rease, oil, paints, etc.), or any usage contrary vailable at an additional cost. Chlorine, filters, settlement of soil on or around any part of
rated capacity; or flooding by external means. Rodent, insect or fire ant A renewal service contract should be activated (30) thirty days before prior to expiration of existing contract.		
Serviced by: Countrys		
Walker Chapman - Operator		
Print Name (X) S7	EVZ Wygins	Date:
(X) WRIPER Physican Date:	Authori	zed Service Representative
05000 2929		a de



AFFIDAVIT TO THE PUBLIC

THE COUNTY OF COMAL STATE OF TEXAS

CERTIFICATION OF OSSF REQUIRING MAINTENANCE

According to Texas Commission on Environmental Quality Rules for On-Site Sewage Facilities (OSSF's), this document is filed in the Deed Records of Comal County, Texas.

The Texas Health and Safety Code, Chapter 366 authorizes the Texas Commission on Environmental Quality (commission) to regulate On-Site Sewage Facilities (OSSFs). Additionally, the Texas Water Code (TWC), § 5.012 and § 5.013, gives the commission primary responsibility for implementing the laws of the State of Texas relating to water and adopting rules necessary to carry out its powers and duties under the TWC. The commission, under the authority of the TWC and the Texas Health and Safety code, requires owner's to provide notice to the public that certain types of OSSF's are located on specific pieces of property. To achieve this notice, the commission requires a recorded affidavit. Additionally, the owner must provide proof of the recording to the OSSF permitting authority. This recorded affidavit is not a representation or warranty by the commission of the suitability of this OSSF, nor does it constitute any quarantee by the commission that the appropriate OSSF was installed.

property. To achieve this notice, the commission requires a recorded affidavit. Additionally, the owner must provide proof of the recording to the OSSF permitting authority. This recorded affidavit is not a representation or warranty by the commission of the suitability of this OSSF, nor does it constitute any guarantee by the commission that the appropriate OSSF was installed. An OSSF requiring maintenance contract, according to 30 Texas Administrative Code §285.91 (12) will be installed on the property described as (insert legal description): Lot 40. Block I Ridge Unit 3, a subdivision in Comal The property is owned by (insert owner's full name): Steven J. Wiggins This OSSF must be covered by a continuous maintenance contract for the first two years. After the initial two-year service policy, the owner of an aerobic treatment system for a single family residence shall either obtain a maintenance contract within 30 days or maintain the system personally. Upon sale or transfer of the above-described property, the permit for the OSSF shall be transferred to the buyer or new owner. A copy of the planning materials for the OSSF can be obtained from the Comal County Engineer's Office. WITHESS BY HAND(S) ON THIS 14 DAY OF JULY , 20 75 Owner(s) signature(s) SWORN TO AND SUBSCRIBED BEFORE ME ON THIS 14 DAY OF , 20 75 SHELBY DIANE HUNTER Notary ID #130977406 Notary Public, State of Vexas y Commission Expires

July 15, 2026



This page has been added to comply with the statutory requirements that the clerk shall stamp the recording information at the bottom of the last page.

This page becomes part of the document identified by the file clerk number affixed on preceding pages.

Filed and Recorded
Official Public Records
Bobbie Koepp, County Clerk
Comal County, Texas
08/01/2025 04:03:28 PM
IRENE 2 Page(s)
202506024040

Bobbie Koepp

PLANETFRIENDLYDESIGNS@GMAIL.COM 512-757-5827

July 12, 2025

To Whom It Concerns:

The following septic design was created to service a 5 bedroom single family residence that will be less than 4,500 sq. ft. The project will be located at 1016 Adyson Ridge Drive in Bulverde, TX.

If there are any questions or concerns, please do not hesitate to contact me.

Sincerely,

Eric Schneider, R.S.

R.S. #4431

ERIC SCHNEIDER
RS # 4431



PLANETFRIENDLYDESIGNS@GMAIL.COM 512-757-5827

November 4, 2025

Permit: 188898 1016 Adyson Ridge Drive Bulverde, TX 78163

To Whom It Concerns:

The following changes were made to the OSSF design associated with the permit number above:

- 1. The spray heads were changed from 360 degrees to 180 degrees. An additional 2 spray heads were added to the spray field. This is reflected on the site plan and in the narrative section.
- 2. Friction Head calculations were adjusted to reflect the new length of distribution pipe being used.

If there are any questions or concerns, please do not hesitate to contact me.

Sincerely,

Eric Schneider, R.S.

R.S. #4431

ERIC SCHNEIDER
HS # 4431

III/4/25

Raysin # 2



PLANETFRIENDLYDESIGNS@GMAIL.COM 512-757-5827

OSSF SOIL EVALUATION FORM

Physical	Physical Address: 1016 Adyson Ridge Road Bulverde, TX 78163									
Date Pe	rformed:Jul	y 2, 2025 Propos	ed Excavation Depth:	1 Foot						
Profile	Profile Hole1									
Dept h (ft)	Textural Class	Description of Soil	Drainage Mottles/Water Table	Restrictive Horizon	Comments					
0										
	Class IV	Black Clay	None	None	< 30% Gravel					
1										
2										
3				- 1						
4										
5										

Profile !	Hole2		144		
Dept h (ft)	Textural Class	Description of Soil	Drainage Mottles/Water Table	Restrictive Horizon	Comments
0					
	Class IV	Black Clay	None	None	< 30% Gravel
1		1			
2					
3					
4					
5					

I certify that the above statements are true and based on my own field observations.

Presence of 100 year flood zone: N

Recharge features within 150 feet: N

Existing or proposed water well: Y

Presence of adjacent ponds, streams, water impoundments: N

Organized Sewage available on lot or tract: N Suitable for standard system: N/A

Site Evaluator

SE #



Pump Float Settings

Pump Off Position: 7 in. above tank floor = 131.25 gal Pump On Position: 8 in. above tank floor = 150.00 gal Alarm On Position: 28 in. above tank floor = 525.00 gal

Reserve Capacity: 13.5 in. (778 gal – 525.00 gal) = 253.00 gal (> 2/3 estimated gpd)

Pump and Sprinkler Heads

Elevation Head: 6 ft

Pressure Head: 30 psi x 2.3 = 69

Friction Head: 260 ft of 1 in. Sch. 40 PVC - 260 ft x .0213 = 5.54

Total Head (TDH): 6 + 69 + 5.54 = 80.54 ft (Within the pump performance curve)

Pump: Franklin Electric C1 Series 10CI-05P4-2W230

Sprinkler Heads: K-Rain Pro Plus Professional series with Low Angle Nozzle #4, operating at 30 psi, 30 ft. radius, and 3.4 gpm flow per sprinkler.

Chlorinator

This system will utilize a NSF approved Liquid Chlorinator.


Dosing:

This system will utilize a commercial timer to cycle power to the pump-on float switch twice per night. Disposal period for overnight disposal is between midnight and 5 AM.

360 gpd/2 doses per day = 180 gal per dose

4 sprinklers x 3.4 gal per minute = 13.6 gallons per minute

180 gal per dose/13.6 gal per minute ≈ 14 minutes per dose





Construction/Installation Notes & Requirements

- Refer to site plan for component placement and follow manufacturer's instructions for installation of treatment plant and aerator.
- All materials and construction methods are required to conform to the standards for Private Sewage Facilities set forth by the Texas Administrative Code, Chapter 285 On-Site Sewage Facilities.
- The installer must have a current and valid Texas installer certificate, and is required to have at the minimum an Installer II certification.
- The installer must notify the designer and regulatory authority at least 48 hours in advance to schedule required inspections to ensure that the system in installed in accordance with approved plans and specifications.
- Diversion berms will be placed when needed to protect irrigation and tank areas from excessive runoff.
- It is the responsibility of the installer to maintain the minimum setback requirements as stated in Chapter 285 On-Site Sewage Facilities.
- No part of the system shall be located within 10 feet of a potable water line.

Electrical Components

All electrical wiring shall conform to the requirements of the National Electric Code (1999) or under any other standards approved by the executive director. Additionally, all external wiring shall be installed in approved, rigid, non-metallic gray code electrical conduit. The conduit shall be buried according to the requirements in the National Electric Code and terminated at a main circuit breaker panel or sub-panel. Connections shall be in approved junction boxes. All electrical components shall have an electrical disconnect within direct vision from the place where the electrical device is being serviced. Electrical disconnects must be weatherproof (approved for outdoor use) and have maintenance lockout provisions.

Tank Notes

- The bottom of the excavation for the tanks should be level and free of large rocks and debris.
- All tanks are to be set level on a minimum 4 inch layer of sand, sandy loam, clay loam, or pea gravel.
- Risers are required on tank inspection ports as per 30 TAC 285.38 (9/1/2012.) This includes
 access limitation (<65 lbs lid or hardware secured lid) and secondary plug, net, or mesh in riser.
 Risers are required to be two inches above grade level.
- All openings in the tank must be properly sealed to prevent the escape of wastewater, and/or to prevent the infiltration of water.
- Tanks must be filled with water for at least 24 hours to test for leaks and structural integrity.
- The tanks must be set low enough to have fall of at least 1/8 inch per foot from house to tank.
- PVC pipe from house to tank must be at least Sch. 40 or SDR 26.



Irrigation and Landscape Notes

- Irrigation lines should be 1 inch Sch. 40 PVC. All supply lines, sprinkler heads, and valve cover boxes must be permanently colored purple. Sleeve any pipe that crosses any road, driveway, or other land improvement with Sch. 40 PVC.
- Supply lines must be buried at least 6 inches below finished grade.
- If irrigation area does not have established vegetation, a mixture of winter rye or Bermuda grass will be seeded to establish seasonal vegetation.
- The installer will notify the property owner prior to removal of any trees/bushes that may obstruct the operation of the irrigation system.
- All exposed surface rock must be covered with at least 4 inches of suitable soil.

Additional Notes

- Install audio-visual alarm for aerator and pump on separate breakers.
- The high water and air compressor alarms should be audio/visual and mounted in a place that can be easily seen and heard when alarms are activated.

Maintenance Requirements

- The applicant must furnish to the regulatory authority a valid maintenance contract with a certified maintenance company before a permit will be issued.
- The maintenance company will verify that the system is operating properly and provide ongoing maintenance of the installation.
- The initial contract will be a minimum of 2 years.
- A maintenance contract will authorize the maintenance company to maintain and repair the system as needed.
- The property owner must continuously maintain a signed written contract with a valid maintenance company and will submit a copy of the contract to the permitting authority at least 30 days prior to the date service will cease.

Affidavit

- The applicant must file a certified copy of an affidavit at the County Clerk's Office and file in reference to the real property deed on which the surface application system is to be installed.
- The affidavit will state that the property shall not be transferred to a new owner without:
 - The new owner being advised that the property contains a surface application system for wastewater disposal.
 - The permit issued to the previous owner of the property being transferred to the new owner in accordance with Chapter 285.3(b)(3) of the TCEQ OSSF Rules, i.e.; the permit will be issued in the name of the owner of the OSSF. Permits shall be transferred to the new owner automatically upon legal sale of the OSSF. The transfer of an OSSF permit under this section shall occur upon actual transfer of the property on which the OSSF is located unless ownership of the OSSF has been severed from the property.
 - o The new owners submitting a valid maintenance contract to the permitting authority.



Operation and Management Notes

- The OSSF should not be treated as a normal city sewer.
- Feminine hygiene products should never be disposed of in the toilet. Products such as these can
 be detrimental to a septic system, causing backups inside the home and/or overflowing of the
 tank due to pump malfunction.
- The excessive use of in-sink garbage grinders and grease discarding should be avoided. In-sink garbage grinders can cause a rapid buildup of sludge or scum resulting in a more frequent cleaning and possible system failure.
- Do not use the toilet to dispose of cleaning tissue, cigarette butts, or other trash. This disposal practice will waste water and also impose an undesirable solid load on the treatment system.
- Septic tanks should be cleaned before sludge accumulates to a point where it approaches the bottom of the outlet device. If sludge or scum accumulates to this point, solids will leave the tank with the liquid and possibly cause the system to clog resulting in sewage surfacing or backing up into the house through plumbing fixtures.
- A regular schedule of cleaning the tank at two to three year intervals should be established.
 Commercial cleaners are equipped to readily perform the cleaning operation. Owner of OSSF's will contract only persons registered with TCEQ to transport the septic system waste.
- Do not build driveways, storage buildings, or other structures of system components on the disposal field.
- Chemical additives, or so-called enzymes, are not necessary for the operation of a septic tank.
 Some of these additives may even be harmful to the system's operation.
- Soaps, detergents, bleaches, drain cleaners, and other household cleaning materials will very seldom affect the operation of the system. However, moderation should be exercised in the use of such materials.
- The homeowner shall observe Chapter 285.37 regarding water softeners and reverse osmosis entering into the OSSF.
- The liquid from the OSSF is still heavily laden with bacteria. The surfacing of this liquid constitutes a health hazard to those that might come into contact with it.


Water Conservation Practices

- Showers usually use less water than baths. Installing water saving shower heads that use less than 2.5 gallons per minute saves both water and energy.
- If you take a tub bath, reduce the level of water in the tub from the level to which you customarily fill it.
- Leaky faucets and faulty toilet fill-up mechanisms should be repaired as quickly as possible.
- Leaking toilets may not be evident. Add a few drops of food coloring into the tank. Do not flush. If the color appears in the bowl within a few minutes, adjustments and/or repairs to the toilet need to be made.
- Install low-flow fixtures throughout the house and use faucet aerators that restrict water flow to help reduce consumption.
- Try to run dishwasher with a full load.
- Avoid running the water continuously for brushing teeth, washing hands, shaving, or rinsing kitchen utensils.



- Water can be saved in the laundry room by adjusting water levels to match the size of the load.
 If the washing machine does not have a variable load control, water can be saved by running it only when the washer if full.
- Keep a container of drinking water in the refrigerator instead of running a faucet until it turns cold.
- Insulate hot water pipes to avoid long delays of wasted water while waiting for the water to heat
- Ask your federal, state, county, city, or other local government about programs to conserve water and how they can help you save water.

This proposed system has been designed generally following the minimum requirements under TCEQ Chapter 285 On-Site Sewage Facilities. The site evaluation and subsequent design are based on technical information currently available. There was no indication of shallow groundwater or slopes where seeps could occur at the time of the site evaluation. The performance of the OSSF is not, and cannot be guaranteed, even though all provisions of the Standards have been complied with. If failure should occur, additions or modifications to the OSSF may need to be made. By accepting this design, the homeowner/builder understands that the designer/site evaluator will not be liable for more than the agreed upon design fee.



Received BASIS OF BEARNG IS TEXAS STATE
PLANE COORDINATE SYSTEM OF 1983,
SOUTH CENTRAL ZONE.
FND. PN = 1/2" REBAR FOUND
SET PN = 1/2" REBAR SET WITH YELLOW
PLASTIC CAP STAMPED THOMES 3682". **Brandon Mark Olvera** ELEVATIONS BASED ON NAVD 1988. 09/09/2025 12:16:42 PM ALLED 48.13 AC. 545/560 VF LOT 60, BLOCK 1, CENTENNIAL ITT 3, CITY OF BULVERDE, COMAL TEXAS, PLAT RECORDED IN DOC. 126, OFFICIAL RECORDS, COMAL TEXAS. 16 ADYSON RIDGE DRIVE N0'12'58"E 174.65 LOT 59 BLK. 1 LOT 60 BLK. 1 5.01 AC. memichaellandsurveying.com
MCMICHAEL LAND SURVEYING
907 DIVINE WAY, NEW BRAUNFELS, TX 78130
EMAIL fred@mcmichaellandsurveying.com
(830) 832-8259 FIRM NO. 10193990 LOT 61 BLK. 1 EM = ELEC. METER


WITH WATER METER

AC = AR CONDITIONER

AC = BEED RECORDS

MERR = MAP & PLAT RECORDS

OAKB = 8° DIA. OAK TREE LEGEND 291.8 265.4 I, FRED L. MONTCHAEL, DO HEREBY CERTIFY THAT THIS PLAT WAS PREPARED FROM AN ACTUAL SLAVEY MADE ON THE GROUND AND UNDER MY SUPERVISION. STATE OF TEXAS : FRED L. McMICHAEL
SURVEYED: JANUARY 15, 2025
PROJECT NO:: 21184STK ADYSON RIDGE DR. R.P.L.S. NO. 3682 SCALE:



General Notes:

ALLOW FOR METAL LINTELS

ABOVE DOOR & WDW OPENINGS

WITH MASONARY ABOVE

1. HVAC UNIT IN ATTIC, PROVIDE
220V OUTLET, PROVIDE LIGHT
FIXTURE NEAR UNIT SWITCHED AT
ATTIC ENTRANCE, PROVIDE
METAL DRIP PAN WITH OUTSIDE
DRAIN LINE. PROVIDE SUB-FLOOR
WALKWAY TO & AROUND UNIT
CONFORMING TO APPLICABLE CODE.

2. AC CONTRACTOR MAY REQUIRE THE USE OF ADDITIONAL AREAS FOR THE USE OF DUCTWORK OR EQUIPTMENT. VARIFY ANY CHANGES WITH OWNER & BUILDER

3. TANKLESS W.H. UNIT IN ATTIC, PROVIDE L.P. SUPPLY, PROVIDE LIGHT FIXTURE NEAR UNIT SWITCHED AT ATTIC ENTRANCE, PROVIDE METAL DRIP PAN WITH OUTSIDE DRAIN LINE. PROVIDE SUB-FLOOR WALKWAY TO & AROUND UNIT CONFORMING TO

NOTE: ALL SHT.ROCK CORNERS TO BE ROUNDED.

- 1.0 These construction documents and specifications are intended to meet all applicable codes and ordinances. Contractor to comply with all local codes, ordinances and deed restrictions.
- 2.0 Any discrepancies in construction documents to be brought to the attention of the architect prior to work being performed or materials being ordered.
- 3.0 All windows will be dimensioned to center line unless otherwise noted. Glass size per mfr. specs.
 4.0 All windows within 24" of an exterior or interior door to be tempered glass. Window manufacturer
- to verify for all tempered glass locations as per applicable code.

 5.0 Builder to verify sizing and location of all appliances & related components.
- 6.0 Weather strip attic access door(s).
 7.0 Contractor to provide a 3/4" plywood catwalk from attic access to HYAC units (if applicable).
- Units to be located within 20'-0" of access.

 8.0 Provide I s.f. net free area of attic ventilation per
- 150 s.f. of total covered roof area as per code.
 9.0 All plumbing, appliance & gas vents to vent to rear of roof ridge wherever possible.
 10.0 Provide control and expansion joints as required
- on concrete drives, walks, and patios.


 11.0 Provide a 4" masonry door sill at
- exterior door thresholds with masonary lug.

 12.0 Unless noted otherwise standard pantry shelving to be as follows:

 Lowest 2 shelves to be 16" D. with
- height spacing of 14" clear.
 Remaining shelves to be 12" D. with
 height spacing of 12" clear.

 13.0 Provide blocking for ceiling fans where specified

SQUARE FO	DOTAGES
TOTAL LIVING	3,001 <i>-</i> SQFT
FRONT PORCH	101-SQFT
REAR PORCH	634-SQFT
GARAGE	795-SQFT
TOTAL SLAB	4,531 -SQFT
TOTAL COVERED	4,531 -SQFT




REVISIONS

Received

Brandon Mark Olvera


09/09/2025 12:16:42 PM



SECTION B-B



TOTAL EMPTY WEIGHT: #16880



Received **Brandon Mark Olvera**

09/09/2025 12:16:42 PM

urina

GRAVITY FLOW Liquid Bleach Chlorinator

US Patent Pending

No part of this public anticed, stored in any retrieval systems, electronic, mechanical, photos are, electronic, mechanical, photos ar written permission of LBC MFG. ed in any form or by any m

LBC Manufacturing P.O. Box 454 ayetteville, TEXAS 78940 (979) 826-0139 off.

For a downloadable copy: www.ez-tank.com



THIS PRODUCT WAR SUMMERS OF CHLORINE DISINFECTION DEVICE / ENCEEDS THE APPLICABLE REQUIR NEETTON DEVICE AND MEETS OR

CHLORINE DISINFECTION DEVICE PERFORMANCE

The LBC MFG "EZ-Tank" is a prostandard 46 for Chlorine district ction devices. The EZ-Tank is listed as a certified chi evice for secondary treated effluent. Certification requires the device to be used with 6-10% sodium yporblodie (household bleach) The EZ-Tank Disinfection device is a grawly flow product that applies is the control of the second state of the second se


THE LIQUID CHLORINATION PROCESS

LBC Manufacturing designed and built the "EZ-Tarris" to provide years of trouble-free service. It is constructed from durable Polyethylane material which can withstand the comosive nature of Sodium Phypochlorine (Household Blanch). It was been tested to NSSTANSI Sid 48 and has proven to function more consistently, at a lower operating cost, than any other distribution method.

The binds function of the Liquid Bleech Chlorhator is to introduce disinfectant to the effluent water. Holding/Pump tank as the effluent enters. The longer the contact time the disinfectant has to in with pathogens, the better it disinfects. The ideal method is misoimum contact time for minimal out.

RECOMMENDED INSTALLATION INSTRUCTIONS

- LBC Manufacturing recommends installation by TCEQ licensed and train
- 1. Locate the Aerobic System Holding/Pump tenk
- 2. Remove the green access lid mounting scre-
- it we tical sensing pipe into Holding/Pump tank. Ensure sensing pipe is resting on the totiom of Holding/Pump tank. Cut the sensing pipe off below the top of the Holding/Pump tank lid, and se the sensing pipe to remain vertical in the Holding/Pump tank
- Using PVC Cleaner and PVC glue, attach the barb fitting adapter (supplied on the end
 of EZ-Tanks vinyl tubing) to the sensing pipe.
- Place the EZ-Tank reservoir inside the holding tank access rised (EZ-Tank reservoir re-solely for make the holding tank access risen. If the holding tank access riser close not have followed by the new access riser that accommodules the secondary solely follow.
- Next drift 4.25 inch hole in center of holding tank access lid. (this ellows the fill lid to be accessed without having to reopen the holding tank lid) Next, Re-Install holding tank access lid and replace
- 7. Open E2-Tank gasketed Sii lid. Fill with 6% -10% sodium hypochlorite. Once filled, Replace the gasketed fill fill ensuring a firm secure seal, (if the fill lid is not lightened securely, a vacuum will not form and reservoir will empty sodium hypochlorite contents into Holding/Pump tank premature).



LIQUID CHLORINATOR OPERATION AND MAINTENANCE

it is the Owner's Responsibility to operate and maintain the Liquid Chlorinator to the best of their ability. If

e Plate located on the FII Lid of the Liquid Chic

und constraints uses o-rurs octains ryponaming processor montely for the way my a and on chemicals other than specified. Always maintain a constant supply of disinfector in the Chlorinator Housing at all dises. The rate of disinfectout/filesch usage will way all homeowner water usage. If disinfectont usage increases or decreases, call the septi-

nicals etc., other than Sodium Hypochlorite, enters the Chlorisator Housing, cell :-

****Always use Personal Protective Equipment when Filling or Servicing the Chlorinstor**

Open the Chlorinator Fill Lid and Visually Inspect the liquid level the chlorina reservoir. Staintain a constant supply of Sodium Hypochlorite (Household Bleach) in the Chlorinator Housing and reservoir at all times. Check Sprinkler discharge for Chlorine redicted. If Service is required, refer to the Data/Service Plate located on the Fill Lid of the chlorinator

LY: Open the Chlorinator Fill Lid and Visually Inspect the Chlorinator for debris such as dirt, grass clippings etc. Check Sprinter discharge for Chlorine residuel. If Servi required, refer to the Data/Service Plate located on the Fill Lid of the Chlorinator reservoir


Visually inspect the Chlorinator Housing for any demage from lawsmowers, etc. Remove distant build up , grans, etc. from Chlorinator Housing Fill Ltd. Check Sp discharge for Chlorina residual. nion Pinto located on the FIII Lid of the

FOR INTERIMITENT PERIODS OR EXTENDED PERIODS OF MON-USE

The EZ_Tank is designed to functions under normal use or intermittent periods of use. It non us a exceed 6 months , drain Chlorinator Housing and relia with 6-10% Socilum Hyp Scrivice is required, refer to the Data/Service Plate located on the Fill Lid of the Chlorinator :

Received Brandon Mark Olvera 09/09/2025 12:16:43 PM

C1 Series Family Curve



FEATURES

- Supplied with a removable 5" base for secure and reliable mounting
- Bottom suction design
- Robust thermoplastic discharge head design resists breakage during installation and operation
- Single shell housing design provides a compact unit while ensuring cool and quiet operation
- Hydraulic components molded from high quality engineered thermoplastics
- Optimized hydraulic design allows for increased performance and decreased power usage
- · M All metal components are made of high grade stainless steel for corrosion resistance
- Available with a high quality 115 V or 230 V, 1/2 hp motor
- Fluid flows of 10, 20, and 30 gpm, with a max shut-off pressure of over 100 psi
- Heavy duty 600 V 10 foot SJ00W jacketed lead

APPLICATIONS .

- Gray water pumping
- Filtered effluent service water pumping
- Water reclamation projects such as pumping from rain catchment basins
- Aeration and other foundation or pond applications
- Agriculture and livestock water pumping

ORDERING INFORMATION.

				C1 Seri	es Pumps		
GPM	НР	Volts	Stage	Model No.	Order No.	Length (in)	Weight (lbs)
		115	7	10C1-05P4-2W115	90301005	26	17 .
10		230	7	10C1-05P4-2W230	90301010	26	17
		115	5	20C1-05P4-2W115	90302005	25	16
20	4.00	-230 .	5	20C1-05P4-2W230	90302010	25	16
	1/2	115	6	20XC1-05P4-2W115	90302015	26	17
20X		230	6	20XC1-05P4-2W230	90302020	26	17
		115	4	30C1-05P4-2W115	90303005	25	16
30		230	4-	- 30C1-05P4-2W230 :	90303010	25	16

Note: All units have 10 foot long SJOOW leads.



- 3/4" Intet-Replaces all standard cotors.
- > 2N1 Adjustable or Continuous Retation Provides a full range adjustment from 40° zo a confiruous full sircie.
- Paiented Arc Set Degree Markings Diearly indicates the current watering cattern ano simplifies arc set adjustment.
- Arc Memory Chrich Prayers memai gear gnities noire air of raior sentite: bns egarnati automatically finozzie turet is forced best its stoc.
- Time Proven Patented Reversing Mechanism Azsurss confinuous reverse and "enum" over a 20 year ristory.

- Ratcheling Riser Allows for easy adjustment of your left starting position with a smale turn of the riser.
- Rubber Cover Seals out diri and moreases product durability.
- Wide Selection of Nezzies including standard and low angle provides fexibility in system design.
- Optional Check Valve 3-syemis low head drainage.



IRRIGATION SO WORLDW



rain. ProPlus Performance Data

Model Numbers: 11603, 11603-HP, 11603-SH, 11603-RCW • Arc Adjust: 40-360 • Drive Type: Gcar • Warranty: 5 years

Standard Performance Data:

Metric Performance Data:

Nozzic	Pressure	Radius	Flow	Precip	Precip
:	(PSI)	(ft)	(GPM)	(IN/HR)	(IN/HR)
0.5	30	· 28.	0.5	0.06	0.07
	40	29	0.6	0.07	0.08
	50.	, 29	0.7	0.08	0.09
	60	30	0.8	0.09	0.10
0.75	30	29	0.7	0.08	0.09
. '	40	30	0.8	0.09	0.10
	50	31	0.9	0.09	0.10
	60	32	1.0	0.09	0.11
1	30	32	1.3	0.12	0.14
	40	. 33	. 1.5	0.13	0.15
	50	34	1.6	0.13	0.15
	60	35	1.8	0.14	0.16
2	30.	37	2.4	0.17	0.19
	. 40 .	40	2.5	0.15	0.17
	50 .	42	3.0	0.16	0.19
	60	43	3.3 •	0.17	0.20
2.5	30	38	2.5	0.17	0.19
Pre-	40	39	2.8	0.18	0.20
Installed	50	40	3.2	0.19	0.22
	60	41	3.5	0.20	0.23
3.	30 -	.38	3.6	0.24	0.28
	40	39	4.2	0.27	0.31
	50	41	. 4.6	0.26	0.30
	60 .	42	5.0	0.27	0.32
4	30	43	4.4	0.23	0.26
	40 -	44	5.1	0.25	0.29
•	50	46	5.6	0.25	0.29
-	60	49	5.9	0.24	0.27
6	40	45	5.9	0.28	0.32
	. 50, , ,	46	6.0	0.27	0.32
	60 .	48	6.3	0.26 -	0.30
	70	49	6.7	0.27	0.31
8	40	42	8.0	0.44	0.50
٠.	50	45	8.5	0.40	0.47
٠	60	49	9.5	0.38	0.44
	70	50	10.0	0.39	0.44

TO MEGICE	trajectory				
Nozzle	Pressure (bar)	Radius (meter)	Flow (Vm)	Precip (mm/hr)	Precip (mm/hr)
<u>.</u>	• •	,			A
0.5	2.0	8.5	1.9	1.6	1.8
	3.0	8.8	2.3	1.7	2.0
	3.5	. 8.8	2.6	2.0	2.3
L	4.0	9.1	3.0	2.2	2.5
0.75	2.0 .	8.8	2.6	2.0	. 2.3
•	3.0	. 9.1	3.0 ;	2.2	2.5
:	3.5	9.4	3.4	2.3	.2.6
1	4.0	9.8	3.8	2.4	2.8
1	2.0	9.8	4.9	3.1	3.6
1	3.0	10.1	5.7	3.4	3.9
and the same of th	3.5	10.4	6.1	3.4	3.9
<u></u>	4.0	10.7	6.8	3.6	4.1
2	2.0	11.3	9.1	4.3	4.9
•	3.0	12.2	9.5	3.8	4.4
•	3.5	12.8	11.4	4.2	4.8
	4.0	13.1	12.5	4.4	5.0
2.5	2.0	11.6	9.5	4.2	4.9
Pre-	3.0	11.9	10.6	4.5	5.2
Installed	3.5	12.2	12.1	4.9	5.6
Ĺ	4.0	12.5	13.2	5.1	5.9
3	2.0	11.6	13.6	6.1	7.0
,	3.0	11.9	15.9	6.8	7.8
}	3.5	12.5	17.4	6.7	7.7
	4.0	12.8	18.9	6.9	8:0
4	2.0	13.1	16.7	5.8	6.7
	3.0	13.4	19.3	6.4	7.4
Control of the Contro	3.5	14.0	21.2	6.5	7.5
	. 4.0	14.9	22.3	6.0	6.9
6	3.0	13.7	22.3	7.1	8.2
i	3.5	14.0	22.7	. 6.9	8.0
•	4.0	14.6	23.8	6.7	-7.7
	5.0	14.9	25.4	6.8	7.9
8	. 3.0	12.8	30.3	11.1	12.8
	3.5	13.7	32.2	10.3	11.8
	4.0	·14.9	36.0	9.7	11.2
	5.0	15.2	37.9	9.8	11.3

Low Angle Standard Performance Data

Low Angle Metric Performance Data

Nozzle	(PSI)	Radius (ft)	. Flow (GPM)	Precip (IN/HR)	Precip (IN/HR)
1	30	22	1.2	0.24	0.28
	. 40	24	1.7	0.28	0.33
•,	50 .	26	1.8	0.26	0.30
	60	28	2.0	0.25	0.28
3	30	29	3.0	0.34	0.40
	40	32	3.1	0.29	0.34
	50	35	3.5	0.28	0.32
	60	37	3.8.	0.27	0.31
4.	30	31	3.4	0.34	0.39
	40	34	3.9	0.32	0.37
	50	37	4.4	0.31 -:	0.36
	. 60		4.7	. : 0.31	0.36_
6.	40	38	6.5	0.43	0.50
	50	40	7.3	0.44	0.51
	60	42	8.0	0.44	0.50
	70	44	8.6	0.43	0.49

12 degree tr	ajectory				
Nozzle	Pressure (bar)	Radius (meter)	Flow (Vm)	Precip (mm/hr)	Precip (mm/hr)
					. 🛕
	2.0	6.7	4.5	6.1	7.0
[:	3.0	7.3	6.4	7.2	8.3
1 .	3.5	. 7.9	6.8	6.5	7.5
L	. 4.0 .	8.5	7.6	6.2	7.2
! 3	2.0	8.8	11.4	8.7	10.1
	3.0	9.8	11.7	7.4	8.5
i	3.5	10.7	13.2	7.0	8.1
<u> </u>	4.0	11.3	14.4	6.8	7.8
. 4	2.0	9.4	12.9	8.6	10.0
1	3.0	10.4	14.8	8.2	9.5
Į.	3.5	11.3	16.7	7.9	9.1
L	4.0	11.6	17.8	8.0	9.2
: 6	3.0	11.6	24.6	11.0	12.7
;	3.5	12.2	27.6	11.2	12.9
	4.0	12.8	30.3	11.1	12.8
•	5.0	13.4	32.6	10.9	12.5



Address:	 	
Legal Description:		

Dear Property Owner & Agent,

Thank you for your submission. We have reviewed the planning materials for the referenced permit application, and unfortunately, they are insufficient. To proceed with processing this permit, we require the following:

118884.pdf Markup Summary

3 (1)

(If yes, the R.S., or P.E. shall certify that the issued for the proposed OSSF until the CZF Is this property within an incorporated c If yes, indicate the city: Bulverde

Page Label: 3

Date: 8/28/2025 2:02:52 PM Checkmark: Unchecked Author: Brandon Mark Olvera



Submit a copy of the approved building permit or written verification from the City of Bulverde stating that the improvements on the referenced property do not require a building permit.

9 (1)



Page Label: 9

Date: 8/28/2025 1:43:06 PM Checkmark: Unchecked Author: Brandon Mark Olvera



Which ATU are you purposing to use?

15 (2)



Page Label: 15

Date: 8/28/2025 1:47:55 PM Checkmark: Unchecked Author: Brandon Mark Olvera



Property dimensions do not match the plat.



Page Label: 15

Date: 8/28/2025 1:53:08 PM Checkmark: Unchecked Author: Brandon Mark Olvera



Please label the easements on the site plan.



PLANETFRIENDLYDESIGNS@GMAIL.COM 512-757-5827

August 29, 2025

Permit #118898 1016 Adyson Ridge Drive Bulverde, TX 78163

To Whom It Concerns:

The following adjustments were made to the design associated with the above permit number:

- 1. The builder/property owner will supply the appropriate documentation from the City of Bulverde.
- 2. The typo in the narrative section has been corrected to show that a Solar Air Model SA600LP is going to be used for this project.
- 3. The property lines that were originally combined into one dimension have now been broken down to reflect what is shown on the plat.
- 4. The setbacks and easements are all now labeled directly on the site plan.

If there are any questions or concerns, please do not hesitate to contact me.

Sincerely,

Eric Schneider, R.S.

R.S. #4431

ERIC SCHNEIDER
PS # 4431
Rivsic

PLANETFRIENDLYDESIGNS@GMAIL.COM 512-757-5827

OSSF SOIL EVALUATION FORM

		016 Adyson Ridge Road E		1.5	
Profile		y 2, 2025 Propos	ed Excavation Depth:	1 Foot	
Dept	Textural	Description of Soil	Drainage Mottles/Water	Restrictive	Comments
0			lable		
0	Class IV	Black Clay	None	None	< 30% Gravel
1				065	
3				-	
4				g processor and a second	
5					
				Physical Co.	
Profile	2				
Dept	2 Textural	Description of Soil	Drainage Mottles/Water	Restrictive	Comments
Dept h (ft)	Z	Description of Soil	Drainage Mottles/Water Table	Restrictive Horizon	Comments
Dept		Description of Soil Black Clay	Mottles/Water		Comments < 30% Gravel
Dept h (ft)	Class		Mottles/Water Table	Horizon	
Dept h (ft)	Class		Mottles/Water Table	Horizon	
Dept h (ft) 0	Class		Mottles/Water Table	Horizon	
Dept h (ft) 0	Class		Mottles/Water Table	Horizon	
Dept h (ft) 0	Class		Mottles/Water Table	Horizon	

I certify that the above statements are true and based on my own field observations.

Presence of 100 year flood zone: N

Recharge features within 150 feet: N

Existing or proposed water well: Y

Presence of adjacent ponds, streams, water impoundments: N

Organized Sewage available on lot or tract: N Suitable for standard system: N/A

Site Evaluator

SE#

The proposed system has been designed to serve a 5 Bedroom (equivalent) Single Family Residence that will be < 4,500 sq ft. It will have a maximum daily water usage rate of 360 gal/day, as per table III of the Chapter 285 Rules for On-Site Sewage Facilities by the TCEQ.

Site Description and Site Evaluation

The subject property is located within a subdivision. The legal description is Unit 3, Lot 60, Block 1 in the Centennial Ridge Subdivision. The existing vegetation consists of some native grasses. The site evaluation indicated that the site has suitable soil for an aerobic surface irrigation system. No evidence of shallow ground water was observed during the site evaluation. All exposed rock within the proposed surface distribution area will be removed or covered with suitable soil and seeded prior to final inspection. The spray heads will remain a minimum of 15 feet away from any trees. The property has a

private well water supply as the source for potable water. All of the systems components will be 100 feet away from all wells. All portions of the spray radii will maintain at least a 20 feet separation from all property lines. No portion of this system lies within 10 feet of a waterline. There are no recharge features within 150 feet of the proposed system. Minimum separation distances as stated in Chapter 285.30 TCEC Site Sewage within 150 feet of the proposed system.

Description oposed bic nent Sys

The residence utilize of Air of C wastewath em I 600L is a propried treatment plant upro in TCEC is seein Texas. The second entropy of the 785 compartment of th

sign Specifications

Size of Residence: < 4,500 sq. ft.

Number of Bedrooms: 4 + Study with closet Average Expected Daily Flow (Q): 360 gpd

Application Rate: 0.064 gal/ft²/day

Minimum Application Area Required (A=Q/Ra): A= 360/0.064 = 5,626 ft²

Actual Application Area: 5,652 ft2

System Components

Pretreatment/Trash Tank: 375 gal

Aeration Tank: 785 gal

Pump Tank: 778 gal (41.5 inches of usable space) – 18.75 gallons/inch



Pump Float Settings

Pump Off Position: 7 in. above tank floor = 131.25 gal Pump On Position: 8 in. above tank floor = 150.00 gal

Reserve Capacity: 13.5 in. (778 gal - 525.00 gal) = 253.00 gal (> 2/3 estimated gpd

Pump and Sprinkler Heads

Elevation Head: 6 ft

Pressure Head: $30 \text{ psi} \times 2.3 = 69$

Frict ad: 100 ft ... Sch x .0213 =

Total (TDH): f + 2.1 25 ft (N. re pun form urve)

Pump klin F c C1 9 10CI-05P4-2V

Sprink ar Rain Pro Professional with Angle le #4, oper at 30 psi, 30 ft.

Chlorin

This system will utilize a NSF approved Liquid Chlorinator.

Dosing

This system will utilize a commercial timer to cycle power to the pump-on float switch twice per night

360 gpd/2 doses per day = 180 gal per dose

2 sprinklers x 3.4 gal per minute = 6.8 gallons per minute

180 gal per dose/6.8 gal per minute ≈ 27 minutes per dose



Construction/Installation Notes & Requirements

- Refer to site plan for component placement and follow manufacturer's instructions for installation of treatment plant and aerator.
- All materials and construction methods are required to conform to the standards for Private Sewage Facilities set forth by the Texas Administrative Code, Chapter 285 On-Site Sewage Facilities.
- the minimum an Installer II certification.
- The installer must notify the designer and regulatory authority at least 48 hours in advance to schedule required inspections to ensure that the system in installed in accordance with approved plans and specifications.
- Diversion berms will be placed when seeded to protect irrigation and tank areas from excessive off.
- he respond by of scaller to ain the mum of requirements as stated apter 2 -Site ge Facilities.
- rt of stem be located with 0 fee pota ater line.

actrics management

All electric schall conform the requirements of the National Electric Code and terminated at a main circuit breaker panel or sub-panel. Connections shall be in approved junction boxes. All electrical components shall have an electrical disconnect within direct vision from the place where the electrical device is being serviced. Electrical disconnects must be weatherproof (approved for outdoor use) and have maintenance lockout provisions.

Tank Notes

- The bottom of the excavation for the tanks should be level and free of large rocks and debris.
- All tanks are to be set level on a minimum 4 inch layer of sand, sandy loam, clay loam, or pea gravel.
- Risers are required on tank inspection ports as per 30 TAC 285.38 (9/1/2012.) This includes
 access limitation (<65 lbs lid or hardware secured lid) and secondary plug, net, or mesh in riser.
 Risers are required to be two inches above grade level.
- All openings in the tank must be properly sealed to prevent the escape of wastewater, and/or to prevent the infiltration of water.
- Tanks must be filled with water for at least 24 hours to test for leaks and structural integrity.
- The tanks must be set low enough to have fall of at least 1/8 inch per foot from house to tank.
- PVC pipe from house to tank must be at least Sch. 40 or SDR 26.

Irrigation and Landscape Notes

- Irrigation lines should be 1 inch Sch. 40 PVC. All supply lines, sprinkler heads, and valve cover boxes must be permanently colored purple. Sleeve any pipe that crosses any road, driveway, or other land improvement with Sch. 40 PVC.
- Supply lines must be buried at least 6 inches below finished grade.
- If irrigation area does not have established vegetation, a mixture of winter rye or Bermuda grass will be seeded to establish seasonal vegetation.
- The installer will notify the property owner prior to removal of any trees/bushes that may
 obstruct the operation or the irrigation system.
- All exposed surface rock must be covered with at least 4 inches of suitable soil.

Additional Notes

- Install audio-visual alarm for aerator and pump on separate breakers.
- ne high wa' air coz and should lio/vi sed in a place that n be easiled and and should live are act.

Mair nce F eme

- e ap t must shi to the regular aut a val intenance of the with a tiff and intenance of the mean tiff and intenance of the me
- Renance of the work of the state of the st
- tial contract will 1 of 2 year
- A maintenance contract will authorize the maintenance company to maintain and repair the system as needed.
- The property owner must continuously maintain a signed written contract with a valid maintenance company and will submit a copy of the contract to the permitting authority at least

Affidavit

- The applicant must file a certified copy of an affidavit at the County Clerk's Office and file in reference to the real property deed on which the surface application system is to be installed.
- The affidavit will state that the property shall not be transferred to a new owner without:
 - The new owner being advised that the property contains a surface application system for wastewater disposal.
 - The permit issued to the previous owner of the property being transferred to the new owner in accordance with Chapter 285.3(b)(3) of the TCEQ OSSF Rules, i.e.; the permit will be issued in the name of the owner of the OSSF. Permits shall be transferred to the new owner automatically upon legal sale of the OSSF. The transfer of an OSSF permit under this section shall occur upon actual transfer of the property on which the OSSF is located unless ownership of the OSSF has been severed from the property.
 - o The new owners submitting a valid maintenance contract to the permitting authority.

Operation and Management Notes

- The OSSF should not be treated as a normal city sewer.
- Feminine hygiene products should never be disposed of in the toilet. Products such as these can be detrimental to a septic system, causing backups inside the home and/or overflowing of the tank due to pump malfunction.
- The excessive use of in-sink garbage grinders and grease discarding should be avoided. In-sink garbage grinders can cause a rapid buildup of sludge or scum resulting in a more frequent cleaning and possible system failure.
- Do not use the toilet to dispose of cleaning tissue, cigarette butts, or other trash. This disposal practice will waste water and also impose an undesirable solid load on the treatment system.
- Septic tanks should be cleaned before sludge accumulates to a point where it approaches the
 bottom of the outlet device. If sludge or scum accumulates to this point, solids will leave the
 tank with the liquid and possibly cause the sustem to slog resulting in sowage surfacing or
 backing up into the house through plumbing fixtures.
- A regular schedule of cleaning the tank at two to three year intervals should be established.
 Commercial cleaners are equipped to readily perform the cleaning operation. Owner of OSSF's will contract only persons registered with TCEQ to transport the septic system waste.
- Do not build driveways, storage buildings, or other structures of system components on the osal field.
- e nical add or so enzym not not no ry for peratic eptic tank.


 e of the ditive even be han to the em's tion.
- is, det is, blood, drain clean dot buset eaning mat will very may the open in of the syste were odera should be each the use of the class.
- e to the OSSF.
- The part of from the OSSF is any laden with teria. The part of this liquid constitutes a health hazard to those that might come into contact with it.

Water Conservation Practices

- Showers usually use less water than baths. Installing water saving shower heads that use less
 than 2.5 gailons per minute saves both water and energy.
- If you take a tub bath, reduce the level of water in the tub from the level to which you customarily fill it.
- Leaky faucets and faulty toilet fill-up mechanisms should be repaired as quickly as possible.
- Leaking toilets may not be evident. Add a few drops of food coloring into the tank. Do not
 flush. If the color appears in the bowl within a few minutes, adjustments and/or repairs to the
 toilet need to be made.
- Install low-flow fixtures throughout the house and use faucet aerators that restrict water flow to help reduce consumption.
- Try to run dishwasher with a full load.
- Avoid running the water continuously for brushing teeth, washing hands, shaving, or rinsing kitchen utensils.

- Water can be saved in the laundry room by adjusting water levels to match the size of the load.
 If the washing machine does not have a variable load control, water can be saved by supplied it only when the washer if full.
- Keep a container of drinking water in the refrigerator instead of running a faucet until it turns cold.
- Insulate hot water pipes to avoid long delays of wasted water while waiting for the water to heat.
- our feder e, cov local go lent a conserve

This property systems been upped general win minin equirement or TCEQ Chapters, in ewage it es. The site tion ubset design are on technical information of a low growth water or where seeps could occur, time of the site of the site of the standards occur, additions or modifications to the OSSF may need to be made. By accepting this design, the homeowner/builder understands that the designer/site evaluator will not be liable for more than the agreed upon design fee.



NOTES: BASIS OF BEARING IS TEXAS STATE PLANE COORDINATE SYSTEM OF 1983, SOUTH CENTRAL ZONE.


FND. PN = 1/2" REBAR FOUND
SET PN = 1/2" REBAR SET WITH YELLOW
PLASTIC CAP STAMPED TYCHLS 3682".
ELEVATIONS BASED ON NAVD 1988.

LEGEND

EM = ELEC. METER
WM = WATER HETER
AC = AR CONDITIONER
OR = DEED RECORDS
HAPR = MAP & PLAT RECORDS
OAKS = 8" DIA OAK TREE



SCALE: 1' = 60'



ADDRESS: 1016 ADYSON RIDGE DRIVE

SURVEY OF LOT 60, BLOCK 1, CENTENNIAL RIDGE, UNIT 3. CITY OF BULVERDE, COMAL. COUNTY, TEXAS, PLAT RECORDED IN DOC. 202006046126, OFFICIAL RECORDS, COMAL. COUNTY, TEXAS.


mcmichaellandsurveying.com
MCMICHAEL LAND SURVEYING
907 DIVINE #AY, NEW BRAUNFELS, TX 78130
EMAIL fred@mcmichaellandsurveying.com
(830) 632-6259 FIRM NO. 10193990


STATE OF TEXAS : COUNTY OF COMAL:

1, FRED I. HIMTOHAEL, DO HEREBY CERTIFY THAT THS PLAT WAS PREPARED FROM AN ACTUAL SURVEY HADE ON THE GROUND AND UNDER MY SUPERVISION.

FRED L MCMICHAEL R.P.L.S. NO. 3682

SURVEYED: JANUARY 15, 2025 PROJECT NO: 21184STK





SA600LP

LBC Manufacturing "EZ-Tank" **GRAVITY FLOW**


Liquid Bleach Chlorinator US Patent Pending

"Copyright Notice"
No part of this publication may be separated, stored in any univiews sys-transmitted in any form or by any resears, electronic, stockwistel, photo-recording, or otherwise without the pion withen permiseds of LEC MPG.

1.80 Manufacturing P.O. Box 454 Fayetieville, TEXAS 78940 (979) 828-0139 off.

RECOMMENDED INSTALLATION INSTRUCTIONS

- *** LBC Manufacturing recommends installation by TCEQ licensed and baland lostgilers.
- 1. Locate tim Aerobic System Holding/Pump tank
- 2. Remove the green access following screws and remove green access to.
- install we that sensing pipe into Holding/Pump tenk. Ensure sensing pipe is realing on the bottom of the Holding/Pump tenk. Cut the sensing pipe off below the top of the Holding/Pump tenk lid, and secure the sensing pipe to remain vertical in the Holding/Pump tenk
- 5. Place the EX-Tank reservoir halds the hubbling tests access door. (EX-Tank reservoir rests on this secondary safety lid middle the hubbling tests access about the hubbling tests access about the secondary safety lid. replace with new access itser that accommodates the secondary safety lid to code.)



standard 46 for Objection diskription devices. The EZ-Tank is listed an a certified chicking diskription device for scanding threated effluent. Confliction requires the device to be used with 6-10% sodium hypochlodie (household black) The E2-Tank Distriction device is a proving thou product that applied distributions to a halding tank as the water level isses that giving the ultimate arround of contact time to

THE LIQUID CHLORINATION PROCESS

LBC Manufacturing designed end built the "EZ-Tatal" to provide years of trouble-fee service. It is constructed from destable Polyethylane molecular which can veltostand the complex eather of Stoffum - Hypochisting behavior that the provided the provided to NSTANASI SI 44 and has proven to function must consistently, at a lower operating cost, then any other distribution method.

The bipain function of the Liquid Bleach Chlorisselor is to introduce diskelectant to the efficient water in the Holding/Pump tank as the officient esters. The larger the context time the dishelecant has to interest with pathogens, the better it dishelecant has to interest with pathogens, the better it dishelecant pathogens survival.

vice Plate located on the Fill Lid of the Liquid Chiofmator

n Liquid Chicrimator uses 6-10% Stodium Hypochicrite (Household Blanch). Do not use any other ducts and or chemicals other then specified, Always malchin o constant supply of disinfectant such in the Chicrimator Housing at all flows. The rate of disinfectant/Blanch usage will viry with distant homeownier water usage. It disinfectant usage increases or decreases, call the septice

province. If Bood waters, units, chemicals etc., other than Socilum Hypochicrite, enters the Chicelaster Housing, call "

**** Abusive use Personal Protective Equipment when Filling or Servicing the Chlorinstor*****


Open the Chinkmin FII Lid and Visually inspect the lipids level the chloring reservoir, Habitain a commant supply of Sodium Hypochicitic (Household Bleach) in the Chlorineter Housing and reservoir at all liness. Check Sprinkler discharge for Chlorine radduni. If Senion is required, cuter to the Date/Senion Plate Incided on the FII Lid of the chlorineter.

PERSONCALLY: Open the Chlorinator Fill Ltd and Visually inspect the Chlorinator for cloths such as dirt, grasp elippings etc. Check Sprintler discharge for Chlorine residual. If Seni required, refer to the Data/Service Plate located on the Fill Ltd of the Chlorinator reservoir.

Visually impact the Chlorineter Housing for any densage from lawnscewers, etc. Passove distinct total up, grass, etc. from Chlorineter Housing Fill Ltd. Cheek Sprinter decharge for Chlorine readon!. If Service is required, refer to the Data/Serdon Fileta located on the Fill Ltd of the Chlorineter reservoir.

FOR INTERMITTENT PERSONS OR EXTENDED PERSONS OF MONAUME

The EX_Twink is designed to function under normal use or interestant periods of use. If paints of nor use expend 6 months, drain Caterinator Heusing and retil with 6-10% Socilum hypochable. If Screice is required, refer to the Data/Service Piete bested on the Fill Lid of the Chlerkwise reservoir,




82	Available with	а гиви физи	uà 113 a ot	230 V, 73	ub maror

- Fluid flows of 10, 20, and 30 gpm, with a max shut-off pressure of over 100 psi
- ## Heavy duty 600 V 10 foot SJOOW jacketed lead

ORDERIN	G INFO	RMATIC	ĴN -										
C1 Series Pumps													
GPM	HP	Volts	Stage	Model No.	Order No.	Length (in)	Weight (lbs)						
10		115	7	10C1-05P4-2W115	90301005	26	17						
101		230	7	10C1-05P4-2W230	90301010	26	17						
20		115	5	20C1-05P4-2W115	90302005	25	16						
20	1/2	-230 .	5	20C1-05P4-2W230	90302010	25	16						
201	1/2	115	6	20XC1-05P4-2W115	90302015	26	17						
20/		230	6	. 20XC1-05P4-2W230	90302020	26	17						
30		115	4	30C1-05P4-2W115	90303005	25	16						
50		230	4-	30C1_05P4-2W230	90303010	25	16						

Note: All wills have 10 foot long SJOOW leads.





- > 3/4" Inlet-Replaces all standard cotors.
- 2N1 Adjustable or Continuous Retation Provides a full range adjustment from 40° to a continuous full sincie.
- Patentiad Arc Set Degree Markings –
 Diearly Indicates the current watering carters
 and simplifies arc set adjustment.
- Arc Memory Clutch Prevents internal gear damage and returns rotor to its prior setting automatically if nozzle tunet is forced past its stop.
- Time Proven Patented Reversing Mechanism Assures continuous reverse and return over a 20 year ristory.

- Rationeting Riser Mowe for easy adjustment of your left starting position with a sample turn of the riser.
- Rubber Cover Seas out dirt and noreases product durability.
- Wide Selection of Nozzles including standard and low engle provides flexibility in system design.
- Optional Check Valve 3-events low head drainage.



IRRIGATION SO WORLDW



RAIN. Pro*Plus* Performance Data

Model Numbers: 11003, 11003-HP, 11003-SH, 11003-RCW • Arc Adjust: 40-360 • Drive Type: Gcar • Warranty: 5 years

Standard Performance Data:

Metric Performance Data:

Nozzic	Pressure (PSI)	Radius (ft)	Flow (GPM)	Precip (IN/HR)	Precip (IN/HR)	Nozzle	Pressure (bar)	Radius (meter)	Flow (1/m)	Precip (mm/hr)	Precip (mro/hr)
				F3	A	•					A
0.5	30 40	28- 29	0.5· 0.6	0.06 0.07	0.07 0.08	0.5	2.0 3.0 3.5	8.5 8.8 8.8	1.9 2.3 2.6	1.6 1.7 2.0	1.8 2.0 2.3
	60	30	0.8	0.09	0.10	2		9.1	,3, U		2.5
	30		0.7		0.09		2.0 .	8.8	2.6	2.0	. 3
			0.8		0.10		3.0	. 9.1	3.0 ;	2.2	2.2
		31	0.9		0.10		3.5	9.4	3.4	2.3	.2.6
	60		.1.0			8	4.0	9.8	3.8 4.9	2.4	2.8 3.6
1	30		1.3		0.14	I I	2.0	9.8	4.9	3.1	3.6
		. 33	1.5	0.13	0.15		3.0	10.1	5.7	3.4	3.9
		34	1.6	0.13	0.15		3.5	18.4	6.1	3.4	3.9
		35	110	0.14	16		4.0	10.0	6.8	3.6	
2		37	A. Carrier	-		2	2.0			4.3	4.9
de		40	2.5			1	3.0			3.8	4.4
		42	3.0				3.5	12.8		4.2	4.8
		· A	3.3	17	0	1	4.0	13:1		4.4	5.0
		te direction and the control of	19 5	0.17	0.1		2.	11.6		4.2	4.9
Pre-			2.1	0.18	0.21		3	11,9		4.5	5.2
nstalled			2	0.19	0.2	Total	3	12.2		4.9	5.6
			2	0.20	0.2			12.5		5.1	5.9
	-00° 10° 10° 10° 10° 10° 10° 10° 10° 10°			0.24	0.7	Emp. Apper 91		11.6		6.1	
3			4	0.27	U.	ì		11.9		6.8	7.8 .
			- 4.	0.26	:	ì		12.5		6.7	7.7
		100	5.0	0,20				10.8			
and a second second	***************************************	61 L	4.4	Sala I	A			d alore the	7		
4		43 44	5.1						19.3	6.4	7.4
		46	5.6		0.29				21.2	6.5	7.5
	60			0.24	0.27		. 4.0	14.9	22.3	6.0	
			5.9			6	3.0	13.7	22.3	7.I	
			5.9	0.28	0.32	. 0	3.5	14.0	22.7	. 6.9	8.0
	50 .		6.0	0.27			4,0	14.6	23.8	6,7	7.7
	60		6.3	0.26	0.30				25.4	6.8	7.7
	70	49	6.7	0.27	16.0		5.0	14.9	30.3	11.1	1.7
8	40	42	8.0	0.44	0.50		3.0	13.7	32.2	10.3	.0
	. 50 -	45	8.5	0:48	0.47	***************************************	3.3	13.7	344	10.3	11.2
	70	50	10.0	0.39	0.44	1	5.0	15.2	37.9	9.8	11.3

Low Angle Standard Performance Data

Low Angle Metric Performance Data

12 degree t	raiectory		12 degree trajectory									
Nozzle	Pressure (PSI)	Radius (ft)	Flow (GPM)	Precip (IN/HR)	Precip (IN/HR)		Nozzie	Pressure (bar)	Radius (moter)	Flow (1/m)	Precip (mm/br)	Precip (mm/hr)
;						÷ ;		•			18.5	A
1 1	30	22	1.2	0.24	0.28	1	1	2.0	6.7	4.5	6.1	7.0
-	49	24	1.7	0.28 :.	0.33			3.0	7.3	6.4	7.2	8.3
	50	26	- 1.8	0.26	0.30			3.5	· 7.9	6.8	6.5	7.5
	_ 60	28	2.0	0.25	0.28	. L		4.0 .	8.5	7.6	6.2	7.2
3	30	29	3.0	0.34	0.40	. !	3	2.0	8.8	11.4	8.7	10.1
	40	32	3.1	0.29	0_34	ž - 1		3.0	9.8	11.7	7.4	8.5
1	50	35	3.5	0.28	0.32			3.5	10.7	13.2	7.0	8.1
1	60	37	3.8,	0.27	0.31	1 1		4.0	11.3	14.4	6.8	7.8
4-	30	18	3.4	0.34	0.39	T [.	4	2.0	9.4	12.9	8.6	10.0
	40	34	3.9	0.32	0.37	1 [3.0	10.4	14.8	8.2	9.5
	50	37	4.4	0.31	0.36			3.5	11.3	16.7	7.9	9.1
	60	38	4.7	0.31	0.36_	1		4.0	11.6	17.8	8.0	9.2
6.	40	38	6.5	0.43	0.50	:	6	3.0	11.6	24.6	11.0	12.7
1	50	40	7.3	0.44	0.51	:		3.5	12.2	27.6	11.2	12.9
•	60	42	8.0	0.44	0.50			4.0	12.8	30.3	11.1	12.8
	70	44	8.6	0.43	0.49			5.0	13.4	32.6	10.9	12.5



The proposed system has been designed to serve a 5 Bedroom (equivalent) Single Family Residence that will be < 4,500 sq ft. It will have a maximum daily water usage rate of 360 gal/day, as per table III of the Chapter 285 Rules for On-Site Sewage Facilities by the TCEQ.

Site Description and Site Evaluation

The subject property is located within a subdivision. The legal description is Unit 3, Lot 60, Block 1 in the Centennial Ridge Subdivision. The existing vegetation consists of some native grasses. The site evaluation indicated that the site has suitable soil for an aerobic surface irrigation system. No evidence of shallow ground water was observed during the site evaluation. All exposed rock within the proposed surface distribution area will be removed or covered with suitable soil and seeded prior to final

slope of less than 15 percent within the proposed surface distribution area. The residence will utilize a private well water supply as the source for potable water. All of the systems components will be 100 feet away from all wells. All portions of the spray radii will maintain at least a 20 feet separation from all property lines. No portion of this system lies within 10 feet of a waterline. There are no recharge features 150 feet of proposed Minimum station at least a 20 feet separation from all property lines. Stated in Chapter 285.30 TO In-Site Section 150 feet of Facility and the stated in Chapter tained.

Description Prop Aer reatment m

The reside will use a Solar Merobic waster ray Mode LP. It is a pretary treatment of the ded by the for use in Tender of the ded by the for use in Tender of the ded by the for use in Tender of the ded by the for use in Tender of the ded by the for use in Tender of the ded by the ded by

Design Specifications

Size of Residence: < 4,500 sq. ft.

Number of Bedrooms: 4 + Study with closet Average Expected Daily Flow (Q): 360 gpd

Application Rate: 0.064 gal/ft²/day

Minimum Application Area Required (A=Q/Ra): A= 360/0.064 = 5,626 ft²

Actual Application Area: 5,652 ft²

System Components

Pretreatment/Trash Tank: 375 gal

Aeration Tank: 785 gal

Pump Tank: 778 gal (41.5 inches of usable space) – 18.75 gallons/inch







Pump Float Settings

Pump Off Position: 7 in. above tank floor = 131.25 gal Pump On Position: 8 in. above tank floor = 150.00 gal Alarm On Position: 28 in. above tank floor = 525.00 gal

Reserve Capacity: 13.5 in. (778 gal – 525.00 gal) = 253.00 gal (> 2/3 estimated gpd)

Pump and Sprinkler Heads

Elevation Head: 6 ft

Pressure Head: $30 \text{ psi} \times 2.3 = 69$

Total I (TDH): 6 + 2.1 .13 ft (the pu erfor e curv.

Pump: klin F c C1 10Cl-05P4-2

Sprinkle ac Rain Pro Professiona es w w An bzzle #4, o ng at 30 psi, 30 ft

radius, a m flow pe kler.

Chlorinator

This system will utilize a NSF approved Liquid Chlorinator.

Dosing:

This system will utilize a commercial timerre systematical national difficulty and system will be a system of the system of the

Disposal period for overnight disposal is between midnight and 5 AM.

360 gpd/2 doses per day = 180 gal per dose

2 sprinklers x 3.4 gal per minute = 6.8 gallons per minute

180 gal per dose/6.8 gal per minute ≈ 27 minutes per dose





construction/installation Notes & Requirements

- Refer to site plan for component placement and follow manufacturer's instructions for installation of treatment plant and aerator.
- All materials and construction methods are required to conform to the standards for Private Sewage Facilities set forth by the Texas Administrative Code, Chapter 285 On-Site Sewage Facilities.
- The installer must have a current and valid Texas installer certificate, and is required to have at the minimum an Installer II certification.
- The installer must notify the designer and regulatory authority at least 48 hours in advance to schedule required inspections to ensure that the system in installed in accordance with approved plans and specifications.
- Diversion berms will be placed when needed to protect irrigation and tank areas from excessive runoff.
- It is the responsibility of the installer to maintain the minimum setback requirements as stated in Chapter 285 On-Site Sewage Facilities.
- It is to fit the symmetry shall be seen to find 10 feet potal

All electric ring Confo the requirer of t tiona tric Code (or under any other star) is at ed by t ecutive direct Addi III, all rinal wiring be installed in approved, a letallic to be electric duit cond hall be buy cording to the requireme. National E. Code at linat a maturit breat let or sub-panel. Connection the in approved All electrical disconnect within direct vision from the place where the electrical device is being serviced. Electrical

provisions.

Jank Notes

- The bottom of the excavation for the tanks should be level and free of large rocks and debris.
- All tanks are to be set level on a minimum 4 inch layer of sand, sandy loam, clay loam, or pea gravel.
- Risers are required on tank inspection ports as per 30 TAC 285.38 (9/1/2012.) This includes access limitation (<65 lbs lid or hardware secured lid) and secondary plug, net, or mesh in riser. Risers are required to be two inches above grade level.
- All openings in the tank must be properly sealed to prevent the escape of wastewater, and/or to prevent the infiltration of water.
- Tanks must be filled with water for at least 24 hours to test for leaks and structural integrity.
- The tanks must be set low enough to have fall of at least 1/8 inch per foot from house to tank.
- PVC pipe from house to tank must be at least Sch. 40 or SDR 26.



irrigation and Lanuscape Notes

- Irrigation lines should be 1 inch Sch. 40 PVC. All supply lines, sprinkler heads, and valve cover boxes must be permanently colored purple. Sleeve any pipe that crosses any road, driveway, or other land improvement with Sch. 40 PVC.
- Supply lines must be buried at least 6 inches below finished grade.
- If irrigation area does not have established vegetation, a mixture of winter rye or Bermuda grass will be seeded to establish seasonal vegetation.
- The installer will notify the property owner prior to removal of any trees/bushes that may obstruct the operation of the irrigation system.
- All exposed surface rock must be covered with at least 4 inches of suitable soil.

Additional Notes

- Install audio-visual alarm for aerator and pump on separate breakers
- The high water and air compressor alarms should be audio/visual and mounted in a place that can be easily seen and heard when alarms are activated.

Mainto ce Requestents

- applica set for to the regular authors and intenance act with a lied of enance appropriate the issue.
- hair ince come y will verify the state is on the property provide on-
- T contract w minim 2 yea
- A nance contract the magnitude ance system as needed.
- The property owner must continuously maintain a signed written contract with a valid maintenance company and will submit a copy of the contract to the permitting authority at lea 30 days prior to the date service will cease.

Affidavit

- The applicant must file a certified copy of an affidavit at the County Clerk's Office and file in reference to the real property deed on which the surface application system is to be installed.
- The affidavit will state that the property shall not be transferred to a new owner without:
 - The new owner being advised that the property contains a surface application system for wastewater disposal.
 - The permit issued to the previous owner of the property being transferred to the new owner in accordance with Chapter 285.3(b)(3) of the TCEQ OSSF Rules, i.e.; the permit will be issued in the name of the owner of the OSSF. Permits shall be transferred to the new owner automatically upon legal sale of the OSSF. The transfer of an OSSF permit under this section shall occur upon actual transfer of the property on which the OSSF is located unless ownership of the OSSF has been severed from the property.
 - The new owners submitting a valid maintenance contract to the permitting authority.



Operation and Management Notes

- The OSSF should not be treated as a normal city sewer.
- Feminine hygiene products should never be disposed of in the toilet. Products such as these can
 be detrimental to a septic system, causing backups inside the home and/or overflowing of the
 tank due to pump malfunction.
- The excessive use of in-sink garbage grinders and grease discarding should be avoided. In-sink
 garbage grinders can cause a rapid buildup of sludge or scum resulting in a more frequent
 cleaning and possible system failure.
- Do not use the toilet to dispose of cleaning tissue, cigarette butts, or other trash. This disposal practice will waste water and also impose an undesirable solid load on the treatment system.
- better tanks should be cleaned before sludge accumulates to a point where it approaches the bottom of the outlet device. If sludge or scum accumulates to this point, solids will leave the tank with the liquid and possibly cause the system to clog resulting in sewage surfacing or backing up into the house through plumbing fixtures.
- A regular schedule of cleaning the tank at two to three year intervals should be established.

 Communication of cleaning the tank at two to three year intervals should be established.

 Ser of OSSF's will control to the control of t
- Do not all driver story alldings, or struct of sy compone to the dispose of.
- Chemic diti/ /r so-c enzymes, are ece for the eration of a c tank.

 Some of second vives may be harmful to be second vives may be second vives may be harmful to be second vives may be seco
- Soaps, d , bleaches cleaner othe sehol ning ma will very seldom e operation d wever eration of such researches.
- The homeowner shall observe Chapter 285.37 regarding water softeners and reverse osmosis
 entering into the OSSF.
- The liquid from the OSSF is still heavily laden with bacteria. The surfacing of this liquid constitutes a health hazard to those that might come into contact with it.


Water Conservation Practices

- Showers usually use less water than baths. Installing water saving shower heads that use less than 2.5 gallons per minute saves both water and energy.
- If you take a tub bath, reduce the level of water in the tub from the level to which you customarily fill it.
- Leaky faucets and faulty toilet fill-up mechanisms should be repaired as quickly as possible.
- Leaking toilets may not be evident. Add a few drops of food coloring into the tank. Do not flush. If the color appears in the bowl within a few minutes, adjustments and/or repairs to the toilet need to be made.
- Install low-flow fixtures throughout the house and use faucet aerators that restrict water flow to help reduce consumption.
- Try to run dishwasher with a full load.
- Avoid running the water continuously for brushing teeth, washing hands, shaving, or rinsing kitchen utensils.



- Water can be saved in the laundry room by adjusting water levels to match the size of the load. If the washing machine does not have a variable load control, water can be saved by running it only when the washer if full.
- Keep a container of drinking water in the refrigerator instead of running a faucet until it turns cold.
- heat.
- Ask your federal, state, county, city, or other local government about programs to conserve
 water and how they can help you save water.

esign ar sequ the site e Chapter 28 Site Se rater or slo ble. was no indi ofs w gro ot be f the is not, and luation. The rma could occur the si is of the Sta d with. If should all pro s ha en co guaranteed, epting th OSSF m n, the d to re than the



PERMIT



PERMIT #: 2025-288

PROJECT ADDRESS: 1016 Adyson Ridge Drive NSFR

DESIGNATION: Residential

OWNER NAME: Steven and Natalie Wiggins PERMIT TYPE: New Single Family

(Residential)

ISSUED TO (CONTRACTOR): Stone Creek Custom Homes - Blake Libert

25120 Blanco Road (210) 287-2100 Blake@stonecreekcustomhomes.com

Issued Date: August 01, 2025

Expiration Date: January 28, 2026

STIPULATIONS IF ANY:

THIS PERMIT MUST BE POSTED IN A CONSPICUOUS PLACE ON CONSTRUCTION SITE

PERMIT



INSPECTION INFORMATION

- TO SCHEDULE INSPECTIONS PLEASE REQUEST ONLINE VIA https://mgoconnect.org/cp/portal. Please schedule by 2pm for next day inspections.
- REQUIRED INSPECTIONS:

Required inspections are subject to change at the discrection of the Jurisdiction.

- o Electric Trench
- o Gas Rough In
- o Sewer Yard Line
- o Shear Wall/Exterior Sheathing
- o TML (Electrical Temporary Meter Loop)
- o Water Service
- o Plumbing Rough
- o Foundation Pre Pour
- o Electrical Rough
- o Framing
- o Mechanical Rough
- o Plumbing Top Out
- o Insulation
- o Shower Pan
- o TOPS (Electrical Temporary on Permanent Set
- o Gas Final
- o Building Final
- o Electrical Final
- o Mechanical Final
- o Plumbing Final

PERMIT



- For all other questions regarding building & permitting please contact:
 - o Claudia Cardenas, ccardenas@bulverdetx.gov
 - o Bailey Dorn, bdorn@bulverdetx.gov
 - o Heath Edwards, hedwards@bulverdetx.gov

CTT4300312400801CR

General Warranty Deed with Vendor's Lien

Notice of confidentiality rights: If you are a natural person, you may remove or strike any or all of the following information from any instrument that transfers an interest in real property before it is filed for record in the public records: your Social Security number or your driver's license number.

Date: Effective as of October 9, 2024, regardless of the date(s) actually executed by the undersigned

Grantor: Paul S. Uribe and Cherie M. Uribe FKA Cherie M. Patti

Grantee: Steven J. Wiggins and Natalie R. Wiggins, a married couple

2154 Appellation New Braunfels, TX 78132

Consideration: Ten and No/100ths (\$10.00) Dollars, and other good and valuable consideration, the receipt and sufficiency of which is hereby acknowledged and confessed, and the further consideration of the execution and delivery by said Grantee of a certain Promissory Note in the principal amount of \$273,600.00, of even date herewith, payable to the order of First Commercial Bank, N.A., hereinafter referred to as the "Mortgagee", bearing interest at the rate therein provided. The note is secured by a vendor's lien retained in this deed in favor of First Commercial Bank, N.A., and by a deed of trust of even date from Grantee to Mark A. Long, Trustee.

Whereas the Mortgagee has, at the special instance and request of Grantee, paid to Grantor a portion of the purchase price of the Property, as included in the above-described Promissory Note, the said vendor's lien against the Property securing the payment of the Promissory Note and superior title are hereby assigned, transferred and delivered to Mortgagee, Grantor hereby conveying to said Mortgagee the superior title to the Property, subrogating said Mortgagee to all the rights and remedies of Grantor in the premises by virtue of said lien.

Property (including any improvements): Lot 60, Block 1, Centennial Ridge Unit 3, a subdivision in Comal County, Texas, according to the map or plat thereof recorded in Document No. 202006046126, Map and Plat Records, Comal County, Texas.

Reservations from Conveyance: None.

Exceptions to Conveyance and Warranty: Vendor's lien and superior title retained in this deed, validly existing easements, rights-of-way, and prescriptive rights, whether of record or not; all presently recorded and validly existing restrictions, reservations, covenants, conditions, oil and gas leases, mineral interests, and water interests outstanding in persons other than Grantor, and other instruments, other than conveyances of the surface fee estate, that affect the Property; validly existing rights of adjoining owners in any walls and fences situated on a common boundary; any discrepancies, conflicts, or shortages in area or boundary lines; any encroachments or overlapping of improvements; and taxes for the current year, which Grantee assumes and agrees to pay, and subsequent assessments for that and prior years due to change in land usage, ownership, or both, the payment of which Grantee assumes.

Grantor, for the Consideration and subject to the Reservations from Conveyance and the Exceptions to Conveyance and Warranty, grants, sells, and conveys to Grantee the Property, together with any and all improvements and all and singular the rights and appurtenances thereto in any way belonging, to have and to hold it to Grantee and Grantee's heirs, successors, and assigns forever. Grantor binds Grantor and Grantor's heirs and successors to warrant and forever defend all and singular the Property to Grantee and Grantee's heirs, successors, and assigns against every person whomsoever lawfully claiming or to claim the same or any part thereof, except as to the Reservations from Conveyance and the Exceptions to Conveyance and Warranty.

It is expressly agreed that the vendor's lien herein described and superior title are retained in favor of the payee of the Promissory Note hereinabove described against the Property and any improvements thereon, until said Promissory Note and all interest thereon shall have been fully paid according to the terms thereof, at which time this deed will become absolute.

When the context requires, singular nouns and pronouns include the plural. Additionally, this instrument may be executed in multiple counterparts and by different parties in separate counterparts, which, when taken together, shall constitute one original instrument.

Paul S. Uribe

THE STATE OF

COUNTY OF ___

-Bend

This instrument was acknowledged before me by means of an interactive two-way audio and video communication on this ____ day of October, 2024, by Paul S. Uribe. This notarial act was an online notarization.

SHARON S MILLER
Notary ID #124242587
My Commission Expires
December 7, 2025

Notary Public, State of

Cherie M. Uribe

COUNTY OF FORT BEND

This instrument was acknowledged before me by means of an interactive two-way audio and video communication on this day of October, 2024, by Cherie M. Uribe. This notarial act was an online notarization.



Notary Public, State of Toyas

After Recording Return To: Steven J. Wiggins and Natalie R. Wiggins

2154 Appellation New Braunfels, TX 78132 Filed and Recorded Official Public Records Bobbie Koepp, County Clerk Comal County, Texas 10/10/2024 01:40:25 PM CHRISTY 3 Pages(s) 202406030922

