

Permit of Authorization to Construct an On-Site Sewage Facility Permit Valid For One Year From Date Issued

Permit Number: 119074

Issued This Date: 11/14/2025

This permit is hereby given to: Stuart Wentworth

To start construction of a private, on-site sewage facility located at:

1188 BLUERIDGE DR CANYON LAKE, TX 78133

Subdivision: Canyon Lake Hills

Unit: 1

Lot: 145

Block: 0

Acreage: 0.0000

APPROVED MINIMUM SIZES AS PER ATTACHED DESIGN

Type of System: Aerobic

Drip Irrigation

This permit gives permission for the construction of the above referenced on-site facility to commence. Installation must be completed by an installer holding a valid registration card from the Texas Commission on Environmental Quality (TCEQ). Installation and inspection must comply with current TCEQ and Comal County requirements.

Call (830) 608-2090 to schedule inspections.





OSSF DEVELOPMENT APPLICATION CHECKLIST

Staff will complete shaded items

| and the End of Fide | | | |
|-------------------------------------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|----------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|
| | Date Received | Initials | Permit Number |
| Instructions: | | | |
| Place a check mark next to all items that apply. For iter Checklist <u>must</u> accompany the completed application. | ms that do not apply, plac | ce "N/A". This O | SSF Development Application |
| OSSF Permit | | | |
| Completed Application for Permit for Authorization | n to Construct an On-Site | Sewage Facility | and License to Operate |
| Site/Soil Evaluation Completed by a Certified Site | Evaluator or a Profession | nal Engineer | |
| Planning Materials of the OSSF as Required by the of a scaled design and all system specifications. | ne TCEQ Rules for OSSF | Chapter 285. P | lanning Materials shall cons |
| Required Permit Fee - See Attached Fee Schedul | le | | |
| Copy of Recorded Deed | | | |
| Surface Application/Aerobic Treatment System | | | |
| Recorded Certification of OSSF Requiring N | Maintenance/Affidavit to th | ne Public | |
| Signed Maintenance Contract with Effective | Date as Issuance of Lice | ense to Operate | |
| | er terre antenne per e provincia (1799) provincia e e escribilitario, combine non antenne de como meneral e escalargo (1700 de la completa e provincia e e Maria | | er yezhoù ez El Allen e eo euske e en euske e euske e Benedik e euske e eusk Benedik e |
| | | | |
| affirm that I have provided all information required constitutes a completed OSSF Development Applications | l for my OSSF Developr ation. | nent Applicatio | n and that this application |
| att the | | | |
| Elisteth Mewer | 10/31/ | 2025 | |
| Signature of Applicant | | Da | te |
| Check No Receipt No. | (Mis | | E APPLICATION ed, Application Refeused) |



ON-SITE SEWAGE FACILITY APPLICATION

195 DAVID JONAS DR NEW BRAUNFELS, TX 78132 (830) 608-2090 <u>WWW.CCEO.ORG</u>

| and some of the same | | Kecely | | | | AND THE RESERVE THE PARTY OF TH | |
|---------------------------------|------------------------------------------------------------------------------------------------------------|---------------------------------------|--------------------|--------------------|------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|
| Date | | Brandon Mark (11/13/2025 9:07: | Permit Number | | | | |
| | T / AGENT INFORMATION | | | | | | |
| Owner Name | NTWORTH STUART II TRUST | & MEURER LIVING T | RUST Agent Name | David Winte | rs Septics LLC |). | |
| Mailing Addre | ss 1187 Blueridge Dr. | | Agent Address | P.O Box 195 | | | |
| City, State, Zij | Canyon Lake, TX 78133 | | City, State, Zip | Spring Brand | ch, TX 78070 | | |
| Phone # | 925-203-0071 | | Phone # | 830-935-247 | 7 | | |
| Email | Stuart@Qualityproduct.com | | Email | Winterssepti | cs@gvtc.com | | |
| 2. LOCATION | | | | | | | |
| Subdivision N | ame Canyon Lake Hills | | U | nit 1 | Lot 145 | Block | |
| Survey Name | / Abstract Number | | | | Acreage | | |
| Address 1188 | B Blueridge Dr. | Ci | ty Canyon Lake | | State TX | Zip 78133 | |
| | EVELOPMENT | Andrea Agreement | | | | | |
| ⊠ Single F | amily Residential | | | | | | |
| | Construction (House, Mobile, I | RV. Etc.) House | | | | | |
| | of Bedrooms 2 | | | | | | |
| | Sq Ft of Living Area 1264 | | | | | | |
| | gle Family Residential | | | | | | |
| | gie i armiy ixesidential g materials must show adequate la | and area for doubling the | roquired land need | dad for tractmo | nt units and dis | l\ | |
| | | ind area for doubling the r | equired land need | ied for treatme | nt units and dis | posar area) | |
| Type of | | | | | | | |
| | Factories, Churches, Schools, | | Number Of Occi | ipants | | | |
| | ants, Lounges, Theaters - Indic | | | | | | |
| Hotel, M | lotel, Hospital, Nursing Home - | Indicate Number of Be | eds | | | | |
| Travel T | railer/RV Parks - Indicate Num | ber of Spaces | | | | | |
| Miscella | neous | | | | | | |
| | | | | | | | |
| Estimated C | ost of Construction: \$200, | 000 (Str | ucture Only) | | | | |
| Is any portio | on of the proposed OSSF locate | ed in the United States | Army Corps of | Engineers (U | SACE) flowag | e easement? | |
| ☐ Yes ⊠ | No (If yes, owner must provide a | approval from USACE for pro | posed OSSF impro | vements within the | ne USACE flowag | ge easement) | |
| Source of Wa | ater 🔀 Public 🗌 Private V | Well Rainwater | | | | | |
| 4. SIGNATURI | E OF OWNER | | | | | | |
| - The completed | pplication, I certify that: application and all additional infor hat I am the property owner or I po | | | | | | |
| | s hereby given to the permitting aution and inspection of private sewa | | ents to enter upo | n the above de | scribed propert | y for the purpose o | |
| I understand the by the Comal C | at a permit of authorization to cons County Flood Damage Prevention (| struct will not be issued u Order. | | | | | |
| I affirmatively c | onsent to the online posting/public | release of my e-mail add | Iress associated v | with this permit | application, as | applicable. | |
| THE | great | | 10/31/20 | 025 | | | |
| Signature of | Owner M | | Date | | | Page 1 o | |





PPLICATION

195 DAVID JONAS DR NEW BRAUNFELS, TX 78132 (830) 608-2090 WWW.CCEO.ORG

| Planning Materials & Site Evaluation as Required Completed By Garrett R. Winters R.S | | | | | | | | |
|-------------------------------------------------------------------------------------------------------------------------------------------------------------------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|--|--|--|--|--|--|
| System Description Aerobic System W/ Drip Application | | | | | | | | |
| Size of Septic System Required Based on Planning Materials | & Soil Evaluation | | | | | | | |
| Tank Size(s) (Gallons) 600gpd | Absorption/Application Area (Sq Ft) 1264 | | | | | | | |
| Gallons Per Day (As Per TCEQ Table III) 180 | | | | | | | | |
| (Sites generating more than 5000 gallons per day are required to obtain | ain a permit through TCEQ.) | | | | | | | |
| Is the property located over the Edwards Recharge Zone? |] Yes 🔀 No | | | | | | | |
| (If yes, the planning materials must be completed by a Registered Sa | anitarian (R.S.) or Professional Engineer (P.E.)) | | | | | | | |
| Is there an existing TCEQ approved WPAP for the property? | Yes X No | | | | | | | |
| (If yes, the R.S. or P.E. shall certify that the OSSF design complies v | vith all provisions of the existing WPAP.) | | | | | | | |
| If there is no existing WPAP, does the proposed development | activity require a TCEQ approved WPAP? Yes No | | | | | | | |
| (If yes, the R.S. or P.E. shall certify that the OSSF design will comply be issued for the proposed OSSF until the proposed WPAP has bee | with all provisions of the proposed WPAP. A Permit to Construct will not n approved by the appropriate regional office.) | | | | | | | |
| Is the property located over the Edwards Contributing Zone? | Yes □ No | | | | | | | |
| Is there an existing TCEQ approval CZP for the property? | Yes No | | | | | | | |
| (If yes, the P.E. or R.S. shall certify that the OSSF design complies v | vith all provisions of the existing CZP.) | | | | | | | |
| If there is no existing CZP, does the proposed development a | ctivity require a TCEQ approved CZP? 🔲 Yes 🔀 No | | | | | | | |
| (If yes, the R.S. or P.E. shall certify that the OSSF design will comply issued for the proposed OSSF until the CZP has been approved by t | with all provisions of the proposed CZP. A Permit to Construct will not be he appropriate regional office.) | | | | | | | |
| Is this property within an incorporated city? $\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \$ | O SERVE OF TELLON | | | | | | | |
| If yes, indicate the city: | GARRETT R. WINTERS 5213 **EGISTER** **COINTERS** **COI | | | | | | | |
| | Hanri Im | | | | | | | |
| By signing this application, I certify that: | my knowledge | | | | | | | |
| The information provided above is true and correct to the best of I affirmatively consent to the online posting/public release of my | my knowledge. e-mail address associated with this permit application, as applicable. | | | | | | | |
| Manuella P.S | 11/3/2025 | | | | | | | |
| Signature of Designer | Date | | | | | | | |

COUNTY OF COMAL STATE OF TEXAS

AFFIDAVIT TO THE PUBLIC

CERTIFICATION OF OSSF REQUIRING MAINTENANCE

According to Texas Commission on Environmental Quality (TCEQ) Rules for On-Site Sewage Facilities (OSSFs), this document is filed in the Deed Records of Comal County, Texas.

The Texas Health and Safety Code, Chapter 366 authorizes the Texas Commission on Environmental Quality (TCEQ) to regulate on-site sewage facilities (OSSFs). Additionally, the Texas Water Code (TWC), § 5.012 and § 5.013, give the commission primary responsibility for implementing the laws of the State of Texas relating to water and adopting rules necessary to carry out its powers and duties under the TWC. The commission, under the authority of the TWC and the Texas Health and Safety Code, requires owners to provide notice to the public that certain types of OSSFs are located on specific pieces of property. To achieve this notice, the commission requires a recorded affidavit. Additionally, the owner must provide proof of the recording to the OSSF permitting authority. This recorded affidavit is not a representation or warranty by the commission of the suitability of this OSSF, nor does it constitute any guarantee by the commission that the appropriate OSSF was installed.

An OSSF requiring a maintenance contract, according to 30 Texas Administrative Code § 285.91 (12) will be installed on the properly described as (insert legal description):

Lot 145, Canyon Lake Hills, Unit 1, according to the map or plat recorded

in Volume 2, Page 17, Comal County, Texas

The property is owned by (Insert owner's full name):

WENTWORTH STUART II TRUST & MEURER LIVING TRUST

This OSSF must be covered by a continuous maintenance contract for the first two years. After the initial two-year service policy, the owner of an aerobic treatment system for a single family residence shall either obtain a maintenance contract within 30 days or maintain the system personally.

Upon sale or transfer of the above described property, the permit for the OSSF shall be transferred to the buyer or new owner. A copy of the planning materials for OSSF may be obtained from Comal County Engineer's Office.

| WITNESS BY HAND(S) ON THIS 26 DAY OF 304 | 2024 |
|-----------------------------------------------------------------------------|------------------------------|
| photoplando | STUART H WENTWORTH |
| afel Mewer | ELIZABETH MEURER |
| Owner(s) signature(s) | (PRINTED NAME) |
| SWORN TO AND SUBSCRIBED BEFORE ME ON THIS 26 DA | AYOF JULY ZUZY ATTACH (ED |
| Notary Public, State of Texas Notary's Printed Name: My Commission Expires: | TI POTED |

ACKNOWLEDGMENT

A notary public or other officer completing this certificate verifies only the identity of the individual who signed the document to which this certificate is attached, and not the truthfulness, accuracy, or validity of that document.

| State of Califo | ornia Alameda | |) | |
|----------------------------------|------------------------------------------|---------------------------------------|--------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------------------|
| On July 26 | , 2024 | before me, | SUNIL VA | SWANI, Notary Public name and title of the officer) |
| personally ap | peared STUAR | T H. WENTWO | RTH and E | IZABETH J. MEURER |
| subscribed to his/her/their a | the within instrum uthorized capacity | nent and acknow y(ies), and that b | rledged to m by his/her/the | e the person(s) whose name(s) is/are e that he/she/they executed the same in eir signature(s) on the instrument the acted, executed the instrument. |
| - | PENALTY OF Perus and correct. | ERJURY under t | he laws of t | ne State of California that the foregoing |
| WITNESS my | hand and official | seal. | | SUNIL VASWANI Notary Public - California Alameda County Commission # 2352343 My Comm. Expires Mar 19, 2025 |
| Cianaturo | Shalan | DAN | /Soal\ | |

Filed and Recorded Official Public Records Bobbie Koepp, County Clerk Comal County, Texas 07/31/2024 11:56:42 AM LAURA 3 Pages(s) 202406022845





DAVID WINTERS SEPTICS, LLC PO BOX 195 SPRING BRANCH, TX 78070 830-935-2477 OFFICE 830-935-2477 FAX wintersseptics@gvtc.com

Routine Maintenance and Inspection Agreement

| This Work-for-Hire Agreement (hereafter referred to as this "Agreement") is ent | ered into, by, and between |
|------------------------------------------------------------------------------------|--------------------------------------------------|
| WENTWORTH STUART II TRUST & MEURER LIVING TRUST (referred to as "Client") ar | nd David Winters Septic's, LLC, Inc. |
| (hereafter referred to as "Contractor") located at 1188 Blueridge Dr. | Date beginning on Issue Date of |
| and contract ending 2 years from Issue Date of License to Operate | License to Operate |
| By this agreement the Contractor agrees to render professional service, as describ | bed herein, and the Client agrees to fulfill the |
| terms of this Agreement as described herein. | |

This agreement will provide for all required inspections, testing, and service for your Aerobic Treatment System. The policy will include the following:

- 1. Three (3) inspections per year/service calls (at least one every four months), for a total of six (6) over the two-year period, including inspection, adjustment, and servicing of the mechanical, electrical and other applicable component parts to ensure proper function. This includes inspecting control panel, air pumps, air filters, diffuser operation, and replacing or repairing any component not found to be functioning correctly. Any alarm situations affecting the proper function of the Aerobic process will be addressed within a 48-hour time frame. This contract does not include labor on warranty and non-warranty parts.
- 2. An effluent quality inspection consisting of a visual check of color, turbidity, scum overflow and examination for odors. A test for chlorine residual and pH will be taken and reported as necessary.
- 3 If any improper operation is observed, which cannot be corrected at the time of the service visit, you will be notified on your inspection report.
- 4. The Client is responsible for the chlorine tablets and/or liquid chlorine; they must be filled before or during the service visit.
- 5. Any additional visits, inspections or sample collection required by specific Municipalities, Water/River Authorities, and County Agencies the TCEQ or any other authorized regulatory agency in your jurisdiction will not be covered by this policy.

At the conclusion of the initial service policy, our company will make available, for purchase on an annual basis, a continuing service policy cover NORMAL inspection, maintenance and repair.

The Homeowners Manual must be strictly followed or warranties are subject invalidation. Pumping of sludge build up is not covered by this policy and will result in additional charges.

This agreement does not cover any labor or parts for items which must be replaced due to acts of God, i.e., lightning strikes, high winds, flooding, freezing.

This agreement DOES NOT COVER materials or parts which must be replaced due to misuse or abuse of the system. These include but are not limited to: Sewage flows exceeding the recommended daily hydraulic design capabilities, Disposal of Non-Biodegradable materials, such as chemicals, grease or oil, sanitary napkins, tampons, baby wipes, disposable diapers, Clogs in the line between the house and the tank.

This agreement DOES NOT COVER LABOR OR PARTS for out- of- warranty items.

Service calls made outside of the regular maintenance schedule are subject to a \$75.00 SERVICE CALL FEE due at the time of service.

Received Brandon Mark Olvera 11/13/2025 9:12:46 AM

ACCESS BY CONTRACTOR

The contractor or anyone authorized by the contractor may enter the property at reasonable times without prior notice for the purpose of service described above.

First 2 years

PAYMENT AGREEMENT

included with new

The client will pay compensation to the contractor for the services in the amount of <u>install</u>. This compensation shall be payable in one lump sum payment upon acceptance of this agreement. Payments not received within 30 days of the above described due date will be subject to a \$25.00 late penalty.

TERMINATION OF THIS AGREEMENT

Either party may terminate this agreement within 10 days of written notice in the event of substantial failure to perform in accordance with its terms by other party without fault of the terminating party. If this agreement is terminated, the contractor will immediately notify the appropriate health authority.

LIMIT OF LIABILTY

Permit #

The Contractor will not be liable for indirect, consequential, incidental or punitive damages, whether in contract or any other theory. In no event shall the Contractor's liability for direct damages exceed the price for the services described in this agreement.

| Client | Contractor |
|-------------------------------------------------|----------------------------------|
| WENTWORTH STUART II TRUST & MEURER LIVING TRUST | David Winters Septic's, LLC |
| Name | |
| 1188 Blueridge Dr. | 1550 OAK MEADOWS |
| Address | CANYON LAKE, TX 78133 |
| | 830-935-2477 |
| Canyon Lake, Texas (Lot 145 Canyon Lake Hills) | |
| City/State/Zip Code | |
| 925-203-0071 | Office 830-935-2477 |
| Phone | |
| Stuart@Qualityproduct.com | 0 1 111 |
| Email address | By: Deril Winte |
| 110-1-1 | |
| Station | Signature of Contractor |
| B. The Oan | orginature of Contractor |
| Signature of Client Leure | Maintenance Provider #-MP0001686 |

OSSF Soil & Site Evaluation

| Page 1 (Soil | & Site Eval | uation) | Date Performed: // | | | | |
|---------------------------------------------------------------|---------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------|--------------------------------------------|-------------------------------------------------------------------------------|--|--|
| Property Own | ner:WEN | ГWORTH STUART | | | | | |
| borings or dug pleast two feet be | IENTS: st two soil excava pits must be show elow the proposed | tions must be performed on the on the site drawing. For such disposal field excavation delentify any restrictive features | he site, at opposite ends ibsurface disposal, soil e pth. For surface disposa | valuations must be pal, the surface horizo | osal area. Locations of soil performed to a depth of at n must be evaluated. | | |
| Soil Boring | | | | | | | |
| Number: Depth (Feet) | Texture Class | Gravel Analysis (If Applicable) | Drainage (Mottles/ Water Table) | Restrictive Horizon | Observations | | |
| 1 FT. | | | | | | | |
| 2 FT. | | | | | | | |
| 3 FT. | | | | | | | |
| 4 FT. | | | | | | | |
| 5 FT. | | | | | | | |
| Soil Boring Number: Depth (Feet) | Texture Class | Gravel Analysis (If Applicable) | Drainage (Mottles/ Water Table) | Restrictive Horizon | Observations | | |
| 1 FT. | | | | | | | |
| 2 FT. | | | | | | | |
| 3 FT. | | | | | | | |
| 4 FT. | | | | | | | |
| 5 FT. | | | | | | | |
| Presence of u Presence of a Existing or proground Slope | roposed water e | zone | hin 150 feet) | | ☐ Yes ☐ No ☐ te to the best of my | | |
| (Signature o | of person perfo | orming evaluation) | (Date) | Registration N | Number and Type | | |

Preliminary Field Check For Drip Systems



DATE:8/26/24

INSPECTOR: Corey Allen

OBSERVATION: 2 probes at 8 inches







GW Septic Designs



On-Site Sewage Facility Application and Design

Prepared By:
Garrett R. Winters
Registered Professional Sanitarian
R.S# <u>5213</u>



Contact Information

Phone: (210) 854-2673

Email: Gwintersseptics@gmail.com



Owner/Site Location

Owner: WENTWORTH STUART

Address: 1188 BLUERIDGE DRCanyon Lake, TX 78133

Subdivision: CANYON LAKE HILLS 1

LOT: 145

LOT DESCRIPTION

The proposed method of wastewater treatment is aerobic treatment with Drip irrigation. The sizing of the OSSF was determined as specified in the Texas Commission on Environmental Quality (TCEQ) CHAPTER 285.33 (C)(2). Water saving devices are assumed for the septic system design. This site is not within the 100-Year flood plain (see site plan). Water to the property will be serviced by a public water supply. All parts of the system will maintain at least a 10' setback from all water lines and 5' from property lines.

System Summary

This design was performed in conformance with Chapter 285 of Texas Commission on Environmental Quality.

- 600gpd Aerobic DRIP treatment unit
- Manual 12hr control timer
- 20gpm submersible effluent pump
- SCH40 PVC Sewer line
- 1" purple PVC SCH40 supply/return manifold
- NETAFIM Arkal 100-micron disk filter
- Pressure Gauge
- 30 PSI pressure regulator Model PMR30MF
- Vacuum Breakers installed at the highest points of the drip field.
- Spin lock connectors to prevent kinking of tubing.
- Drip Tubing (Netafim Bioline)
- Visual and audio alarms monitoring high water and aerator failure placed in a noticeable location.

Wastewater Design Flow

Structure: Single Family Residence (1262sf)

of Bedrooms: 2

Wastewater Usage Rate: 180GPD

Application Rate: 0.2

Application Area Required: 900sf Actual Application Area: 1264sf

System Components

Pretreatment Tank: 500gal

Pump Tank: 800gal Aeration Tank: 600gpd

Pump: C1 20gpm submersible pump (Model no. 20C1-05P4-2W115 or equivalent)

Pump tank reserve minimum: 60gal

Potable Water Lines

Potable water lines must be at a minimum distance of 10 feet from OSSF components. If a water line is within 10 feet, it must be sleeved with 2" SCH40 PVC Pipe in order to provide equivalent protection of a 10' separation in compliance with TAC chapter 290, Subchapter D, Rules for Public Drinking Water Systems.







Electrical Components

All electrical wiring shall conform to the requirements of the National Electric Code (1999) or under any other standards approved by the executive director. Additionally, all external wiring shall be installed in approved, rigid, non-metallic gray code electrical conduit. The conduit shall be buried according to the requirements in the National Electric Code and terminated at a main circuit breaker panel or sub-panel. Connections shall be in approved junction boxes. All electrical components shall have an electrical disconnect within direct vision from the place where the electrical device is being serviced. Electrical disconnects must be weatherproof (approved for outdoor use) and have maintenance lockout provisions.

Installation

A 3" or 4" solid-wall SCH40 or SDR 26 PVC pipe with a minimum downward slope of 1/8 inch per foot will be installed between the tank and house. A 2-way cleanout must be included in the line between the house and tank. All piping from house-to-tank and tank-to-drain field must be bedded with class lb, II, or III soils containing less than 30% gravel. The bottom of the excavation for the tank shall be level and free of large rocks/debris, the tanks shall then be bedded with a 4"-6" layer of sand, sandy loam, 3/4 dust or pea gravel. All openings in the tank are to be sealed to prevent the escape of wastewater. For all OSSF's permitted on or after September 1, 2023, inspection and cleanout ports shall have risers over the port openings which extend to a minimum of two inches above grade. A secondary plug, cap, or other suitable restraint system shall be provided below the riser cap to prevent tank entry if the cap is unknowingly damaged or removed. A secondary plug, cap, or other suitable restraint system shall be provided below the riser cap to prevent tank entry if the cap is unknowingly damaged or removed. Risers must be fitted with removable watertight caps and protected against unauthorized intrusions. Acceptable protective measures include: a padlock and a cover that can be removed with tools.

LANDSCAPING

The native vegetation in the distribution area should consist of low-level shrubs, plains grass, bluestem, or Bermuda. The entire area of the drip disposal must be covered with a ground cover such as grass seed or sod prior to the final inspection. The placement of the drip tubing will be on soil that has been scarified. The location of an individual sewage system shall not be in a poorly drained or filled area, or in any area where seasonal flooding/seeping occurs, without prior written approval. Stormwater runoff should not be allowed to flow over the drip field or tanks. Berms, swales and/or rain gutters should be installed by the owner/contractor to minimize erosion and field saturation. If the slope in the drain field area is greater than 30% or is complex, the area is unsuitable for the disposal method, suitable fill shall be brought into the field area to meet this requirement. The drip field shall then either be seeded and covered with Curlex or sodded.

Maintenance Contract

For any OSSF with a pump, the installer shall provide the Designated Representative with proof of an executed two-year full-service maintenance contract as required by the TCEQ. The maintenance company will verify that the system is operating properly and that they will provide on-going maintenance of the installation. The initial contract will be for a minimum of 2 years. A maintenance contract will authorize the Maintenance Company to maintain and repair the system as needed. The owner must continuously maintain a signed written contract with a valid maintenance company and shall submit a copy of the contract to the permitting authority at least 30 days prior to the date service will cease.





Affidavit

Prior to issuance of a permit, a certified copy of an affidavit must be submitted to the County Clerk's office. The affidavit is a recorded file in reference to the real property deed on which the surface application is installed on the property. The permit issued to the previous owner of the property being transferred to the new owner in accordance with §285.20(5) of the TCEQ OSSF Rules. The permit will be issued in the name of the owner of the OSSF. Permits shall be transferred to the new owner automatically upon legal sale of the OSSF. The transfer of an OSSF permit under this section shall occur upon actual transfer of the property on which the OSSF is located unless the ownership of the OSSF has been severed from the property.

Proposed System

A 3- or 4-inch SCH-40 pipe discharges from the residence into an Aquaklear AKA600CA (600GPD) aerobic treatment plant containing a 500-gallon pretreatment tank and an 800-gallon pump chamber. A threaded union will be installed in the pump tank on the supply manifold to the drip field, and a pressure regulator will be installed on the supply manifold to maintain a pressure of 30 psi. The pump chamber contains a 0.5 HP Franklin C1-Series-20XC1-05P4-2W115 submersible well pump (or equivalent). Distribution is through a self-flushing 100-micron Arkal Disk filter then through a 1" SCH-40 manifold to a minimum of 1,264sf drip tubing field with Netifim Bioline drip lines approximately two feet apart with 0.61gph emitters set every two feet as per the attached schematic. A 1" SCH-40 return line is installed to periodically flush the system. Solids caught in the disk filter are flushed each cycle back to the Pre-Treatment tank. Vacuum breakers installed at the highest point on each manifold will prevent siphoning of effluent from higher to lower parts of the field. The field area shall be scarified and built up with 2" of Imported TYPE II OR TYPE III soil (Not Sand) and capped with 6." The drip field will then either be seeded and covered with Curlex or sodded.



The following design is intended to follow and meet the TCEQ 30 TAC 285 OSSF Regulations. The performance of this system cannot be guaranteed even though all provisions of 30 TAC 285 have been met or exceeded.





GW Designs Garrett R. Winters 1332 Mountain View DR, Canyon Lake TX (210) 854-2673

November 13th, 2025 <u>Comal County Engineers Office</u> 195 Jonas Dr. New Braunfels, TX 78132

RE- **Septic Design** 1188 Blueridge Dr. Canyon Lake, TX 78133

Brenda/Brandon

I am requesting a variance for a water line that is within 10ft of the OSSF drip field, and crossing supply/return lines. The variance is being requested due to lack of space on this particular lot, equivalent protection will be maintained by sleeving the water line with 2" SCH 40 PVC pipe where it is within 10' of the OSSF components. I hereby request a variance to chapter 285.91(10). In my professional opinion this variance will not pose a threat to the environment or public health.

Please feel free to contact me with any questions or concerns.

Sincerely,

Garrett R. Winters R.S #5213



FLOOD PLAIN: AFTER CAREFUL EXAMINATION AND STUDY OF AVAILABLE DATA (INCLUDING FEMA PANEL ZONE X (AREA OF MINIMAL FLOOD HAZARD) I HAVE DETERMINED, TO THE BEST OF MY ABILITY, THAT NEITHER THE HOUSE NOR THE SEPTIC IS LOCATED WITHIN THE 100 YEAR FLOOD PLAIN.

NOTE

AEROBIC TREATMENT UNIT AND THE

BURIED AT A DEPTH TO ALLOW FOR 12"

AEROBIC TREATMENT UNIT TO BE

OF SOIL BETWEEN TOP OF THE

BOTTOM THE DRIP TUBING

Brandon Mark Olvera 11/13/2025 9:26:22 AM

OSSF INFORMATION

- STRUCTURE: 1262SF
- BEDROOMS: 2
- DAILY WASTEFLOW: 180GPD
- TANK MANUFACTURER: AQUAKLEAR AKA600CA
- MINIMUM DRIP FIELD COVERAGE: 900SF
- ACTUAL COVERAGE AREA: 1264SF

NOTE: DRIP FIELD AREA TO BE SCARIFIED BEFORE PLACEMENT OF DRIP TUBING

5FT OSSF SETBACK TH1 \oplus 0 0 SETBACK **DECK** 5FT OSSF 1015 SINGLE FAMILY

RESIDENCE

TH₂

 \oplus

50'

BLUERIDGE DR.

5FT OSSF SETBACK (W)

2BR

DRIP FIELD LAYOUT

12 LINES @ 36FT 10 LINES @ 20FT 632LF 1264SF

SETBACK

OSSF

WATER LINE TO BE SLEEVED W/ SCH40 PIPE WHERE IT IS WITHIN 10' OF THE SUPPLY/RETURN MANIFOLD AND DRIP FIELD. SLEEVING THE WATER LINE WILL PROVIDE EQUIVALENT PROTECTION TO THE SETBACK REQUIREMENTS IN TAC285 CONCERNING WATER LINES.

_ 1FT POWER/ELEC. **EASEMENT**

1" VACUUM **BREAKERS**

DESCRIPTION

Revised 11/03/2025 8:29:46 AM

NOTE

· WATER LINE

WATER SERVICE METER

PREPARED BY: GARRETT R. WINTERS

R.S #5213

OWNER: WENTWORTH STUART

ADDRESS: 1188 BLUERIDGE DR

DWAY

Canyon Lake, TX 78133

SUBDIVISION: CANYON LAKE HILLS 1

LOT: 145

1FT POWER/ELEC. -

EASEMENT


SCALE:1"- 16'

DATE: 11/3/2025

NOTES

- ALL POTABLE WATER LINES SHALL BE A MINIMUM OF 10 FEET FROM ANY PART OF THE OSSF
- TANK SEWER PIPE MUST HAVE AT MINIMUM .25" FALL PER 1'
- USE 3" OR 4" SCH40 PIPE TO CONNECT STRUCTURE TO TANK
- VACUUM BREAKERS ARE TO BE PLACED AT THE HIGHEST POINT ON THE SUPPLY AND RETURN LINES
- NO VEHICLE TRAFFIC IS TO BE ON ANY PART OF THE DISPOSAL AREA
- SYSTEM SHALL INCLUDE AUDIO AND VISUAL ALARMS TO INDICATE HIGH WATER
- ALL PIPES SHALL BE SCHEDULE 40 PVC OR APPROVED EQUAL, UNLESS NOTED OTHERWISE. ALL JOINTS SHALL BE CLEANED WITH THE APPROPRIATE SOLVENT AND GLUED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATION
- ONLY GOOD QUALITY SANDY LOAM SHALL BE APPLIED OVER THE DISPOSAL FIELDS. CLAY LOAM IS UNACCEPTABLE AND WILL CAUSE SYSTEM FAILURE. SANDY LOAM SHALL BE DEFINED AS SHOWN IN TABLE VI (USDA SOIL TEXTURAL CLASSIFICATIONS) OF THE RULES AND REGULATIONS OF THE TCEQ. THE INSTALLER IS RESPONSIBLE FOR VERIFYING THE QUALITY OF EACH LOAD OF LOAM PLACED ON THE SYSTEM.
- STORM WATER (RAINFALL RUNOFF) SHOULD NOT BE ALLOWED TO FLOW OVER THE DISPOSAL FIELDS OR THE TANKS. DIVERSION BERMS, SWALES AND/OR RAIN GUTTERS SHOULD BE INSTALLED AS NECESSARY TO PREVENT SUCH RUNOFF
- THIS DISPOSAL SYSTEM HAS BEEN DESIGNED TO OPERATE PROPERLY AT SPECIFICATIONS NOTED IN THESE PLANS. ALTERATIONS TO THE SYSTEM BY THE OWNER, INCLUDING BUT NOT LIMITED TO LANDSCAPING, DRAINAGE, BUILDING AND/OR WATER USAGE, MAY CAUSE PREMATURE FAILURE AND SHALL BE THE SOLE RESPONSIBILITY OF THE OWNER THIS SITE PLAN IS EXPRESSLY INTENDED
- FOR ON-SITE SEWAGE FACILITY (OSSF) USE ONLY AND SHOULD NOT BE UTILIZED OR CONSTRUCTED FOR SURVEYING PURPOSES. ITS PURPOSE IS TO ACCURATELY REPRESENT THE LAYOUT AND DESIGN OF THE SEWAGE SYSTEM WITHIN THE SPECIFIED PROPERTY **BOUNDARIES FOR REGULATORY AND** OPERATIONAL COMPLIANCE






CROSS SECTION DETAIL OF DRIPFIELD **GARRETT R. WINTERS** Know what's below. 5213 Call before you dig. 2FT-12.5. **NETAFIM BIOLINE DRIP TUBING** ON 2FT SPACING CLASS II OR III SOIL TO BE USED FOR IMPORTED MATERIAL 6"-8" CAP MINIMUM 12" SOIL BELOW DRIP TUBING **NOTES** NATURAL GROUND **EACH LINE OF TUBING IS TO BE** (NATIVE SOIL TO BE SCARIFIED) **INSTALLED AS LEVEL AS POSSIBLE SPACED TWO FEET APART** MINIMUM 12" SOIL UNDER DRIP TUBING EXISTING OR IMPORTED. 6" TO 8" TO BE ADDED ABOVE DRIP TUBING ANY SOIL DEPTH MUST BE MEASURED **AFTER 100% COMPACTION** SEEDED EROSION CONTROL BLANKET OR SAND BACKED SOD IS REQUIRED TO COVER THE DRIP FIELD AREA **AFTER INSTALLATION** SCARIFICATION PRIOR TO BUILD UP NETAFIM™ OF THE DRIP FIELD IS CRUCIAL FOR **DRIP FIELD LONGEVITY** FIELD SHOULD BE COVERED AND HAVE A SLIGHT DOWNWARD SLOPE NATAFIM BIOLINE PRESSURE FROM CENTER TO PREVENT PONDING CLASS II OR III SOIL TO BE USED FOR IMPORTED MATERIAL COMPENSATING OF WATER ON DRIP FIELD 6"-8" DRIP TUBING (0.61GPH) W/ 24" CENTER TO CENTER EMITTER SPACING. MINIMUM 12" SOIL BELOW DRIP TUBING NATURAL GROUND (NATIVE SOIL TO BE SCARIFIED)





C1 SERIES FAMILY CURVE



FEATURES

- Supplied with a removable 5" base for secure and reliable mounting
- Bottom suction design
- Robust thermoplastic discharge head design resists breakage during installation and operation
- Standard backflow prevention through a built-in, but removable, check valve.
- Single shell housing design provides a compact unit while ensuring cool and quiet operation
- Hydraulic components molded from high quality engineered thermoplastics
- Optimized hydraulic design allows for increased performance and decreased power usage
- All metal components are made of high grade stainless steel for corrosion resistance
- Available with a high quality 115 V or 230 V, 1/2 hp motor
- Fluid flows of 10, 20, and 30 gpm, with a max shut-off pressure of over 100 psi
- Heavy-duty 300 V 10 foot SJ00W jacketed lead

APPLICATIONS

- Gray water pumping
- Filtered effluent service water pumping
- Water reclamation projects such as pumping from rain catchment basins
- Aeration and other foundation or pond applications
- Agriculture and livestock water pumping

ORDERING INFORMATION

| GPM | HP | Volts | Stage | Model No. | Order No. | Length (in) | Weight (lbs) |
|-----|-----|-------|-------|------------------|-----------|-------------|--------------|
| 10 | | 115 | 6 | 10C1-05P4-2W115 | 90301005 | 26 | 17 |
| 10 | | 230 | 6 | 10C1-05P4-2W230 | 90301010 | 26 | 17 |
| 20 | | 115 | 4 | 20C1-05P4-2W115 | 90302005 | 25 | 16 |
| 20 | 1/2 | 230 | 4 | 20C1-05P4-2W230 | 90302010 | 25 | 16 |
| 20X | 1/2 | 115 | 5 | 20XC1-05P4-2W115 | 90302015 | 26 | 17 |
| 201 | | 230 | 5 | 20XC1-05P4-2W230 | 90302020 | 26 | 17 |
| 30 | | 115 | 3 | 30C1-05P4-2W115 | 90303005 | 25 | 16 |
| 30 | | 230 | 3 | 30C1-05P4-2W230 | 90303010 | 25 | 16 |

NOTE: All units have 10 foot long SJ00W leads





BIOLINE® DRIPLINE

THE WORLD'S MOST ADVANCED CONTINUOUS SELF-CLEANING, PRESSURE COMPENSATING DRIPLINE SPECIFICALLY DESIGNED FOR WASTEWATER

CROSS SECTION OF BIOLINE DRIPLINE

Bioline dripper inlets are positioned in the center of flow where water is the cleanest





PRODUCT ADVANTAGES

- Pressure compensation all drippers deliver equal flow, even on sloped or rolling terrain.
- Unique flow path Turbonet technology provides more control of water and a high resistance to clogging.
- Continuous self-flushing dripper design flushes debris, as it is detected - throughout operation, not just at the beginning or end of a cycle. Ensures uninterrupted dripper operation.
- · Single hole dripper outlet from tubing:
 - Better protection against root intrusion
 - Allows the dripline to be used in subsurface applications without need for chemical protection
- Drippers capture water flow from the center of the tubing ensures that only the cleanest flow enters the dripper.
- Built-in physical root barrier drippers are protected from root intrusion without the need for chemical protection. Water exits dripper in one location while exiting the tubing in another.
- Three dripper flow rates provides the broadest range of flow rates available. Allows the designer to match the dripline to any soil or slope condition.
- Bioline tubing is completely wrapped in purple easily identifying it for non-potable use, regardless of how the tubing is installed.
- Anti-bacterial-impregnated drippers prevents buildup of microbial slime.
- Can be used subsurface Bioline can be installed on-surface, under cover or subsurface.
- No special storage requirements does not degrade if stored outdoors.
- Techfilter compatible an optional level of protection, provides a limited lifetime warranty against root intrusion.

APPLICATIONS

- Typically installed following a treatment process
- Can be used with domestic septic tank effluent with proper design, filtration and operation
- Reuse applications including municipally treated effluent designated for irrigation and other disinfected and non-disinfected water sources.

SPECIFICATIONS

- Dripper flow rates: 0.4, 0.6 or 0.9 GPH
- Dripper spacings: 12", 18" or 24" dripper spacings and blank tubing
- Pressure compensation range: 7 to 58 psi (stainless steel clamps recommended above 50 psi)
- Maximum recommended system pressure: 50 psi
- Tubing diameter: 0.66" OD, 0.57" ID
- Tubing color: Purple color indicates nonnotable
- Coil lengths: 500' or 1,000' (Blank tubing in 250')
- · Recommended filtration: 120 mesh
- Bending radius: 7"
- UV resistant
- Tubing material: Linear low-density polyethylene

Additional spacing and pipe sizes available by special order. Please contact Netafim USA Customer Service for details.

BIOLINE DRIPLINE

MAXIMUM LENGTH OF A SINGLE LATERAL WITH 3.0 fps Flush velocity ADDITIONAL FLOW OF 2.3 GPM REQUIRED PER LATERAL TO ACHIEVE 3 fps DRIPPER SPACING DRIPPER FLOW RATE (GPH) | 0.4 GPH | 0.6 GPH | 0.9 GPH | 0.4 GPH | 0.6 GPH | 0.9 GPH | 0.4 GPH | 0.6 GPH | Flow per 100' (GPM / GPH) 1.53/92 0.77/46 0.67/40 1.02/61 0.44/26.67 0.68/41 1.02/61 0.51/31

Lateral lengths are based on flows allowing for a 3 fps flushing/scouring velocity

| MAX | MAXIMUM LENGTH OF A SINGLE LATERAL WITH 2.5 fps FLUSH VELOCITY | | | | | | | | | | |
|----------|--------------------------------------------------------------------|---------|---------|---------|------------|---------|---------|---------|---------|---------|--|
| ADD | ADDITIONAL FLOW OF 2.0 GPM REQUIRED PER LATERAL TO ACHIEVE 2.5 fps | | | | | | | | | | |
| I | DRIPPER SPACING 12" | | | | | 18" | | | 24" | | |
| DRIP | PER FLOW RATE (GPH) | 0.4 GPH | 0.6 GPH | 0.9 GPH | 0.4 GPH | 0.6 GPH | 0.9 GPH | 0.4 GPH | 0.6 GPH | 0.9 GPH | |
| щ | 15 | 128 | 115 | 100 | 172 | 155 | 136 | 205 | 187 | 165 | |
| SE | 25 | 183 | 161 | 137 | 248 | 220 | 188 | 301 | 268 | 231 | |
| PRESSURE | 35 | 228 | 198 | 166 | 310 | 272 | 229 | 379 | 333 | 283 | |
| INLET | 40 | 248 | 214 | 178 | 338 | 295 | 247 | 413 | 362 | 305 | |
| Z | 45 | 266 | 229 | 190 | 364 | 316 | 263 | 447 | 389 | 327 | |
| Flow | per 100' (GPM / GPH) | 0.67/40 | 1.02/61 | 1.53/92 | 0.44/26.67 | 0.68/41 | 1.02/61 | 0.34/20 | 0.51/31 | 0.77/46 | |

Lateral lengths are based on flows allowing for a 2.5 fps flushing/scouring velocity

| MAX | MAXIMUM LENGTH OF A SINGLE LATERAL WITH 2.0 fps FLUSH VELOCITY | | | | | | | | | | |
|----------|--------------------------------------------------------------------|---------|---------|---------|------------|---------|---------|---------|---------|---------|--|
| ADD | ADDITIONAL FLOW OF 1.6 GPM REQUIRED PER LATERAL TO ACHIEVE 2.0 fps | | | | | | | | | | |
| I | DRIPPER SPACING | | 12" | | | 18" | | | 24" | | |
| DRIP | PER FLOW RATE (GPH) | 0.4 GPH | 0.6 GPH | 0.9 GPH | 0.4 GPH | 0.6 GPH | 0.9 GPH | 0.4 GPH | 0.6 GPH | 0.9 GPH | |
| ш | 15 | 161 | 141 | 119 | 217 | 191 | 164 | 263 | 233 | 201 | |
| PRESSURE | 25 | 221 | 190 | 157 | 302 | 261 | 218 | 369 | 321 | 270 | |
| PRES | 35 | 269 | 229 | 187 | 370 | 316 | 260 | 455 | 391 | 324 | |
| INLET | 40 | 290 | 246 | 200 | 399 | 340 | 278 | 493 | 421 | 347 | |
| 2 | 45 | 310 | 261 | 212 | 427 | 362 | 296 | 527 | 449 | 369 | |
| Flow | per 100' (GPM / GPH) | 0.67/40 | 1.02/61 | 1.53/92 | 0.44/26.67 | 0.68/41 | 1.02/61 | 0.34/20 | 0.51/31 | 0.77/46 | |

Lateral lengths are based on flows allowing for a 2 fps flushing/scouring velocity

| MAX | MAXIMUM LENGTH OF A SINGLE LATERAL WITH 1.5 fps FLUSH VELOCITY | | | | | | | | | | |
|-----------------|--------------------------------------------------------------------|---------|---------|---------|------------|---------|---------|---------|---------|---------|--|
| ADD | ADDITIONAL FLOW OF 1.2 GPM REQUIRED PER LATERAL TO ACHIEVE 1.5 fps | | | | | | | | | | |
| DRIPPER SPACING | | | 12" | | | 18" | | | 24" | | |
| DRIP | PER FLOW RATE (GPH) | 0.4 GPH | 0.6 GPH | 0.9 GPH | 0.4 GPH | 0.6 GPH | 0.9 GPH | 0.4 GPH | 0.6 GPH | 0.9 GPH | |
| щ | 15 | 201 | 171 | 140 | 275 | 235 | 194 | 337 | 289 | 241 | |
| PRESSURE | 25 | 266 | 222 | 179 | 366 | 308 | 251 | 453 | 383 | 313 | |
| RES | 35 | 316 | 262 | 210 | 437 | 365 | 295 | 543 | 455 | 369 | |
| INLET | 40 | 337 | 280 | 223 | 469 | 391 | 313 | 583 | 487 | 393 | |
| 2 | 45 | 358 | 296 | 235 | 497 | 413 | 331 | 619 | 517 | 415 | |
| Flow | per 100' (GPM / GPH) | 0.67/40 | 1.02/61 | 1.53/92 | 0.44/26.67 | 0.68/41 | 1.02/61 | 0.34/20 | 0.51/31 | 0.77/46 | |

Lateral lengths are based on flows allowing for a 1.5 fps flushing/scouring velocity

| | MAXIMUM LENGTH OF A SINGLE LATERAL WITH 1.0 fps FLUSH VELOCITY ADDITIONAL FLOW OF 0.8 GPM REQUIRED PER LATERAL TO ACHIEVE 1.0 fps | | | | | | | | | |
|----------------------------------------------------------------------------------------------|------------------------------------------------------------------------------------------------------------------------------------|---------|---------|---------|---------|---------|---------|---------|---------|---------|
| - 1 | DRIPPER SPACING 12" 18" 24" | | | | | | | | | |
| DRIP | PER FLOW RATE (GPH) | 0.4 GPH | 0.6 GPH | 0.9 GPH | 0.4 GPH | 0.6 GPH | 0.9 GPH | 0.4 GPH | 0.6 GPH | 0.9 GPH |
| ш | 15 | 248 | 205 | 163 | 344 | 285 | 228 | 427 | 355 | 285 |
| PRESSURE | 25 | 315 | 258 | 203 | 440 | 361 | 286 | 549 | 453 | 359 |
| PRES | 35 | 367 | 299 | 234 | 513 | 419 | 331 | 643 | 527 | 417 |
| INLET | 40 | 389 | 316 | 248 | 545 | 445 | 350 | 683 | 559 | 441 |
| Z | 45 | 409 | 332 | 260 | 574 | 468 | 367 | 721 | 589 | 463 |
| Flow per 100' (GPM / GPH) 0.67/40 1.02/61 1.53/92 0.44/26.67 0.68/41 1.02/61 0.34/20 0.51/31 | | | | | | 0.77/46 | | | | |

Lateral lengths are based on flows allowing for a 1 fps flushing/scouring velocity

| MAX | MAXIMUM LENGTH OF A SINGLE LATERAL WITH 0.5 fps Flush Velocity | | | | | | | | | |
|-----------------------------|------------------------------------------------------------------------------------------------------|---------|----------|----------|----------|----------|---------|---------|---------|---------|
| ADD | ITIONAL FLOW OF 0.4 | GPM REC | QUIRED F | PER LATE | RAL TO A | CHIEVE 0 | .5 fps | | | |
| DRIPPER SPACING 12" 18" 24" | | | | | | | | | | |
| DRIP | PER FLOW RATE (GPH) | 0.4 GPH | 0.6 GPH | 0.9 GPH | 0.4 GPH | 0.6 GPH | 0.9 GPH | 0.4 GPH | 0.6 GPH | 0.9 GPH |
| ш | 15 | 301 | 242 | 188 | 422 | 341 | 265 | 531 | 429 | 335 |
| PRESSURE | 25 | 369 | 296 | 228 | 520 | 418 | 323 | 655 | 527 | 409 |
| PRES | 35 | 421 | 337 | 260 | 595 | 476 | 368 | 749 | 603 | 467 |
| INLET | 40 | 443 | 354 | 273 | 626 | 501 | 387 | 790 | 635 | 491 |
| 2 | 45 | 464 | 371 | 285 | 656 | 524 | 404 | 829 | 665 | 513 |
| Flow | Flow per 100' (GPM / GPH) 0.67/40 1.02/61 1.53/92 0.44/26.67 0.68/41 1.02/61 0.34/20 0.51/31 0.77/46 | | | | | | | | 0.77/46 | |

Lateral lengths are based on flows allowing for a 0.5 fps flushing/scouring velocity

Netafim recommends flushing velocities capable of breaking free any accumulated bioslimes and debris in the piping network.

- Notes: 1. Refer to local regulations for information on flushing velocities that may be written into codes.
 - 2. Netafim does not endorse a specific flushing velocity.
 - 3. Flushing velocities should be determined based on regulations, quality of effluent, and type of flushing control.
 - Using a flushing velocity less than 1 fps does not provide turbulent flow as defined by Reynolds Number.
 - Higher flushing velocities provide more aggressive flushing.

EXPLODED VIEW OF BIOLINE EMITTER

Large inlet filtration area (bottom of emitter) Chemical-resistant molded silicon diaphragm TurboNet wide flow path Emitter Outlet (top of emitter) Physical Barrier separates where water leaves the dripper from where it leaves the tubing. Emitter's Top View Top of emitter (turned over)


BIOLINE EMITTER OPERATION

Bioline® dripperline emitters are pressure compensating - delivering the water uniformly into the soil for further treatment or for reuse by the landscape. These unique emitters allow the tubing to be installed on flat topography or steep slopes.

Bioline emitters are protected against microbial slime. Each emitter is impregnated with an antimicrobial agent to resist biological build-up.

Netafim emitters are continuously self-cleaning during operation, not just at the beginning and end of a cycle. The result is dependable, clog-free operation, year after year.


DRIPPER FLOW RATE VS. PRESSURE



Between 0 and 7 psi, the dripper functions as a turbulent flow emitter, ensuring that the nominal design flow is not exceeded at system start-up.

| FLOW PER 100 FEET | | | | | | | |
|-------------------|-----------|--------|---------|---------|-----------------|------|--|
| DRIPPER | 0.4 GPH [| RIPPER | 0.6 GPH | DRIPPER | 0.9 GPH DRIPPER | | |
| SPACING | GPH | GPM | GPH | GPM | GPH | GPM | |
| 12" | 40.0 | 0.67 | 61.0 | 1.02 | 92.0 | 1.53 | |
| 18" | 26.7 | 0.44 | 41.0 | 0.68 | 61.0 | 1.02 | |
| 24" | 20.0 | 0.34 | 31.0 | 0.51 | 46.0 | 0.77 | |

SPECIFYING INFORMATION



BLANK Tubing Model Number: 250' = 08WRAM-250

| ORDERII | NG INFORI | MATION | |
|--------------|--------------------|----------------|---------------------------------|
| FLOW RATE | DRIPPER SPACING | COIL LENGTH | MODEL Number |
| 0.4 GPH | 12" | 1,000' 500' | 08WRAM.4-12V 08WRAM.4-12V500 |
| 0.4 GPH | 18" | 1,000' 500' | 08WRAM.4-18V 08WRAM.4-18V500 |
| 0.4 GPH | 24" | 1,000' 500' | 08WRAM.4-24V 08WRAM.4-24V500 |
| 0.6 GPH | 12" | 1,000' 500' | 08WRAM.6-12V 08WRAM.6-12V500 |
| 0.6 GPH | 18" | 1,000' 500' | 08WRAM.6-18V 08WRAM.6-18V500 |
| 0.6 GPH | 24" | 1,000' 500' | 08WRAM.6-24V 08WRAM.6-24V500 |
| 0.9 GPH | 12" | 1,000' 500' | 08WRAM.9-12V 08WRAM.9-12V500 |
| 0.9 GPH | 18" | 1,000' 500' | 08WRAM.9-18V 08WRAM.9-18V500 |
| 0.9 GPH | 24" | 1,000' 500' | 08WRAM.9-24V 08WRAM.9-24V500 |
| Blank Tubin | g 17mm | 250' | 08WRAM-250 |



1" SUPER/LONG MANUAL DISC FILTER

INSTALLATION, OPERATION & MAINTENANCE INSTRUCTIONS

FEATURES

- A "T' shaped reinforced plastic filter with two 1" male connections.
- Filter element consists of grooved discs, mounted on a spine, forming a cylindrical filter element. The discs are compressed together by a spring located at the bottom of the filter cover.
- · Screw-on filter cover.
- · Resistant to chemicals and liquid fertilizers.
- Available filtration grades: 040, 080, 120, 140 and 200.

| TECHNICAL DATA | |
|------------------------|-------------|
| FLOW RANGE | 10 - 35 GPM |
| MAXIMUM PRESSURE | 140 psi |
| FILTERING SURFACE AREA | 78 sq. in. |
| FILTERING VOLUME | 36 cu. in. |
| LENGTH | 13 13/32" |
| WIDTH | 6 7/32" |
| WEIGHT | 3.11 lbs. |
| DISTANCE BETWEEN ENDS | 6 7/32" |
| INLET/OUTLET DIAMETER | 1" Male |
| MAXIMUM TEMPERATURE | 158° F |
| pH | 5 - 11 |



| MESH/MICRON | | | | | | |
|-------------|--------|------------|--|--|--|--|
| MESH | MICRON | DISC COLOR | | | | |
| 040 | 400 | Blue | | | | |
| 080 | 200 | Yellow | | | | |
| 120 | 130 | Red | | | | |
| 140 | 115 | Black | | | | |
| 200 | 55 | Green | | | | |

INSTALLATION

- 1. Filter can be installed either vertically or horizontally.
- 2. Use Teflon tape on filter threads Do Not Use Pipe Dope.
- 3. Ensure correct inlet/outlet direction.
- 4. When connecting filter to pipe, do not overtighten.
- 5. Never use spanners for tighening the filter cover.


MAINTENANCE AND CLEANING


DISMANTLING

- 1. Ensure system is turned off and no pressure remains in the pipeline.
- 2. Unscrew cover from the filter body.
- 3. Pull out entire filter element.

CLEANING

- 1. Move tightening ring to end of spine and flush discs with pressurized water.
- 2. If discs are not clean after flushing with water:
 - a. If the discs have an accumulation of algae in the grooves, soak the discs and spine in a small bucket of Clorox bleach for one hour and then reflush with fresh water.
 - b. If the discs have an accumulation of iron in the grooves, soak the discs and spine in a small bucket of 10% Muriatic Acid for one hour and then reflush with fresh water.
 Muriatic Acid can be purchased at any pool supply store.







MAINTENANCE AND CLEANING

ASSEMBLY

- 1. Verify that spring is in place inside the filter cover.
- 2. Insert filter element and make sure it is seated correctly.
- 3. Replace cover.
- 4. Tighten filter cover securely by turning the fixing nut clockwise and do not overtighten.


WINTERIZATION

Drain all the water from the filter to avoid cracking due to freezing.

| PART | PARTS BREAKDOWN - 1" SUPER/LONG FIL | | | | | | |
|-------------|-------------------------------------|----------------------|-----------|--|--|--|--|
| KEY | MODEL NUMBER | DESCRIPTION | MATERIALS | | | | |
| 1 | SEE # 11 | GAUGE PORT NUT | R.PP | | | | |
| 2 | SEE # 11 | GAUGE PORT SEAL | EPDM | | | | |
| 3 | - | FILTER ADAPTER RING | R.PA | | | | |
| 4 | 25AP531140 | COVER O RING | NR | | | | |
| 5 | 25AP50440011 | COMPRESSION SPRING | SS | | | | |
| 6 | 25AP23113 | FILTER COVER | R.PA | | | | |
| 7 | - | 1/4" TAP (OPTIONAL) | BRASS | | | | |
| 8 | 25AP231131 | FIXING NUT | R.PA | | | | |
| 9 | 25AP131199 | FILTER WRENCH | R.PA | | | | |
| 10 | 25AP21121-*** | RING SET WITH SPINE | PP | | | | |
| 11 | 25AP25000101 | FILTER BODY COMPLETE | - | | | | |

Substitute *** for proper mesh size.

| MATERIALS KEY | | | | | | |
|---------------|--------------------------|--|--|--|--|--|
| CODE | MATERIAL | | | | | |
| SS | STAINLESS STEEL | | | | | |
| PP | POLYPROPYLENE | | | | | |
| NR | NITRILE RUBBER | | | | | |
| R.PP | REINFORCED POLYPROPYLENE | | | | | |
| R.PA | REINFORCED POLYAMIDE | | | | | |
| EPDM | ETH. PROPY. RUBBER | | | | | |





5470 E. Home Ave. Fresno, CA 93727 888.638.2346 • 559.453.6800 FAX 800.695.4753 www.netafimusa.com

PR-HF



The PR-HF (Pressure Regulator High Flow) is ideal for installations requiring higher flows of 10 to 32 gpm (2271 to 7268 L/hr), including solid-set sprinkler and low volume manifolds.

FEATURES

- Senninger regulators maintain a constant preset outlet pressure with varying inlet pressures, which alleviates pressure differences that can cause an applicator's area of coverage to change.
- Pressure tested, to ensure quality and performance
- Very low hysteresis and friction losses
- Can be installed above or below ground
- Two-year warranty on materials, workmanship and performance



BSPT MODELS ALSO AVAILABLE

| PR-HF DESIGN CRITERIA | Preset Operating Pressure | Maximum Inlet Pressure | Flov | w Range L/hr | Inlet Sizes | Outlet Sizes |
|-----------------------------|---------------------------------|------------------------------|---------|-----------------|-------------------------------------------------------------------------------|---------------------------------------------------------------------------------------------------|
| PR10 HF | 10 psi (0.69 bar) | 90 psi (6.20 bar) | 10 - 32 | 2271 - 7268 | 1 ¹ / ₄ " F NPT, 1 ¹ / ₄ " F BSPT | 1" F NPT, 11/4" F NPT, 1" F BSPT,11/4" F BSPT |
| PR15 HF | 15 psi (1.03 bar) | 95 psi (6.55 bar) | 10 - 32 | 2271 - 7268 | 11/4" F NPT, 11/4" F BSPT | 1" F NPT, 11/4" F NPT, 1" F BSPT,11/4" F BSPT |
| PR20 HF | 20 psi (1.38 bar) | 100 psi (6.89 bar) | 10 - 32 | 2271 - 7268 | 1 ¹ / ₄ " F NPT, 1 ¹ / ₄ " F BSPT | 1" F NPT, 1 ¹ / ₄ " F NPT, 1" F BSPT,1 ¹ / ₄ " F BSPT |
| PR25 HF | 25 psi (1.72 bar) | 105 psi (7.24 bar) | 10 - 32 | 2271 - 7268 | 11/4" F NPT, 11/4" F BSPT | 1" F NPT, 11/4" F NPT, 1" F BSPT,11/4" F BSPT |
| PR30 HF | 30 psi (2.07 bar) | 110 psi (7.58 bar) | 10 - 32 | 2271 - 7268 | 11/4" F NPT, 11/4" F BSPT | 1" F NPT, 11/4" F NPT, 1" F BSPT,11/4" F BSPT |
| PR40 HF | 40 psi (2.76 bar) | 120 psi (8.27 bar) | 10 - 32 | 2271 - 7268 | 11/4" F NPT, 11/4" F BSPT | 1" F NPT, 11/4" F NPT, 1" F BSPT,11/4" F BSPT |
| PR50 HF | 50 psi (3.45 bar) | 130 psi (8.96 bar) | 10 - 32 | 2271 - 7268 | 11/4" F NPT, 11/4" F BSPT | 1" F NPT, 11/4" F NPT, 1" F BSPT,11/4" F BSPT |


The pressure regulator shall maintain the predetermined operating pressure provided that the inlet pressure is at least 5 psi (0.34 bar) above the expected outlet pressure, but not exceeding the maximum inlet pressure as shown above.

CAUTION: Always install downstream from all shut-off valves. Recommended for outdoor use only. Not NSF certified.

IRREGULAR FIELD SHAPE LAYOUT

Triangular field with looping and varied positioning of flush manifolds:

- Used when site limitations dictate unequal dripperline length with respect to dispersal field length
- Loop the Bioline® to increase lateral length and reduce the number of connections
- Keep the Bioline laterals as close to the same length as possible to provide for an equal field flush
- The flush manifold may be located on the same or opposite side of the supply manifold
- As pictured, it may be necessary to make one or more distal end connections to the flush line on an opposing side in order to balance dripperline lateral lengths and to limit the number of connections



ArcGIS Web Map





195 David Jonas Dr, New Braunfels, Texas 78132 (830)608-2090

Address: 1188 BLUERIDGE DR

Legal Description: Canyon Lake Hills 1, LOT 145

Dear Property Owner & Agent,

Thank you for your submission. We have reviewed the planning materials for the referenced permit application, and unfortunately, they are insufficient. To proceed with processing this permit, we require the following:

119074.pdf Markup Summary 10-30-2025

Brandon Mark Olvera (5)



Subject: Group Page Label: 2

Checkmark: Unchecked Author: Brandon Mark Olvera Date: 10/30/2025 3:22:24 PM



The owner needs to resign and date the application.



Subject: Group Page Label: 3

Checkmark: Unchecked Author: Brandon Mark Olvera Date: 10/30/2025 3:46:23 PM



285.91(3) What is the purposed gallons per day for the property,



Subject: Group Page Label: 8

Checkmark: Unchecked Author: Brandon Mark Olvera Date: 10/30/2025 3:27:06 PM



285.7(d)(1)(F)

indicate the business physical address and telephone number for

the

maintenance provider.



Subject: Group Page Label: 16

Checkmark: Unchecked Author: Brandon Mark Olvera Date: 10/30/2025 3:38:38 PM



Wastewater design flow and site plan show a sq. ft. of absorption

area of 1264

Click on highlight to see site plan.

195 David Jonas Dr, New Braunfels, Texas 78132 (830)608-2090

Address: 1188 BLUERIDGE DR

Legal Description: Canyon Lake Hills 1, LOT 145

Dear Property Owner & Agent,

Thank you for your submission. We have reviewed the planning materials for the referenced permit application, and unfortunately, they are insufficient. To proceed with processing this permit, we require the following:



Subject: Group Page Label: 17

Checkmark: Unchecked Author: Brandon Mark Olvera Date: 10/30/2025 3:41:07 PM



Indicate the length of the Supply

and return line



OSSF DEVELOPMENT APPLICATION CHECKLIST

Staff will complete shaded items

119074

| | | | Date Receive | ed Initi | als | Permit Number |
|-------------------------------|----------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------------------|----------------|--------------|--------------------------------------|
| Instructions | | | | | | |
| Place a check mark r | next to all items that ap mpany the completed a | | do not apply, | place "N/A | .". This OSS | F Development Application |
| SSF Permit | | | | | | |
| Completed A | ition for P or A | - Contract of the Contract of | ruct an | te Se | Clon | cense to Operate |
| Site/Soil Eval | Com by a | ed Site Eval | ra F | sional | neer | |
| Planning Mate of a scaled des | of SSF as system s | red by the To | ules | SSF (| er 285. Pla | /laterials shall cor |
| Required Perm | See Attached F | | | | | |
| Copy of Record | led Deed | | | | | |
| Surface Applica | tion/Aerobic Treatment | t System | ito Primitiva (C | | | |
| Recorded | Certification of OSSF | Requiring Maintena | ance/Affidavit | to the Pub | lic | |
| Signed Ma | aintenance Contract wi | ith Effective Date a | s Issuance of | f License to | Operate | |
| | | | Margane Co | | | |
| | provided all information | | | | | and that this application |
| got chi | | | 7 | 1/26/2 | 7 | |
| Eljale | th Me | ver | 7 | /26/ | 24 | |
| Si | ignature of Applicant | $\begin{aligned} & (1-\epsilon)^{-1} = \sum_{i=1}^{n} (-1)^{i} \sum_{j=1}^{n} \frac{d_j^2 = \sum_{i=1}^{n} d_j^2}{d_j^2 = \sum_{i=1}^{n} d_i^2} \frac{d_j^2}{d_j^2} + \frac{d_j^2}{d_j$ | ng 1132 m Til Au | Za 100,00 31.0 | Date | |
| CC | OMPLETE APPLICATION Receipt No | ON | | | | APPLICATION Application Refeused) |

Revised: September 2019





ON-SITE SEWAGE FACILITY APPLICATION

195 DAVID JONAS DR NEW BRAUNFELS, TX 78132 (830) 608-2090 <u>WWW.CCEO.ORG</u>

| Date | | Permit Number11 | 9074 |
|---------------------------------------------------------------------------------------------------------------------------------|-----------------------------------|-----------------------------------|--------------------|
| . APPLICANT / AGENT INFORMATION WENTWORTH STUART II TRUST & MEURI | ER LIVING TRUST | | |
| Owner Name | Agent Name | David Winters Septics LLC | |
| Mailing Address 1187 Blueridge Dr. | Agent Address | P.O Box 195 | |
| City, Star , Zip Canyon Lake, TX 78133 | City, State, Zip | Spring Branch, TX 78070 | |
| Phote # 925-203-0071 | Phone # | 830-935-2477 | |
| Stuart@Qualityproduct.com | Email | Wintersseptics@gvtc.com | |
| DCATION | | | |
| u division Name (Lake Hills | | nit 145 | Block |
| u vey Name / Absti umber | | age | |
| d ress 1188 Blueri | Car | Sta Sta | Zip <u>78133</u> |
| YPE OF DEVELO | | | |
| Single Family Romatia | | | |
| Type of Constru | House | | |
| Number of Bedro 2 | | | |
| Indicate Sq Ft of rea 1264 | | | |
| Non-Single Family Residential | | | |
| (Planning materials must show adequate land area for | r doubling the required land need | ded for treatment units and disp | osal area) |
| | | | |
| Office, | | | |
| Restaurants, Lounges, Theaters - Indicate Numb | ner of Seats | | |
| Hotel, Motel, Hospital, Nursing Home - Indicate I | | The owner ne | eds to |
| Travel Trailer/RV Parks - Indicate Number of Spa | 시대 가지 그러지 않는 내가 있는 것은 없고 그렇게 다 | resign and da | te the |
| | | application. | |
| Miscellaneous | | | |
| 200,000 | | | |
| Estimated Cost of Construction: \$200,000 | (Structure Only) | | |
| Is any portion of the proposed OSSF located in the U | Inited States Army Corps of | Engineers (USACE) flowage | easement? |
| Yes No (If yes, owner must provide approval from | n USACE for proposed OSSF impro | vements within the USACE llowage | e easement) |
| Source of Water Public Private Well | Rainwater | | |
| SIGNATURE OF OWNER | | | |
| y signing this application, I certify that: | itt. d | o information and door not so | |
| The completed application and all additional information subfacts. I certify that I am the property owner or I possess the | | | |
| property. | | | |
| Authorization is hereby given to the permitting authority and site/soil evaluation and inspection of private sewage facilities. | s | | |
| understand that a permit of authorization to construct will n | ot be issued until the Floodplain | Administrator has performed th | ne reviews require |
| ey the Comal County Flood Damage Prevention Order affirmatively consent to the galine posting public re | my e-mail address associated | with mis permit application, as a | applicable. |
| Stit Well | 7/26/2 Date 1/26/2 | 24 | |
| Signature of Owner | Date | | Page 1 o |
| Elalet Meuros | 1/1/2 | 4 | Revised January 2 |



Signature of Designer

ON-SITE SEWAGE FACILITY APPLICATION

195 DAVID JONAS DR NEW BRAUNFELS, TX 78132 (830) 608-2090 WWW.CCEO.ORG

| Planning Materials & Site Evaluation as Required Completed By Garrett R. Winters R.S | | | | | | |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|---------------------------------------------------------------------------|---------------------------------------------------------------------------|--|--|--|--|
| System Description Aerobic System W/ Drip Application | | | | | | |
| Size of Septic System Required Based on Planning Materials | & Soil Evaluation | | | | | |
| Tank Size(s) (Gallons) 600gpd | Absorption/Application Area (Sq Ft)_ | 1264 | | | | |
| Gallons Per Day (As Per TCEQ Table III) (Sites generating more than 5000 gallons per day are required to obtain | ain a permit through TCEQ.) | | | | | |
| Is the property located over the Edwards Recharge Zone? (If yes, the plane of materials must be completed by a Registered Salls there are existing TCEQ approved WPAP for the property? (If yes, the R.S. or P.E. shall certify that the OSSF design complies we | Yes X No | 285.91(3) What is the purposed gain as per day for the property, | | | | |
| If there is no existing WPA es the production of that the Control of that the Control of the proposed Other in the proposed Other in the production of the proposed Other in the production of t | | Yes No it to Construct will not | | | | |
| If there is no existing CZP, does the proposed development act (If yes, the V.S. or P.E. shall certify that the OSSF design will comply issued for the proposed OSSF until the CZP has been approved by the state of the property within an incorporated city? | with all provisions of the proposed CZP. An appropriate regional office.) | | | | | |
| If yes, indicate the city: | | RETT R. WINTERS 5213 **EG/STERE S07/ONAL SANTAN 2.5 | | | | |
| By signing this application, I certify that: - The information provided above is true and correct to the best of - I affirmatively consent to the online posting/public release of my e | • | application, as applicable. | | | | |

7/15/2024

Date

DAVID WINTERS SEPTICS, LLC PO BOX 195 SPRING BRANCH, TX 78070 830-935-2477 OFFICE 830-935-2477 FAX

wintersseptics@gvtc.com

Routine Maintenance and Inspection Agreement

| This Work-for-Hire Agreement (hereafter referred to as this "Agreement") is entered | d into, by, and between |
|--------------------------------------------------------------------------------------|---------------------------------------------|
| WENTWORTH STUART II TRUST & MEURER LIVING TRUST (referred to as "Client") and I | David Winters Septic's, LLC, Inc. |
| (hereafter referred to as "Contractor") located at 1188 Blueridge Dr. | Date beginning on Issue Date of |
| and contract ending 2 years from Issue Date of License to Operate | License to Operate |
| By this agreement the Contractor agrees to render professional service, as described | herein and the Client agrees to fulfill the |
| to as of this Agreement as described herein. | |

This agreement will provide for all required inspections, testing, and service for your Aerobic Treatment System. The policy will include the following:

- 1. Three (3) inspections per year/service calls (at least one every four months), for a total of six (6) over the two-year period, including inspection adjustment, a wicing of the considerable size of the consumer proper function includes in a ground component and to be ming any component and to be ming any component and to be ming any component and to be ming and any component and to be any component any component and to be any component and to be any component and to be any component any component any component and to be any component any component and to be any component and component any compo
- 2. An effluent q insp consist a visual check c, tur scum ow and exam in for odors. A test for chlorine is all if will be and reported as arranged arranged arranged as a larger of the consist of the con
- 3 If any improper is observed, sannot be sed at the e of the ce visit see notified on your inspection
- 4. The Client is responsible for the chlorine tablets and/or liquid chlorine; they must be filled before or during the service visit
- 5. Any additional visits, inspections or sample collection required by specific Municipalities, Water/River Authorities, and Sounty Agencies the TCEO or any other authorized regulatory agency in your jurisdiction will not be covered by this policy

At the conclusion of the initial service policy, our company will make available, for purchase on an annual basis, a continuing service policy cover NORMAL inspection, maintenance and repair.

The Homeowners Manual must be strictly followed or warranties are subject invalidation. Pumping of sludge build up is not covered by this policy and will result in additional charges.

This agreement does not cover any labor or parts for items which must be replaced due to acts of God, i.e., lightning strikes, high winds, flooding, freezing.

This agreement DOES NOT COVER materials or parts which must be replaced due to misuse or abuse of the system. These include but are not limited to: Sewage flows exceeding the recommended daily hydraulic design capabilities, Disposal of Non-Biodegradable materials, such as chemicals, grease or oil, sanitary napkins, tampons, baby wipes, disposable diapers, Clogs in the line between the house and the tank.

This agreement DOES NOT COVER LABOR OR PARTS for out- of- warranty items.

Service calls made outside of the regular maintenance schedule are subject to a \$75.00 SERVICE CALL FEE due at the time of service.

ACCESS BY CONTRACTOR

The contractor or anyone authorized by the contractor may enter the property at reasonable times without prior notice for the purpose of service described above.

First 2 years

PAYMENT AGREEMENT

included with new

The client will pay compensation to the contractor for the services in the amount of <u>install</u>. This compensation shall be payable in one lump sum payment upon acceptance of this agreement. Payments not received within 30 days of the above described due date will be subject to a \$25.00 late penalty.

TERMINATION OF THIS AGREEMENT

Either carty may terminate this agreement within 10 days of written notice in the event of substantial failure to perform in accordance with its terms by other party without fault of the terminating party. If this agreement is terminated, the contractor will immediately notify the appropriate health authority.

IMIT OF LIABILTY

he Contractor will not be liable for indirect, consequential, incidental or punitive damages, whether in contract or any other neory. In no event with the Contractor will lity for discussions are exceed the form of the contract of the little of the

| ermit# | | | |
|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|--|---|--|
| Transmiss of the Contract of t | | , | |
| | | | |

he effective date of initia tenan eement shall be ate to ense to ate is

the business phy address and tele e number for he ance provider

llient

VENTWORTH STUART I

Jame

188 Blueridge Dr

ddress

evon Lake, Texas (Lot 145 Canvon Lake Hills)

City/Su. /Zin Code

925-203-0071

Phone

Stuart@Qualityproduct.com

Email address

Signature of Client

Office 830-935-2477


Fax 830-935-2477

3y. 22A

Signature of Contractor

Maintenance Provider #-MP0001686

GW Septic Designs



Contact Information

Phone: (210) 854-2673

Email: Gwintersseptics@gmail.com

1332 Mountain View Dr. Canyon Lake, TX 78133

Owner/Site Location

Owner: WENTWORTH STUART

Address: 1188 BLUERIDGE DRCanyon Lake, TX 78133

Subdivision: CANYON LAKE HILLS 1

LOT: 145

LOT DESCRIPTION

The proposed method of wastewater treatment is aerobic treatment with Drip irrigation. The sizing of the OSSI was determined as specified in the Texas Commission on Environmental Quality (TCEQ) CHAPTER 285.33 (C)(2). Water saving devices are assumed for the septic system design. This site is not within the 100-Year flood plain (see site plan). Water to the property will be serviced by a public water supply. All parts of the system will maintain at least a 10' setback from all water lines and 5' from property lines.

System mary

This desire a perform confusion with Company of the confusion of the confu

- 6 Aero (P tre
- M 12h rol tin
- 20 sul ble effl ump
- SC ver line
- 1" SCH40 sup urn mar
- NE kal 100-micro
- Pre auge
- 30 PSI pressure regulator Model PMR30MF
- Vacuum Breakers installed at the highest points of the drip field.
- Spin lock connectors to prevent kinking of tubing.
- Drip Tubing (Netafim Bioline)
 - Visual and audio alarms monitoring high water and aerator failure placed in a noticeable location.

Wastewater Design Flow

Structure: Single Family Residence (1264sf)

of Bedrooms: 2

Wastewater Usage Rate: 180GPD

Application Rate: 0.2

Application Area Required: 900sf Actual Application Area: 1264sf

System Components

Pretreatment Tank: 500gal

Pump Tank: 800gal Aeration Tank: 600gpd

Pump: C1 20gpm submersible pump (Model no. 20C1-05P4-2W115 or equivalent)

Pump tank reserve minimum: 60gal

Potable Water Lines

Potable water lines must be at a minimum distance of 10 feet from OSSF components. If a water line is within 10 feet, it must be sleeved with 2" SCH40 PVC Pipe in order to provide equivalent protection of a 10' separation in compliance with TAC chapter 290, Subchapter D, Rules for Public Drinking Water Systems.



Electrical Components

All electrical wiring shall conform to the requirements of the National Electric Code (1999) or under any other standards approved by the executive director. Additionally, all external wiring shall be installed in approved, rigid, non-metallic gray code electrical conduit. The conduit shall be buried according to the requirements in the National Electric Code and terminated at a main circuit breaker panel or sub-panel. Connections shall be in approved junction boxes. All electrical components shall have an electrical disconnect within direct vision from the place where the electrical device is being serviced. Electrical disconnects must be weatherproof (approved for outdoor use) and have maintenance lockout provisions.

dallation

A 3" or 4" solid-wall SCH40 or SDR 26 PVC pipe with a minimum downward slope of 1/8 inch per foot will be installed between the tank and house. A 2-way cleanout must be included in the line between the house and tank. All piping from house-to-tank and tank-to-drain field must be bedded with class Ib, II, or III soils containing less than 30% gravel. The bottom of the excavation for the tank shall be level and free of large rocks/debris, the tanks shall then be bedded with a 4"-6" layer of sand, sandy loam, 3/4 dust or pea gravel. All enemings in the tank are to be sealed to 10 to the escar astew. It is permitted for after the escar astew. It is permitted for a stripping in the tank are to be sealed to 10 to the escar astew. It is permitted for a stripping in the tank are to be sealed to 10 to the escar astew. It is permitted for a stripping in the tank are to be sealed to 10 to the escar astew. It is permitted for a stripping in the tank are to be sealed to 10 to the escar astew. It is permitted for a stripping in the tank are to be sealed to 10 to the escar astew. It is permitted for a stripping in the tank are to be sealed to 10 to the escar astew. It is permitted for a stripping in the tank are to be sealed to 10 to the escar astew. It is permitted for a stripping in the tank are to be escaled to 10 to the escar astew. It is permitted for a stripping in the tank are to be escaled to 10 to the escar astew. It is permitted for a stripping in the tank are to be escaled to 10 to the escar as the loam, 3/4 dust or pea gravel. All eneming is permitted for a stripping in the tank are to be escaled to 10 to the escar as the loam, 3/4 dust or pea gravel. All eneming is permitted for a stripping in the tank are to be escaled to 10 to the escar are to be escared for a stripping in the tank are to be escared

LANDSCAPING

The native vegetation in the distribution area should consist of low-level shrubs, plains grass, bluestem, or Bermuda. The entire area of the drip disposal must be covered with a ground cover such as grass seed or sod prior to the final inspection. The placement of the drip tubing will be on soil that has been scarified. The location of an additional sewage system shall not be in a poorly drained or filled area, or in any area where seasonal

drip field or tanks. Berms, swales and/or rain gutters should be installed by the owner/contractor to minimize erosion and field saturation. If the slope in the drain field area is greater than 30% or is complex, the area is unsuitable for the disposal method, suitable fill shall be brought into the field area to meet this requirement. The drip field shall then either be seeded and covered with Curlex or sodded.

Maintenance Contract

For any OSSF with a pump, the installer shall provide the Designated Representative with proof of an executed two-year full-service maintenance contract as required by the TCEQ. The maintenance company will verify that the system is operating properly and that they will provide on-going maintenance of the installation. The initial contract will be for a minimum of 2 years. A maintenance contract will authorize the Maintenance Company to maintain and repair the system as needed. The owner must continuously maintain a signed written contract with a valid maintenance company and shall submit a copy of the contract to the permitting authority at least 30 days prior to the date service will cease.



Affidavit

Prior to issuance of a permit, a certified copy of an affidavit must be submitted to the County Clerk's office. The

property. The permit issued to the previous owner of the property being transferred to the new owner in accordance with §285.20(5) of the TCEQ OSSF Rules. The permit will be issued in the name of the owner of the OSSF. Permits shall be transferred to the new owner automatically upon legal sale of the OSSF. The transfer of an OSSF permit under this section shall occur upon actual transfer of the property on which the OSSF is located unless the ownership of the OSSF has been severed from the property.

Proposed S n

A 3- or 4-inch 1 D pipe of ges for de residence in Aquilla AKAE (600GPD) aero eatme it cor gla 500-gallor eatme ink an 00-gallon planamber. A threaded union we in a in this plant that on the man to the gld, and a plane regulator will be installed the manife maintain a property of 30 the put tamber con to 5 HP Franklin C1-Seri W P4-2W11 thersible we' (or lent), bution is the a self-flushing 100-mid Disk filter the ghalf of manife to a manife with Netifim Bio lines approximate that with 0 the mid to a manife to a tubing field with Netifim Bio lines approximate that with 0 the mid to a manife to a graph to the disk filter are flushed each cycle back to the Pre-Treatment tank. Vacuum breakers installed at the highest point on each manifold will prevent siphoning of effluent from higher to lower parts of the field. The field area shall be scarified and built up with 2" of Imported TYPE II OR TYPE III soil (Not Sand) and capped with 1." The drip field will be either be seeded and covered with Curlex or sodded.

Wastewater design flow and site plan show a sq. ft. of absorption area of 1264 Click on highlight to see site plan.




The following design is intended to follow and meet the TCEQ 30 TAC 285 OSSF Regulations. The performance of this system cannot be guaranteed even though all provisions of 30 TAC 285 have been met or exceeded.

FLOOD PLAIN: AFTER CAREFUL EXAMINATION AND STUDY OF AVAILABLE DATA (INCLUDING FEMA PANEL ZONE X (AREA OF MINIMAL FLOOD HAZARD) I HAVE DETERMINED, TO THE BEST OF MY ABILITY, THAT NEITHER THE HOUSE NOR THE SEPTIC IS LOCATED WITHIN THE 100 YEAR FLOOD PLAIN.

NOTE: DRIP FIELD AREA TO BE SCARIFIED BEFORE PLACEMENT OF DRIP TUBING

NOTE

AEROBIC TREATMENT UNIT TO BE BURIED AT A DEPTH TO ALLOW FOR 12" OF SOIL BETWEEN TOP OF THE AEROBIC TREATMENT UNIT AND THE **BOTTOM THE DRIP TUBING**



SUBDIVISION: CANYON LAKE HILLS 1

LOT: 145

SCALE:1"- 16'

DATE: 7/15/2024

OSSF INFORMATION

- STRUCTURE: 1262SF
- BEDROOMS: 2
- DAILY WASTEFLOW: 180GPD
- TANK MANUFACTURER: AQUAKLEAR AKA600CA
- MINIMUM DRIP FIELD COVERAGE: 900SF
- ACTUAL COVERAGE AREA: 1264SF

NOTES

- ALL POTABLE WATER LINES SHALL BE A MINIMUM OF 10 FEET FROM ANY PART OF THE OSSF
- TANK SEWER PIPE MUST HAVE AT MINIMUM .25" FALL PER 1'
- USE 3" OR 4" SCH40 PIPE TO CONNECT STRUCTURE TO TANK
- VACUUM BREAKERS ARE TO BE PLACED AT THE HIGHEST POINT ON THE SUPPLY AND **RETURN LINES**
- NO VEHICLE TRAFFIC IS TO BE ON ANY PART OF THE DISPOSAL AREA
- SYSTEM SHALL INCLUDE AUDIO AND VISUAL ALARMS TO INDICATE HIGH WATER
- ALL PIPES SHALL BE SCHEDULE 40 PVC OR APPROVED EQUAL, UNLESS NOTED OTHERWISE. ALL JOINTS SHALL BE CLEANED WITH THE APPROPRIATE SOLVENT AND GLUED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATION
- ONLY GOOD QUALITY SANDY LOAM SHALL BE APPLIED OVER THE DISPOSAL FIELDS. CLAY LOAM IS UNACCEPTABLE AND WILL CAUSE SYSTEM FAILURE. SANDY LOAM SHALL BE DEFINED AS SHOWN IN TABLE VI (USDA SOIL TEXTURAL CLASSIFICATIONS) OF THE RULES AND REGULATIONS OF THE TCEQ. THE INSTALLER IS RESPONSIBLE FOR VERIFYING THE QUALITY OF EACH LOAD OF LOAM PLACED ON THE SYSTEM.
- STORM WATER (RAINFALL RUNOFF) SHOULD NOT BE ALLOWED TO FLOW OVER THE DISPOSAL FIELDS OR THE TANKS. DIVERSION BERMS, SWALES AND/OR RAIN GUTTERS SHOULD BE INSTALLED AS NECESSARY TO PREVENT SUCH RUNOFF.
- THIS DISPOSAL SYSTEM HAS BEEN DESIGNED TO OPERATE PROPERLY AT SPECIFICATIONS NOTED IN THESE PLANS. ALTERATIONS TO THE SYSTEM BY THE OWNER, INCLUDING BUT NOT LIMITED TO LANDSCAPING, DRAINAGE, BUILDING AND/OR WATER USAGE, MAY CAUSE PREMATURE FAILURE AND SHALL BE THE SOLE RESPONSIBILITY OF THE OWNER
- THIS SITE PLAN IS EXPRESSLY INTENDED FOR ON-SITE SEWAGE FACILITY (OSSF) USE ONLY AND SHOULD NOT BE UTILIZED OR CONSTRUCTED FOR SURVEYING PURPOSES. ITS PURPOSE IS TO ACCURATELY REPRESENT THE LAYOUT AND DESIGN OF THE SEWAGE SYSTEM WITHIN THE SPECIFIED PROPERTY **BOUNDARIES FOR REGULATORY AND** OPERATIONAL COMPLIANCE



PREPARED BY: GARRETT R. WINTERS

R.S #5213

OWNER: WENTWORTH STUART

ADDRESS: 1188 BLUERIDGE DR

Canyon Lake, TX 78133

195 David Jonas Dr, New Braunfels, Texas 78132 (830)608-2090

| Address: | | | |
|--------------------|------|------|--|
| | | | |
| Legal Description: | | | |

Dear Property Owner & Agent,

Thank you for your submission. We have reviewed the planning materials for the referenced permit application, and unfortunately, they are insufficient. To proceed with processing this permit, we require the following:

119074.pdf Markup Summary 11-13-2025

Group (1)



Subject: Group

Page Label: Water Line Variance Checkmark: Unchecked Author: Brandon Mark Olvera Date: 11/13/2025 9:22:07 AM



I cannot request a variance to 290.44(e)(8). If TAC 290

requirements cannot be met, then it will be a variance to 285.91(10).

Line (1)



Subject: Line

Page Label: Water Line Variance Checkmark: Unchecked Author: Brandon Mark Olvera Date: 11/13/2025 9:28:31 AM



The variance should also include the crossing of sewer pipes and

waterlines.



GW Designs Garrett R. Winters

(210) 854-2673

November 23, 2025
Comal County Engineers Office
195 Jonas Dr.
New Braunfels, TX 78132

RE- **Septic Design** 1188 Blueridge Dr. Canyon Lake, TX 78133 The variance should also include the crossing of sewer pipes and waterlines.

⊿renda/Brandon

l am requesting a variance for a water line that is within 10ft of the OSSF drip field, and supply/return lines. The variance is being requested due to lack of space on this particular lot, equivalent protection will be maintained by sleeving the water line with 2" SCH 40 PVC pipe where it is a fin 10' of the SF company of the second state of the space of the second state of the seco

Please feel to cor any question cor s

Sincerely,

Garrett R. Winters R.S #5213

to 290.44(e)(8). If TAC 2.0

met, then it will be a variance to 285.91(10).



NOTICE OF CONFIDENTIALITY RIGHTS: IF YOU ARE A NATURAL PERSON, YOU MAY REMOVE OR STRIKE ANY OR ALL OF THE FOLLOWING INFORMATION FROM ANY INSTRUMENT THAT TRANSFERS AN INTEREST IN REAL PROPERTY BEFORE IT IS FILED FOR RECORD IN THE PUBLIC RECORDS: YOUR SOCIAL SECURITY NUMBER OR YOUR DRIVER'S LICENSE NUMBER.

CORRECTION SPECIAL WARRANTY DEED

Date:

July 19, 2023

Grantor:

STUART WENTWORTH, A SINGLE PERSON

Grantor's Mailing Address:

1187 Blueridge Dr.

Canyon Lake, Texas 78133

Grantee:

STUART H. WENTWORTH, TRUSTEE, OR HIS SUCCESSORS IN INTEREST, OF THE STUART H. WENTWORTH TRUST DATED MAY 2, 2016, AND ANY AMENDMENTS THERETO

Grantee's Mailing Address:

1187 Blueridge Dr.

Canyon Lake, Texas 78133

Consideration:

TEN and NO/100 DOLLARS (\$10.00) and other good and valuable consideration, the receipt of which is hereby acknowledged.

Property (including any improvements):

An undivided ½ interest in Lots 114R, 116, 117, 144, 145, and 146, Canyon Lake Hills Unit 1, according to the map or plat recorded in Volume 2, Page 17, Comal County Texas, Map and Plat Records.

THIS CORRECTION SPECIAL WARRANTY DEED IS EXECUTED AND DELIVERED IN LIEU AND SUBSTITUTION OF A SPECIAL WARRANTY DEED DATED JULY 14, 2023, RECORDED IN DOCUMENT NUMBER 202306022652 ON JULY 18, 2023, AND IS IN CORRECTION OF AN ERROR IN THE NAME OF THE GRANTEE, STUART H. WENTWORTH, TRUSTEE, OR HIS SUCCESSORS IN INTEREST, OF THE STUART H. WENTWORTH TRUST DATED MAY 2, 2016, AND ANY AMENDMENTS THERETO, OF THE PREVIOUSLY FILED SPECIAL WARRANTY DEED. THIS INSTRUMENT IS MADE BY GRANTOR IN ORDER TO CORRECT SAID MISTAKE AND IN ALL OTHER RESPECTS CONFIRMING

SAID FORMER SPECIAL WARRANTY DEED.

Reservations from Conveyance:

None

Exceptions to Conveyance and Warranty:

Validly existing easements, rights-of-way, and prescriptive rights, whether of record or not; all presently recorded and validly existing instruments, other than conveyances of the surface fee estate, that affect the Property; and taxes for 2023, which Grantee assumes and agrees to pay, and subsequent assessments for that and prior years due to change in land usage, ownership, or both, the payment of which Grantee assumes.

Grantor warrants that Grantor is lawfully seized of good and indefeasible title to the Property and has the right to convey title to the Property subject to any Reservations or Exceptions from Conveyance contained herein.

Grantor, for the Consideration and subject to the Reservations from Conveyance and the Exceptions to Conveyance and Warranty, grants, gives, and conveys to Grantee the Property, together with all and singular the rights and appurtenances thereto in any way belonging, to have and to hold it to Grantee and Grantee's heirs, successors, and assigns forever. Grantor binds Grantor and Grantor's heirs and successors to warrant and forever defend all and singular the Property to Grantee and Grantee's heirs, successors, and assigns against every person whomsoever lawfully claiming or to claim the same or any part thereof when the claim is by, through, or under Grantor but not otherwise, except as to the Reservations from Conveyance and the Exceptions to Conveyance and Warranty.

GRANTEE IS TAKING THE PROPERTY IN AN ARM'S-LENGTH AGREEMENT BETWEEN THE PARTIES. THE CONSIDERATION WAS BARGAINED ON THE BASIS OF AN "AS IS, WHERE IS" TRANSACTION AND REFLECTS THE AGREEMENT OF THE PARTIES THAT THERE ARE NO REPRESENTATIONS OR EXPRESS OR IMPLIED WARRANTIES. GRANTEE HAS NOT RELIED ON ANY INFORMATION OTHER THAN GRANTEE'S INSPECTION.

When the context requires, singular nouns and pronouns include the plural.

This instrument has been prepared based upon information provided by the parties and no independent title search has been made.

GRANTOR:

STUART WENTWORTH, a single person

STATE OF TEXAS

COUNTY OF COMAL

This instrument was acknowledged before me on July 19, 2023, by Stuart Wentworth in the capacity stated above.

CARRIE AULBAUGH Notary Public, State of Texas Comm. Expires 08-27-2025 Notary ID 1829285

Notary Public, State of Texas


My commission expires:

AFTER RECORDING RETURN TO:

DAVIDEK LAW FIRM, PLLC 228 S. Seguin Avenue New Braunfels, Texas, 78130 Telephone: (830) 515-5854

PREPARED IN THE OFFICE OF:

DAVIDEK LAW FIRM, PLLC 228 S. Seguin Avenue New Braunfels, Texas, 78130 Telephone: (830) 515-5854



Filed and Recorded Official Public Records Bobbie Koepp, County Clerk Comal County, Texas 07/19/2023 11:14:02 AM TERRI 3 Pages(s)



NOTICE OF CONFIDENTIALITY RIGHTS: IF YOU ARE A NATURAL PERSON, YOU MAY REMOVE OR STRIKE ANY OR ALL OF THE FOLLOWING INFORMATION FROM ANY INSTRUMENT THAT TRANSFERS AN INTEREST IN REAL PROPERTY BEFORE IT IS FILED FOR RECORD IN THE PUBLIC RECORDS: YOUR SOCIAL SECURITY NUMBER OR YOUR DRIVER'S LICENSE NUMBER.

Special Warranty Deed

Date:

July 14, 2023

Grantor:

ELIZABETH MEURER, A SINGLE PERSON

Grantor's Mailing Address:

1187 Blueridge Dr.

Canyon Lake, Texas 78133

Grantee:

ELIZABETH J. MEURER, TRUSTEE, OR HER SUCCESSORS IN INTEREST,

OF THE MEURER LIVING TRUST DATED JULY 14, 2023, AND ANY

AMENDMENTS THERETO

Grantee's Mailing Address:

1187 Blueridge Dr.

Canyon Lake, Texas 78133

Consideration:

TEN and NO/100 DOLLARS (\$10.00) and other good and valuable consideration, the receipt of which is hereby acknowledged.

Property (including any improvements):

An undivided ½ interest in Lots 114R, 116, 117, 144, 145, and 146, Canyon Lake Hills Unit 1, according to the map or plat recorded in Volume 2, Page 17, Comal County Texas, Map and Plat Records.

Reservations from Conveyance:

None

Exceptions to Conveyance and Warranty:

Validly existing easements, rights-of-way, and prescriptive rights, whether of record or not; all presently recorded and validly existing instruments, other than conveyances of the surface fee estate, that affect the Property; and taxes for 2023, which Grantee assumes and agrees to pay,

and subsequent assessments for that and prior years due to change in land usage, ownership, or both, the payment of which Grantee assumes.

Grantor warrants that Grantor is lawfully seized of good and indefeasible title to the Property and has the right to convey title to the Property subject to any Reservations or Exceptions from Conveyance contained herein.

Grantor, for the Consideration and subject to the Reservations from Conveyance and the Exceptions to Conveyance and Warranty, grants, gives, and conveys to Grantee the Property, together with all and singular the rights and appurtenances thereto in any way belonging, to have and to hold it to Grantee and Grantee's heirs, successors, and assigns forever. Grantor binds Grantor and Grantor's heirs and successors to warrant and forever defend all and singular the Property to Grantee and Grantee's heirs, successors, and assigns against every person whomsoever lawfully claiming or to claim the same or any part thereof when the claim is by, through, or under Grantor but not otherwise, except as to the Reservations from Conveyance and the Exceptions to Conveyance and Warranty.

GRANTEE IS TAKING THE PROPERTY IN AN ARM'S-LENGTH AGREEMENT BETWEEN THE PARTIES. THE CONSIDERATION WAS BARGAINED ON THE BASIS OF AN "AS IS, WHERE IS" TRANSACTION AND REFLECTS THE AGREEMENT OF THE PARTIES THAT THERE ARE NO REPRESENTATIONS OR EXPRESS OR IMPLIED WARRANTIES. GRANTEE HAS NOT RELIED ON ANY INFORMATION OTHER THAN GRANTEE'S INSPECTION.

When the context requires, singular nouns and pronouns include the plural.

This instrument has been prepared based upon information provided by the parties and no independent title search has been made.

GRANTOR:

ELIZABETH MEURER, a single person

STATE OF TEXAS

COUNTY OF COMAL

)

This instrument was acknowledged before me on July 14, 2023, by Elizabeth Meurer in the capacity stated above.

ROBERT S. HARRISON
Notary Public, State of Texas
Comm. Expires 11-04-2025
Notary ID 133430606

Notary Public, State of Texas My commission expires: /

PREPARED IN THE OFFICE OF:

DAVIDEK LAW FIRM, PLLC 228 S. Seguin Avenue New Braunfels, Texas, 78130 Telephone: (830) 515-5854

AFTER RECORDING RETURN TO:

DAVIDEK LAW FIRM, PLLC 228 S. Seguin Avenue New Braunfels, Texas, 78130 Telephone: (830) 515-5854

> Filed and Recorded Official Public Records Bobbie Koepp, County Clerk Comal County, Texas 07/18/2023 12:21:52 PM LAURA 3 Pages(s) 202306022653

